



# **ACTION CIVIL ENGINEERS, PLLC**

*Firm Registration No. F-16376*

## **ADDENDUM NO. 1**

**Addendum Issued: February 4, 2015**

Re-bid Cheek Phase IV (IFB 14-055 JW)

### **Re-Bid Cheek Community Sewer Improvements Grinder Pumps Installation – Cheek Phase IV Jefferson County, Texas**

Re-bid Cheek Phase IV (IFB 14-055 JW)

TXCDBG Contract No. 713520 | ACE Job No. 114-18

The following information is offered for clarification or modification to the project information you now hold.

#### **1. BID PROPOSAL**

(a) Replace **Bid Proposal Pages 84-85** with revised **Bid Proposal Pages 84-85** attached.

**Clarification:** Quantities for 4" PVC has been added as a bid item No.

#### **2. BID OPENING**

The bid opening scheduled for February 10, 2015 will now take place in the **ENGINEERING CONFERENCE ROOM**, 5<sup>th</sup> floor of the Old Courthouse.

**Received**

**Date:** \_\_\_\_\_

**Acknowledged:** \_\_\_\_\_

***The changes listed above will be considered part of the Bid Package. Bidders are advised that each Addendum issued must be recognized by signature and a copy of all addenda must be submitted with Bid.***

**Bid Proposal**  
**ADDENDUM NO. 1**  
**Re-Bid Cheek Community Sewer Improvements Grinder Pumps Installation**  
**Cheek Phase IV Jefferson County, Texas**  
**Jefferson County, Texas**  
**TXCDBG Contract No. 713520|ACE Job No. 114-18**

NO.	ITEM	UNIT	QTY	UNIT PRICE BID WRITTEN IN WORDS		UNIT PRICE WRITTEN IN FIGURES		TOTAL PRICE BID WRITTEN IN FIGURES	
				DOLLARS	CENTS	DOLLARS	CENTS	DOLLARS	CENTS
1	FURNISH & INSTALL LPSS GRINDER PUMP STATION INCLUDING PUMP, FIBERGLASS TANK, CONTROLS & HOUSING INCLUDING ELECTRICAL INSTALLATION , AND 4" SEWER CONNECTION FROM HOUSE, COMPLETE IN PLACE PER SUMMARY OF WORK	EA.	8						
2	FURNISH & INSTALL LPSS GRINDER PUMP STATION INCLUDING <u>(PUMP,FIBERGLASS TANK, CONTROLS - FURNISHED BY JEFFERSON COUNTY)</u> & HOUSING INCLUDING ELECTRICAL INSTALLATION , AND 4" SEWER CONNECTION FROM HOUSE, COMPLETE IN PLACE PER SUMMARY OF WORK.	EA.	5						
3	ABANDON EXISTING SEPTIC TANK	EA.	13						
4	1 1/4" HDPE SDR-11 SANITARY SEWER SERVICE LINE, COMPLETE IN PLACE, FROM VALVE BOX TO GRINDER UNIT	LF	1,900						
5	FURNISH & INSTALL 4" PVC FOR ADDITIONAL LINES WHEN AUTHORIZED BY THE ENGINEER.	LF	100						
								<b>TOTAL</b>	
	<b>STATEMENT FOR SEPARATED CONTRACT COMPLIANCE:</b>								
	<b>NON-CONSUMABLE MATERIALS AND EQUIPMENT .....</b>								\$
	<b>SKILLED LABOR, MATERIALS, EQUIPMENT AND TOOLS .....</b>								\$
								<b>TOTAL</b>	\$

The undersigned agrees to commence work within ten (10) days after the date of written notice to commence work and to substantially complete the work on which he has bid within (\_\_\_\_) calendar days as provided in the General Conditions of the Agreement. Enclosed herewith is a cashier's check, certified check, or bid bond in the sum of 5% of the greatest amount bid which it is agreed shall be collected and retained by the **OWNER** as liquidating damages in the event this proposal is accepted by the **OWNER** within sixty (60) days after the date advertised for the reception of bids and the undersigned fails to execute the contract and the required bond with the **OWNER**, under the conditions hereof, within ten (10) days after the date said proposal is accepted, otherwise said check or bond shall be returned to the undersigned upon demand.

CONTRACTOR: \_\_\_\_\_ ADDRESS: \_\_\_\_\_ Phone: \_\_\_\_\_  
 BY: \_\_\_\_\_ DATE: \_\_\_\_\_

**Alternate Bid Proposal**  
**ADDENDUM NO. 1**  
**Re-Bid Cheek Community Sewer Improvements Grinder Pumps Installation**  
**Cheek Phase IV Jefferson County, Texas**  
**Jefferson County, Texas**  
**TXCDBG Contract No. 713520|ACE Job No. 114-18**

NO.	ITEM	UNIT	QTY	UNIT PRICE BID WRITTEN IN WORDS		UNIT PRICE WRITTEN IN FIGURES		TOTAL PRICE BID WRITTEN IN FIGURES	
				DOLLARS	CENTS	DOLLARS	CENTS	DOLLARS	CENTS
1	FURNISH & INSTALL LPSS GRINDER PUMP STATION INCLUDING PUMP, FIBERGLASS TANK, CONTROLS & HOUSING INCLUDING ELECTRICAL INSTALLATION, AND 4" SEWER CONNECTION FROM HOUSE, COMPLETE IN PLACE PER SUMMARY OF WORK	EA.	5						
2	ABANDON EXISTING SEPTIC TANK	EA.	5						
3	1 1/4" HDPE SDR-11 SANITARY SEWER SERVICE LINE, COMPLETE IN PLACE, FROM VALVE BOX TO GRINDER UNIT	LF	511						
4	FURNISH & INSTALL 4" PVC FOR ADDITIONAL LINES WHEN AUTHORIZED BY THE ENGINEER.	LF	100						