

JEFFERSON COUNTY PURCHASING DEPARTMENT

Deborah L. Clark, Purchasing Agent

OFFICE MAIN: (409) 835-8593

FAX: (409) 835-8456

1149 Pearl Street 1st Floor, Beaumont, TX 77701

LEGAL NOTICE Advertisement for Invitation for Bids

October 29, 2024

Notice is hereby given that sealed bids will be accepted by the Jefferson County Purchasing Department for Invitation for Bid (IFB 24-065/MR) Jefferson County Doggett Park Midway Rehabilitation. Specifications for this project may be obtained from the Jefferson County website, https://www.co.jefferson.tx.us/Purchasing/ or by calling 409-835-8593.

Bids are to be sealed and addressed to the Purchasing Agent with the bid number and name marked on the outside of the envelope or box. Bidders shall forward an original and two (2) copies of their bid to the address shown below. Jefferson County does not accept bids submitted electronically. Late bids will be rejected as non-responsive. Bids will be publicly opened and read aloud in the Jefferson County Engineering Department Conference Room (5th Floor, Historic Courthouse) 1149 Pearl Street, Beaumont, Texas 77701, at the time and date below. Bidders are invited to attend the sealed bid opening.

BID NAME: Jefferson County Doggett Park Midway Rehabilitation

BID NUMBER: IFB 24-065/MR

DUE BY TIME/DATE: 11:00 AM CT, Wednesday, November 20, 2024

MAIL OR DELIVER TO: Jefferson County Purchasing Department

1149 Pearl Street, 1st Floor Beaumont, Texas 77701

There will be a **Pre-Bid Conference and Walk-Through** at **2:00** PM **CT on Thursday**, **November 7, 2024**, at Jefferson County Engineering Department Conference Room (5th Floor, Historic Courthouse) 1149 Pearl Street, Beaumont, Texas 77701.

The County shall require the Bidder to furnish a Bid Security in the amount of five percent (5%) of the total contract cost. The bid bond must be executed with a surety company authorized to do business in the State of Texas.

Within ten (10) days after the date of contract execution and prior to the issuance of Notice to Proceed and/or Purchase Order, the Bidder shall furnish the following bonds: Performance Bond to the County for the full amount of the contract if the contract exceeds one hundred thousand dollars (\$100,000). Payment Bond to the County for the full amount of the contract if the contract exceeds twenty-five thousand dollars (\$25,000.00).

Any questions relating to these bid requirements should be directed to Mistey Reeves, Assistant Purchasing Agent at 409-835-8593 or via email at: mistey.reeves@jeffcotx.us. If no response in 72 hours, contact Deborah Clark, Purchasing Agent at 409-835-8593 or via email at: deb.clark@jeffcotx.us.

Jefferson County encourages Disadvantaged Business Enterprises (DBEs), Minority/Women Business Enterprises (M/WBEs), and Historically Underutilized Businesses (HUBs) to participate in the bidding process. Jefferson County does not discriminate on the basis of race, color, national origin, sex, religion, age or disability in employment, or the provisions of services. Individuals requiring special accommodations are requested to contact our office at least seven (7) days prior to the bid due date at 409-835-8593.

All interested firms are invited to submit a bid in accordance with the terms and conditions stated in this bid.

Bidders are strongly encouraged to carefully read the entire invitation, as failure to return and/or complete all required documentation will result in a response being declared as non-responsive.

Deborah L. Clark, Purchasing Agent Jefferson County, Texas **PUBLISH:**

The Examiner:

October 31, 2024 & November 7, 2024

TABLE OF CONTENTS

TABLE OF CONTENTS	1
SECTION 1: GENERAL CONDITIONS OF BIDDING AND TERMS OF CONTRACT	2
HUB, SBE, MBE OR WBE CERTIFICATION (INSERTION PAGE)	13
SECTION 2: FEMA MANDATED CONTRACT PROVISIONS	14
BYRD ANTI-LOBBYING CERTIFICATION FORM	24
DEBARMENT/SUSPENSION CERTIFICATION	25
CIVIL RIGHTS COMPLIANCE PROVISIONS	
SECTION 3: SPECIAL REQUIREMENTS/BID SUBMISSION REQUIREMENTS	
INSERTION PAGE: SYSTEM FOR AWARD MANAGEMENT (SAM) REGISTRATION PROOF	30
SAMPLE FORM 1295	32
INSERTION PAGE: FORM 1295	33
SECTION 3 (CONTINUED): SPECIAL REQUIREMENTS/BID SUBMISSION REQUIREMENTS	34
INSERTION PAGE: CERTIFICATE OF INSURANCE (COI) PROOF	37
BIDDER INFORMATION FORM	38
SECTION 4: MINIMUM SPECIFICATIONS	39
AFFIDAVIT OF WARRANTY	50
OFFER TO CONTRACT FORM	51
ACCEPTANCE OF OFFER FORM	52
INSERTION PAGE: ADDENDA	53
INSERTION PAGE: BID SECURITY	54
BID FORM	55
VENDOR REFERENCES	56
SIGNATURE PAGE	57
CERTIFICATION REGARDING LOBBYING	58
CONFLICT OF INTEREST QUESTIONAIRE	59
LOCAL GOVERNMENT OFFICER: CONFLICT DISCLOSURE STATEMENT FORM (OFFICE USE ONLY)	60
GOOD FAITH EFFORT DETERMINATION CHECKLIST	61
NOTICE OF INTENT	62
HUB SUBCONTRACTING PARTICIPATION DECLARATION FORM	63
RESIDENCE CERTIFICATION/TAX FORM	67
HOUSE BILL 89 VERIFICATION	
SENATE BILL 252 CERTIFICATION	
BID AFFIDAVIT	
GEOTECHNICAL INVESTIGATION	
	112

BID SUBMISSIONS:

One (1) Original and two (2) Bid Copies; with all copies to include a Completed Copy of this specifications packet (including technical specifications), in its entirety.

Each Bidder shall ensure that required parts of their bid submission are completed with accuracy and submitted as per the requirements within this specifications packet, including any addenda.

Additionally, Bidder shall monitor the Jefferson County Purchasing Department Website for any addenda, additional instructions, or bid updates. https://www.co.jefferson.tx.us/Purchasing/

Failure to return and/or complete all required documentation will result in a response being declared as non-responsive.

SECTION 1: GENERAL CONDITIONS OF BIDDING AND TERMS OF CONTRACT

By execution of this document, the Vendor accepts all general and special conditions of the contract as outlined below and, in the specifications, and plans.

1. BIDDING.

1.1 BIDS.

All bids must be submitted on the bid form furnished in this package.

1.2 AUTHORIZED SIGNATURES.

The bid must be executed personally by the Vendor, duly authorized partner of the partnership, or duly authorized officer of the corporation. If executed by an agent, a power of attorney or other evidence of authority to act on behalf of the Vendor shall accompany the bid to become a valid bid.

1.3 LATE BIDS.

Bids must be in the office of the Jefferson County Purchasing Agent before or at the specified time and date bids are due. Bids received after the submission deadline shall be rejected as non-responsive and returned unopened.

1.4 WITHDRAWAL OF BID PRIOR TO OPENING.

A bid may be withdrawn before the opening date by submitting a written request to the Purchasing Agent. If time allows, the Bidder may submit a new bid. Bidder assumes full responsibility for submitting a new bid before or at the specified time and date bids are due. Jefferson County reserves the right to withdraw a request for bids before the opening date.

1.5 WITHDRAWAL OF BID AFTER OPENING.

Bidder agrees that its offer may not be withdrawn or cancelled by the Vendor for a period of ninety (90) days following the date and time designated for the receipt of bids unless otherwise stated in the bid and/or specifications.

1.6 BID AMOUNTS.

Bids shall show net prices, extensions where applicable and net total. In case of conflict between unit price and extension, the unit price will govern. Any ambiguity in the bid as a result of omission, error, unintelligible or illegible wording shall be interpreted in the favor of Jefferson County.

1.7 EXCEPTIONS AND/OR SUBSTITUTIONS.

All bids meeting the intent of the specifications and plans will be considered for award. Vendors taking exception to the specifications and plans, or offering substitutions, shall state these exceptions in the section provided. If bid is made on an article other than the one specified, which a Bidder considers comparable, the name and grade of said article must be specified in the bid and sufficient specifications and descriptive data must accompany same to permit thorough evaluation. The absence of stated exceptions and/or substitutions shall indicate that the Vendor has not taken any exceptions to the specifications and shall be responsible to perform in strict accordance with the specifications. As a matter of practice, Jefferson County rejects exception(s) and /or substitutions as non-responsive but reserves the right to accept any and/or all of the exception(s) and/or substitution(s) deemed to be in the best interest of Jefferson County.

1.8 ALTERNATES.

The Invitation for Bid and/or specifications may expressly allow Bidder to submit an alternate bid. Presence of such an offer shall not be considered an indication of non-responsiveness.

1.9 DESCRIPTIONS.

Unless otherwise specified, any reference to make, manufacturer and/or model used in the bid specifications is merely descriptive and not restrictive, and is used only to indicate type, style, or quality of material desired.

1.10 BID ALTERATIONS.

Bids cannot be altered or amended after submission deadline. Any interlineations, alterations, or erasures made before opening time must be initialed by the signer of the bid, guaranteeing authenticity.

1.11 TAX EXEMPT STATUS.

Jefferson County is exempt from federal excise tax and state sales tax. Unless the bid form or specifications specifically indicate otherwise, the bid price must be net, exclusive of above-mentioned taxes and will be so construed. Therefore, the bid price shall not include taxes.

1.12 QUANTITIES.

Quantities indicated are estimated quantities only and are not a commitment to buy. Approximate usage does not constitute an order, but only implies the probable quantity that will be used. Commodities will be ordered on an as-needed basis. Bidder is responsible for accurate final counts.

1.13 BID AWARD.

Award of contract shall be made to the most responsible, responsive Bidder, whose offer is determined to be the best value, taking into consideration the relative importance of price. Jefferson County reserves the right to be the sole judge as to whether items bid will serve the purpose intended.

Jefferson County reserves the right to award based upon individual line items, sections or total bid.

1.14 SILENCE OF SPECIFICATIONS FOR COMPLETE UNITS.

All materials, equipment and/or parts that will become a portion of the completed work, including items not specifically stated herein but, necessary to render the service(s) complete and operational per the specifications, are to be included in the bid price. Vendor may be required to furnish evidence that the service, as bid, will meet or exceed these requirements.

1.15 ADDENDA.

Any interpretations, corrections or changes to the specifications and plans will be made by addenda no later than forty-eight (48) hours prior to the bid opening. Addenda will be posted on the Purchasing web site. Vendors are responsible for monitoring the web site in order to remain informed on addenda. Vendors shall acknowledge receipt of all addenda with submission of bid.

1.16 GENERAL BID BOND/SURETY REQUIREMENTS.

Failure to furnish bid bond/surety, if requested, will result in bid being declared non-responsive. Non-responsive bids will not be considered for award.

1.17 GENERAL INSURANCE REQUIREMENTS.

Failure to furnish Affidavit of Insurance, if required in these specifications, will result in bid being declared non-responsive. Non-responsive bids will not be considered for award.

1.18 RESPONSIVENESS.

A responsive bid shall substantially conform to the requirements of this Invitation to Bid and/or specifications contained herein. Bidders who substitute any other terms, conditions, specifications and/or requirements or who qualify their bids in such a manner as to nullify or limit their liability to the contracting entity shall have their bids deemed non-responsive. Also, bids containing any clause that would limit contracting authority shall be considered non-responsive. Examples of non-responsive bids include but shall not be limited to: a) bids that fail to conform to

required delivery schedules as set forth in the bid request; b) bids with prices qualified in such a manner that the bid price cannot be determined, such as with vague wording that may include "price in effect at the time of delivery," and c) bids made contingent upon award of other bids currently under consideration.

1.19 RESPONSIBLE STANDING OF BIDDER.

To be considered for award, Bidder must at least: have the ability to obtain adequate financial resources, be able to comply with required or proposed delivery/completion schedule, have a satisfactory record of performance; have a satisfactory record of integrity and ethics, and be otherwise qualified and eligible to receive award.

1.20 CONFIDENTIAL/PROPRIETARY INFORMATION.

If any material in the bid submission is considered by Bidder to be confidential or proprietary information (including manufacturing and/or design processes exclusive to the Bidder), Bidder <u>must</u> clearly mark the applicable pages of bid submission to indicate each claim of confidentiality. Additionally, Bidder must include a statement on company letterhead identifying all Bid Submission section(s) and page(s) that have been marked as confidential. Jefferson County will protect from public disclosure such portions of a bid, unless directed otherwise by legal authority, including existing open records acts. Merely making a blanket claim that the entire bid submission is protected from disclosure because it contains some proprietary information is not acceptable, and will make the entire bid submission subject to release under the Texas Public Information Act.

By submitting a bid, Bidder agrees to reproduction by Jefferson County, without cost or liability, of any copyrighted portions of Bidder's bid submission or other information submitted by Bidder.

1.21 PUBLIC BID OPENING.

Bidders are invited to be present at the opening of bids. After the official opening of bids, a period of not less than one week is necessary to evaluate bids. The amount of time necessary for bid evaluation may vary and is determined solely by the County. Following the bid evaluation, all bids submitted are available for public review.

2. PERFORMANCE.

2.1 DESIGN, STRENGTH, AND QUALITY.

Design, strength, and quality of materials and workmanship must conform to the highest standards of manufacturing and engineering practices. The apparent silence of specifications and/or plans as to any detailed description concerning any point shall be regarded as meaning that only the best commercial practices are to prevail. All interpretations of these specifications and/or plans shall be made on the basis of this statement.

2.2 AGE AND MANUFACTURE.

All tangible goods being bid must be new and unused, unless otherwise specified, in first-class condition, of current manufacture, and furnished ready to use. All items not specifically mentioned that are required for a complete unit shall be furnished.

2.3 DELIVERY LOCATION.

All deliveries will be made to the address(es) specified on the purchase order during normal office working hours of 8:00 am CT to 4:00 pm CT, Monday through Friday, unless otherwise authorized by the Purchasing Agent or designee.

2.4 DELIVERY SCHEDULE.

Delivery time may be an important consideration in the evaluation of best value. The maximum number of days necessary for delivery ARO shall be stated in the space, if provided, on the bid form.

2.5 DELIVERY CHARGES.

All delivery and freight charges, F.O.B. destination shown on Jefferson County purchase order, as necessary to perform contract are to be included in the bid price.

2.6 INSTALLATION CHARGES.

All charges for assembly, installation and set-up shall be included in the bid price. Unless otherwise stated, assembly, installation and set-up will be required.

2.7 OPERATING INSTRUCTIONS AND TRAINING.

Clear and concise operating instructions and descriptive literature will be provided in English, if requested. On-site detailed training in the safe and efficient use and general maintenance of item(s) purchased shall be provided as needed at the request of Jefferson County. Instructions and training shall be at no additional cost to the County.

2.8 STORAGE.

Bidder agrees to provide storage of custom ordered materials, if requested, for up to thirty (30) calendar days.

2.9 COMPLIANCE WITH FEDERAL, STATE, COUNTY, AND LOCAL LAWS.

Bids must comply with all federal, state, county and local laws, including, but not limited to, all applicable standard safety, emission, and noise control requirements. Any vehicles or equipment shall contain all standard safety, emission, and noise control requirements required for the types and sizes of equipment at the time of their manufacture. The Contractor agrees, during the performance of work or service, to comply with all applicable codes and ordinances of Jefferson County or the State of Texas as they may apply, as these laws may now read, or as they may hereafter be changed or amended.

2.10 OSHA.

The Bidder will certify all equipment complies with all regulations and conditions stipulated under the Williams-Steiger Occupational Safety and Health Act of 1971, as amended. The successful Bidder will further certify that all items furnished under this project will conform and comply with federal and State of Texas OSHA standards. The successful Bidder will agree to indemnify and hold harmless Jefferson County for any and all damages that may be assessed against the County.

2.11 PATENTS AND COPYRIGHTS.

The successful Vendor agrees to protect the County from claims involving infringements of patents and/or copyrights.

2.12 SAMPLES, DEMONSTRATIONS, AND TESTING.

At Jefferson County's request and direction, Bidder shall provide product samples and/or testing of items bid to ensure compliance with specifications. Samples, demonstrations and/or testing may be requested at any point prior to or following bid award. Samples, demonstrations and/or testing may be requested upon delivery and/or any point during the term of resulting contract. All samples (including return thereof), demonstrations, and/or testing shall be at the expense of the Bidder/Vendor.

2.13 ACCEPTABILITY.

All articles enumerated in the bid shall be subject to inspection by an officer designated for that purpose by Jefferson County. If found inferior to the quality called for, or not equal in value to the specifications, deficient in workmanship or otherwise, this fact shall be certified to the Purchasing Agent, who shall have the right to reject the whole or any part of the same. Items and/or work determined to be contrary to specifications must be replaced at the vendor's expense. Inferior items not retrieved by the vendor within thirty (30) calendar days, or an otherwise agreed upon time, shall become the property of the County. If disposal of such items warrants an expense, an amount equal to the disposal expense will be deducted from amounts payable to the vendor.

2.14 MAINTENANCE.

Maintenance required for equipment bid should be available in Jefferson County by a manufacturer authorized maintenance facility. Cost for this service shall be shown on the bid sheet as requested or on a separate sheet, as required. If Jefferson County opts to include maintenance, it shall be so stated in the purchase order and said cost will be included. Service will commence only upon expiration of applicable warranties and should be priced

accordingly.

2.15 MATERIAL SAFETY DATA SHEETS.

Under the "Hazardous Communications Act," common known as the "Texas Right to Know Act," a Bidder must provide the user department, with each delivery, material safety data sheets which are applicable to hazardous substances defined in the Act. Failure of the Bidder to furnish this documentation, will be cause to reject any bid applying thereto.

2.16 EVALUATION.

Evaluation shall be used as a determinant as to which services are the most efficient and/or most economical for the County. It shall be based on all factors having a bearing on price and performance of the items in the user environment. All bids are subject to tabulation by the Jefferson County Purchasing Department and recommendation to Jefferson County Commissioners' Court. Compliance with all bid requirements and needs of the using department are considered in evaluating bids. Pricing is not the only criteria for making a recommendation. The Jefferson County Purchasing Department reserves to right to contact any Bidder, at any time, to clarify, verify or requirement information with regard to this bid.

3. PURCHASE ORDERS AND PAYMENT.

3.1 PURCHASE ORDERS.

A purchase order(s) shall be generated by the Jefferson County Purchasing Agent to the successful vendor. The purchase order number must appear on all itemized invoices and packing slips. The County will not be held responsible for any work orders placed and/or performed without a valid current purchase order number. Payment will be made for all services rendered and accepted by the contract administrator for which a valid invoice has been received.

3.2 INVOICES.

All invoices shall reference the Purchase Order number. Invoices shall reference the bid item number or a detailed description for each item invoiced. If an item purchased and itemized on the invoice does not correspond to an item in any of the categories awarded to the vendor, invoice shall reference the item as "N/C" to indicate that it is a non-contract item. This requirement is to assist the County in verifying contract pricing on all invoices. Payment will be made under terms of net thirty (30) days unless otherwise agreed upon by seller and the purchasing department.

3.3 PROMPT PAYMENT.

In accordance with the State of Texas Prompt Payment Act, Article 601f V.T.C.S., payment will be made after receive and acceptance by the County of the merchandise ordered and of a valid invoice. Successful Bidder(s) is required to pay Subcontractors within ten (10) days after the successful Bidder receives payment from the County.

3.4 FUNDING.

Jefferson County is operated and funded on an October 1 to September 30 basis; accordingly, the County reserves the right to terminate, without liability to the County, any contract for which funding is not available.

4. CONTRACT.

4.1 CONTRACT DEFINITION.

The General Conditions of Bidding and Terms of Contract, Specifications, Plans, Bidding Forms, Addenda, and any other documents made a part of this bid shall constitute the complete bid. This bid, when duly accepted by Jefferson County, shall constitute a contract equally binding between the successful Bidder and Jefferson County.

4.2 CHANGE ORDER.

No different or additional terms will become part of this contract with the exception of a change order. No oral statement of any person shall modify or otherwise change, or affect the terms, conditions or specifications stated in

the resulting contract. All change orders to the contract will be made in writing and at the discretion and approval of Jefferson County. No change order will be binding unless signed by an authorized representative of the County and the vendor.

4.3 PRICE RE-DETERIMINATION.

A price re-determination may be requested at the time of annual renewal. All requests for price re-determination shall be in written form. Cause for such request, i.e., manufacturer's direct cost, postage rates, Railroad Commission rates, Federal/State minimum wage law, Federal/State unemployment taxes, F.I.C.A, Insurance Coverage Rates, etc., shall be substantiated in writing by the source of the cost increase. The Bidder's past experience of honoring contracts at the bid price will be an important consideration in the evaluation of the lowest and best bid. Jefferson County reserves the right to accept or reject any/all requests for price re-determination as it deems to be in the best interest of the County.

4.4 TERMINATION.

Jefferson County reserves the right to terminate the contract for default if the Bidder breached any of the terms therein, including warranties of Bidder or if the Bidder becomes insolvent or commits acts of bankruptcy. Such right of termination is in addition to and not in lieu of any other remedies which Jefferson County may have in law or equity. Default may be construed as, but not limited to, failure to deliver the proper goods and/or service within the proper amount of time, and/or to properly perform any and all services required to Jefferson County's satisfaction and/or to meet all other obligations and requirements. Contracts may be terminated without cause upon thirty (30) days' written notice to either party unless otherwise specified. Jefferson County reserves the right to award canceled contract to the next lowest Bidder. Bidder, in submitting this bid, agrees that Jefferson County shall not be liable to prosecution for damages in the event that the County declares the Bidder in default.

4.5 CONFLICT OF INTEREST.

Employees of the County are not permitted to maintain financial interest in, or receive payment, directly or indirectly, borrow from, lend to, invest in, or engage in any substantial financial transaction with any individual, organization, supplier, or Subcontractor who does business with the County without disclosure. When conflict of interest is discovered, it shall be grounds for termination of contract.

4.6 INTEREST BY PUBLIC OFFICIALS.

No public official shall have interest in this contract, in accordance with Texas Local Government Code.

4.7 PRE-AWARD/CONTRACT CONTACT BETWEEN COUNTY AND VENDORS.

The Jefferson County Purchasing Department may initiate discussions with selected vendors; however, discussions may not be initiated by vendors.

The Jefferson County Purchasing Department expects to conduct discussions with vendor's representatives authorized to contractually obligate the vendor with an offer.

Vendors shall not contact any Jefferson County personnel during the IFB process without the express permission from the Jefferson County Purchasing Agent. The Purchasing Agent will disqualify any vendor who has made site visits, contacted Jefferson County personnel, or distributed any literature without authorization from the Jefferson County Purchasing Department.

All correspondence relating to this IFB, from advertisement to award shall be sent to the Jefferson County Purchasing Department. All presentations and/or meetings between Jefferson County and the vendor relating to this IFB shall be coordinated by the Jefferson County Purchasing Department.

Selected vendors may be expected to make a presentation/product demonstration to an Evaluation Committee. Proposals, vendor presentations, and product/service evaluations may develop into negotiating sessions with the

vendor(s) as selected by the Evaluation Committee. Jefferson County expects to conduct negotiations with vendor representatives authorized to contractually obligate the vendor with an offer. If vendor is unable to agree to contract terms and conditions, Jefferson County reserves the right to terminate contract negotiations with that vendor and initiate negotiations with another vendor. In addition to a presentation, visits by the Evaluation Committee to representative vendor client sites may be conducted where the proposed solution can be demonstrated in a production environment.

4.8 INJURIES OR DAMAGES RESULTING FROM NEGLIGENCE.

Successful vendor shall defend, indemnify and save harmless Jefferson County and all its officers, agents and employees from all suits, actions, or other claims of any character, name and description brought for or on account of any injuries or damages received or sustained by any person, persons, or property on account of any negligent act or fault of the successful vendor, or of any agent, employee, Subcontractor or supplier in the execution of, or performance under, any contract which may result from bid award. Successful vendor shall pay any judgment with cost which may be obtained against Jefferson County growing out of such injury or damages.

4.9 WARRANTY.

The successful vendor shall warrant that all materials utilized in the performance of this contract shall conform to the proposed specifications and/or all warranties as stated in the Uniform Commercial Code and be free from all defects in material, workmanship and title.

4.10 UNIFORM COMMERCIAL CODE.

The successful vendor and Jefferson County agree that both parties have all rights, duties, and remedies available as stated in the Uniform Commercial Code.

4.11 **VENUE.**

This agreement will be governed and construed according to the laws of the State of Texas. This agreement is performable in the County of Jefferson, Texas.

4.12 SALE, ASSIGNMENT, OR TRANSFER OF CONTRACT.

The successful vendor shall not sell, assign, transfer or convey this contract, in whole or in part, without the prior written consent of Jefferson County.

4.13 SILENCE OF SPECIFICATIONS.

The apparent silence of these specifications as to any detailed description concerning any point, shall be regarded as meaning that only the best commercial practices are to prevail. All interpretations of these specifications shall be made on the basis of this statement.

5. REJECTION OR WITHDRAWAL.

Submission of additional terms, conditions or agreements with the bid document are grounds for deeming a bid non-responsive and may result in bid rejection. Jefferson County reserves the right to reject any and all bids and to waive any informalities and minor irregularities or defects in bids. Bids may be withdrawn in person by a bidder or authorized representative, provided their identity is made known and a receipt is signed for the bid, but only if the withdrawal is made prior to the time set for receipt of bids. Bids are an irrevocable offer and may not be withdrawn within <u>90</u> days after opening date.

6. EMERGENCY/DECLARED DISASTER REQUIREMENTS.

In the event of an emergency or if Jefferson County is declared a disaster area, by the County, State, or Federal Government, this Acceptance of Offer may be subjected to unusual usage. Contractor shall service the county during such an emergency or declared disaster under the same terms and conditions that apply during non-emergency/disaster conditions. The pricing as specified in this Acceptance of Offer shall apply to serving the County's needs regardless of the circumstances. If Contractor is unable to supply the services under the terms of the

Acceptance of Offer, then Contractor shall provide proof of such disruption and a copy of the invoice from Contractor's supplier(s).

Additional profit margin as a result of supplying services during an emergency or declared disaster shall not be permitted. In the event that additional equipment, supplies, and materials are required during the declared disaster, additional shipping, handling and drayage fees may apply.

7. AWARD.

The bid will be awarded to the responsible, responsive bidder(s) whose bid, conforming to the solicitation, will be most advantageous to Jefferson County – price and other factors considered. Unless otherwise specified in this IFB, Jefferson County reserves the right to accept a bid in whole or in part, and to award by item or by group, whichever is deemed to be in the best interest of Jefferson County. Any bidder who is in default to Jefferson County at the time of submittal of the bid shall have that bid rejected.

Jefferson County reserves the right to clarify any contractual terms with the concurrence of the Contractor; however, any substantial non-conformity in the offer, as determined by Jefferson County, shall be deemed non-responsive and the offer rejected.

In evaluating bids, Jefferson County shall consider the qualifications of the bidders, and, where applicable, operating costs, delivery time, maintenance requirements, performance data, and guarantees of materials and equipment.

In addition, Jefferson County may conduct such investigation as it deems necessary to assist in the evaluation of a bid and to establish the responsibility, qualifications, and financial ability of the bidders to fulfill the contract.

Jefferson County reserves the right to award this contract on the basis of **lowest and best bid** in accordance with the laws of the State of Texas, to waive any formality or irregularity, to make awards to more than one offeror, and/or to reject any or all bids. In the event the lowest dollar offeror meeting specifications is not a awarded a contract, Offeror may appear before the Commissioners' Court and present evidence concerning Offeror responsibility after officially notifying the Office of the Purchasing Agent of Offeror's intent to appear.

8. CONTRACT.

A response to an IFB is an offer to contract with Jefferson County based upon the terms, conditions, and specifications contained in the IFB. Bids do not become contracts unless and until they are executed by Jefferson County, eliminating a formal signing of a separate contract. For that reason, all of the terms and conditions of the contract are contained in the IFB, unless any of the terms and conditions is modified by an IFB Amendment, a Contract Amendment, or by mutually agreed terms and conditions in the contract documents.

9. WAIVER OF SUBROGATION.

Bidder and bidder's insurance carrier waive any and all rights whatsoever with regard to subrogation against Jefferson County as an indirect party to any suit arising out of personal or property damages resulting from bidder's performance under this agreement.

10. FISCAL FUNDING.

A multi-year contract (if requested by the specifications) continuing as a result of an extension option must include fiscal funding out. If, for any reason, funds are not appropriated to continue the contract, said contract shall become null and void.

11. BID RESULTS.

Bid results are not provided in response to telephone inquiries. A preliminary tabulation of bids received will be posted on the Purchasing web page at https://www.co.jefferson.tx.us/Purchasing/ as soon as possible following bid opening. A final tabulation will be posted following bid award, and will also be available for review in the Purchasing

Department.

12. CHANGES AND ADDENDA TO BID DOCUMENTS.

Each change or addendum issued in relation to this IFB document will be on file in the Office of the Purchasing Agent, and will be posted on the Purchasing web site as soon as possible. It shall be the bidder's responsibility to make inquiry as to change or addenda issued, and to monitor the web site. All such changes or addenda shall become part of the contract and all bidders shall be bound by such addenda. Information on all changes or addenda issued will be available at the Office of the County Purchasing Agent.

13. SPECIFICATIONS.

Unless otherwise stated by the bidder, the bid will be considered as being in accordance with Jefferson County's applicable standard specifications, and any special specifications outlined in the bid document. References to a particular trade name, manufacturer's catalogue, or model number are made for descriptive purposes to guide the bidder in interpreting the requirements of Jefferson County, and should not be construed as excluding bids on other types of materials, equipment, and supplies. However, the bidder, if awarded a contract, will be required to furnish the particular item referred to in the specifications or description unless departure or substitution is clearly noted and described in the bid.

Jefferson County reserves the right to determine if equipment/ product being bid is an acceptable alternate. All goods shall be new unless otherwise so stated in the bid. Any unsolicited alternate bid, or any changes, insertions, or omissions to the terms and conditions, specifications, or any other requirements of the bid, may be considered non-responsive.

14. DELIVERY.

Bids shall include all charges for delivery, packing, crating, containers, etc. Unless otherwise stated by the bidder (<u>in writing on the included Bid Form</u>), prices bid will be considered as being based on F.O.B. destination/delivered freight included.

15. INTERPRETATION OF BID AN/OR CONTRACT DOCUMENTS.

All inquiries shall be made within a reasonable time prior to the date and time fixed for the bid opening, in order that a written response in the form of an addendum, if required, can be processed before the bids are opened. Inquiries received that are not made in a timely fashion may or may not be considered.

16. CURRENCY.

Prices calculated by the bidder shall be stated in U.S. dollars.

17. PRICING.

Prices shall be stated in units of quantity specified in the bid documents. In case of discrepancy in computing the amount of the bid, the unit price shall govern.

18. NOTICE TO PROCEED/PURCHASE ORDER.

The successful bidder may not commence work under this contract until authorized to do so by the Purchasing Agent.

19. CERTIFICATION.

By signing the offer section of the Offer and Acceptance page, Bidder certifies:

- The submission of the offer did not involve collusion or other anti-competitive practices.
- The Bidder has not given, offered to give, nor intends to give at any time hereafter, any economic opportunity, future employment, gift, loan, gratuity, special discount, trip, favor, or service to any public servant in connection with the submitted offer.

• The Bidder hereby certifies that the individual signing the bid is an authorized agent for the Bidder and has the authority to bind the Bidder to the contract.

20. **DEFINITIONS.**

"County" - Jefferson County, Texas.

21. SMALL, MINORITY & WOMEN BUSINESS ENTERPRISE PARTICIPATION

It is the desire of Jefferson County to increase the participation of Small, Minority (MBE) and women-owned (WBE) businesses in its contracting and procurement programs. While the County does not have any preference or set aside programs in place, it is committed to a policy of equitable participation for these firms.

Minority owned business may be eligible for contract procurement assistance with public and private sector entities from MBDA Centers

Dallas Fort Worth MBDA Business Center

8828 N. Stemmons Freeway, Ste. 550 B Dallas, TX 75247 214-920-2436

Website: https://www.mbdadfw.com
Email: admin1@mbdadallas.com

El Paso MBDA Business Center

2401 East Missouri Avenue El Paso, TX 79903 915-351-6232

Website: https://www.mbda.gov/business-center/el-paso-mbda-business-center

Email: treed@ephcc.org

Houston MBDA Business Center

3100 Main Street, Ste. 701 Houston, TX 77002 713-718-8974

Website: https://www.mbda.gov/business-center/houston-mbda-business-center

Email: mbda@hccs.edu

San Antonio MBDA Business Center

501 W. Cesar E. Chavez Blvd., Ste. 3.324 B San Antonio, TX 78207

210-458-2480

Website: https://www.mbda.gov/business-center/san-antonio-mbda-business-center

Email: <u>Jacqueline.jackson@utsa.edu</u>

Small and woman-owned business may be eligible for assistance from U.S. Small Business Administration (SBA):

Website: https://www.sba.gov/local-assistance

[&]quot;Contractor" – The Bidder whose proposal is accepted by Jefferson County.

Dallas/Fort Worth District Office

150 West Parkway, Ste. 130

Euless, TX 76040 817-684-5500

Website: https://www.sba.gov/district/dallas-fort-worth

Email: dfwdo.email@sba.gov

El Paso District Office

211 N. Florence St, Ste. 201

El Paso, TX 79901 915-834-4600

Website: https://www.sba.gov/district/el-paso

Email: Suzanne.aguirre@sba.gov

Houston District Office

8701 S. Gessner Dr, Ste. 1200 Houston, TX 77074

713-773-6500

Website: https://www.sba.gov/district/houston

Email: houston@sba.gov

Lower Rio Grande Valley District Office

2422 E. Tyler Ave, Suite E Harlingen, TX 78550 956-427-8533

Website: https://www.sba.gov/district/lower-rio-grande-valley

Email: lrgvdo.email@sba.gov

San Antonio District Office

615 E. Houston St, Ste 298 San Antonio, TX 78205

210-403-5900

Website: https://www.sba.gov/district/san-antonio

Email: sado.email@sba.gov

West Texas District Office

1205 Texas Ave, Room 408 Lubbock, TX 79401

806-472-7462

Website: https://www.sba.gov/district/west-texas

Email: <u>lubdo@sba.gov</u>

HUB certification information can be found at:

Statewide Procurement Division HUB Program

P.O. Box 13528 Austin, TX 78711

512-463-5872 or 888-863-5881

Website: https://comptroller.texas.gov/purchasing/vendor/hub

Email: statewidehubprogram@cpa.texas.gov

PROPOSER: INSERT HUB, SBE, MBE or WBE Certification behind this p	oage.
(IFB 24-065/MR) Jefferson County Doggett Park Midway Rehabilitation	PAGE 13 OF 122

SECTION 2: FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) MANDATED CONTRACT PROVISIONS FOR NON-FEDERAL ENTITY UNDER FEDERAL AWARDS REQUIRED BY 2 C.F.R. §200.326 APPENDIX II TO 2 CFR §200

2 CFR 200.327 Contract provisions. The non-Federal entity's contracts should contain applicable provisions described in Appendix II to Part 200—Contract Provisions for non-Federal Entity Contracts Under Federal Awards. The non-Federal entity's contracts must contain the provisions described in Appendix II to Part 200—Contract Provisions for non-Federal Entity Contracts Under Federal Awards, as applicable. *Language as of August 31, 2022.

THRESHOLD	PROVISION	CITATION
>\$250,000 (Simplified Acquisition Threshold)	Contracts for more than the simplified acquisition threshold, which is the inflation adjusted amount determined by the Civilian Agency Acquisition Council and the Defense Acquisition Regulations Council (Councils) as authorized by 41 U.S.C. 1908, must address administrative, contractual, or legal remedies in instances where Contractors violate or breach contract terms, and provide for such sanctions and penalties as appropriate.	2 CFR 200 APPENDIX II (A)
>\$10,000	All contracts in excess of \$10,000 must address termination for cause and for convenience by the non-Federal entity including the manner by which it will be affected and the basis for settlement.	2 CFR 200 APPENDIX II (B)
	Equal Employment Opportunity. Except as otherwise provided under 41 CFR Part 60, all contracts that meet the definition of "federally assisted construction contract" in 41 CFR Part 60-1.3 must include the equal opportunity clause provided under 41 CFR 60-1.4(b), in accordance with Executive Order 11246, "Equal Employment Opportunity" (30 FR 12319, 12935, 3 CFR Part, 1964-1965 Comp., p. 339), as amended by Executive Order 11375, "Amending Executive Order 11246 Relating to Equal Employment Opportunity," and implementing regulations at 41 CFR part 60, "Office of Federal Contract Compliance Programs, Equal Employment Opportunity, Department of Labor."	
None	(b) Federally assisted construction contracts. (1) Except as otherwise provided, each administering agency shall require the inclusion of the following language as a condition of any grant, contract, loan, insurance, or guarantee involving federally assisted construction which is not exempt from the requirements of the equal opportunity clause:	2 CFR 200
	The [recipient] hereby agrees that it will incorporate or cause to be incorporated into any contract for construction work, or modification thereof, as defined in the regulations of the Secretary of Labor at 41 CFR Chapter 60, which is paid for in whole or in part with funds obtained from the Federal Government or borrowed on the credit of the Federal Government pursuant to a grant, contract, loan, insurance, or guarantee, or undertaken pursuant to any Federal program involving such grant, contract, loan, insurance, or guarantee, the following equal opportunity clause:	APPENDIX II I and 41 CFR §60-1.4(b)
	During the performance of this contract, the Contractor agrees as follows: (1) The Contractor will not discriminate against any employee or applicant for employment because of race, color, religion, sex, sexual orientation, gender identity, or national origin. The Contractor will take affirmative action to ensure that applicants are employed, and that employees are treated during employment without regard to their race, color, religion, sex, sexual orientation, gender identity, or national origin. Such action shall include, but not be limited to the following:	

Employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The Contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices to be provided setting forth the provisions of this nondiscrimination clause.

- (2) The Contractor will, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, color, religion, sex, sexual orientation, gender identity, or national origin.
- (3) The Contractor will not discharge or in any other manner discriminate against any employee or applicant for employment because such employee or applicant has inquired about, discussed, or disclosed the compensation of the employee or applicant or another employee or applicant. This provision shall not apply to instances in which an employee who has access to the compensation information of other employees or applicants as a part of such employee's essential job functions discloses the compensation of such other employees or applicants to individuals who do not otherwise have access to such information, unless such disclosure is in response to a formal complaint or charge, in furtherance of an investigation, proceeding, hearing, or action, including an investigation conducted by the employer, or is consistent with the Contractor's legal duty to furnish information.
- (4) The Contractor will send to each labor union or representative of workers with which he has a collective bargaining agreement or other contract or understanding, a notice to be provided advising the said labor union or workers' representatives of the Contractor's commitments under this section, and shall post copies of the notice in conspicuous places available to employees and applicants for employment.
- (5) The Contractor will comply with all provisions of Executive Order 11246 of September 24, 1965, and of the rules, regulations, and relevant orders of the Secretary of Labor.
- (6) The Contractor will furnish all information and reports required by Executive Order 11246 of September 24, 1965, and by rules, regulations, and orders of the Secretary of Labor, or pursuant thereto, and will permit access to his books, records, and accounts by the administering agency and the Secretary of Labor for purposes of investigation to ascertain compliance with such rules, regulations, and orders.
- (7) In the event of the Contractor's noncompliance with the nondiscrimination clauses of this contract or with any of the said rules, regulations, or orders, this contract may be canceled, terminated, or suspended in whole or in part and the Contractor may be declared ineligible for further Government contracts or federally assisted construction contracts in accordance with procedures authorized in Executive Order 11246 of September 24, 1965, and such other sanctions may be imposed and remedies invoked as provided in

Executive Order 11246 of September 24, 1965, or by rule, regulation, or order of the Secretary of Labor, or as otherwise provided by law. (8) The Contractor will include the portion of the sentence immediately preceding paragraph (1) and the provisions of paragraphs (1) through (8) in every subcontract or purchase order unless exempted by rules, regulations, or orders of the Secretary of Labor issued pursuant to section 204 of Executive Order 11246 of September 24, 1965, so that such provisions will be binding upon each Subcontractor or vendor. The Contractor will take such action with respect to any subcontract or purchase order as the administering agency may direct as a means of enforcing such provisions, including sanctions for noncompliance: Provided, however, that in the event a Contractor becomes involved in, or is threatened with, litigation with a Subcontractor or vendor as a result of such direction by the administering agency, the Contractor may request the United States to enter into such litigation to protect the interests of the United States. The [recipient] further agrees that it will be bound by the above equal opportunity clause with respect to its own employment practices when it participates in federally assisted construction work: Provided, that if the [recipient] so participating is a State or local government, the above equal opportunity clause is not applicable to any agency, instrumentality or subdivision of such government which does not participate in work on or under the contract. The [recipient] agrees that it will assist and cooperate actively with the administering agency and the Secretary of Labor in obtaining the compliance of Contractors and Subcontractors with the equal opportunity clause and the rules, regulations, and relevant orders of the Secretary of Labor, that it will furnish the administering agency and the Secretary of Labor such information as they may require for the supervision of such compliance, and that it will otherwise assist the administering agency in the discharge of the agency's primary responsibility for securing compliance. The [recipient] further agrees that it will refrain from entering into any contract or contract modification subject to Executive Order 11246 of September 24, 1965, with a Contractor debarred from, or who has not demonstrated eligibility for, Government contracts and federally assisted construction contracts pursuant to the Executive Order and will carry out such sanctions and penalties for violation of the equal opportunity clause as may be imposed upon Contractors and Subcontractors by the administering agency or the Secretary of Labor pursuant to Part II, Subpart D of the Executive Order. In addition, the [recipient] agrees that if it fails or refuses to comply with these undertakings, the administering agency may take any or all of the following actions: Cancel, terminate, or suspend in whole or in part this grant (contract, loan, insurance, guarantee); refrain from extending any further assistance to the [recipient] under the program with respect to which the failure or refund occurred until

>\$2,000

Davis-Bacon Act, as amended (40 U.S.C. 3141-3148). When required by Federal program legislation, all prime construction contracts in excess of \$2,000 awarded by non-Federal entities must include a provision for compliance with the Davis-Bacon Act (40 U.S.C. 3141-3144, and 3146-3148) as supplemented by Department of Labor regulations (29 CFR Part 5, "Labor Standards Provisions

satisfactory assurance of future compliance has been received from such [recipient]; and refer the case to the Department of Justice for appropriate legal

2 CFR 200 APPENDIX II (D)

proceedings.

	Applicable to Contracts Covering Federally Financed and Assisted Construction"). In accordance with the statute, Contractors must be required to pay wages to laborers and mechanics at a rate not less than the prevailing wages specified in a wage determination made by the Secretary of Labor. In addition, Contractors must be required to pay wages not less than once a week. The non-Federal entity must place a copy of the current prevailing wage determination issued by the Department of Labor in each solicitation. The decision to award a contract or subcontract must be conditioned upon the acceptance of the wage determination. The non-Federal entity must report all suspected or reported violations to the Federal awarding agency. The contracts must also include a provision for compliance with the Copeland "Anti-Kickback" Act (40 U.S.C. 3145), as supplemented by Department of Labor regulations (29 CFR Part 3, "Contractors and Subcontractors on Public Building or Public Work Financed in Whole or in Part by Loans or Grants from the United States"). The Act provides that each Contractor or subrecipient must be prohibited from inducing, by any means, any person employed in the construction, completion, or repair of public work, to give up any part of the compensation to which he or she is otherwise entitled. The non-Federal entity must report all suspected or	
>\$100,000	reported violations to the Federal awarding agency. Contract Work Hours and Safety Standards Act (40 U.S.C. 3701-3708). Where applicable, all contracts awarded by the non-Federal entity in excess of \$100,000 that involve the employment of mechanics or laborers must include a provision for compliance with 40 U.S.C. 3702 and 3704, as supplemented by Department of Labor regulations (29 CFR Part 5). Under 40 U.S.C. 3702 of the Act, each Contractor must be required to compute the wages of every mechanic and laborer on the basis of a standard work week of 40 hours. Work in excess of the standard work week is permissible provided that the worker is compensated at a rate of not less than one and a half times the basic rate of pay for all hours worked in excess of 40 hours in the work week. The requirements of 40 U.S.C. 3704 are applicable to construction work and provide that no laborer or mechanic must be required to work in surroundings or under working conditions which are unsanitary, hazardous or dangerous. These requirements do not apply to the purchases of supplies or materials or articles ordinarily available on the open market, or contracts for transportation or transmission of intelligence.	2 CFR 200 APPENDIX II (E)
None	Rights to Inventions Made Under a Contract or Agreement. If the Federal award meets the definition of "funding agreement" under 37 CFR § 401.2 (a) and the recipient or subrecipient wishes to enter into a contract with a small business firm or nonprofit organization regarding the substitution of parties, assignment or performance of experimental, developmental, or research work under that "funding agreement," the recipient or subrecipient must comply with the requirements of 37 CFR Part 401, "Rights to Inventions Made by Nonprofit Organizations and Small Business Firms Under Government Grants, Contracts and Cooperative Agreements," and any implementing regulations issued by the awarding agency.	2 CFR 200 APPENDIX II (F)
>\$150,000	Clean Air Act (42 U.S.C. 7401-7671q.) and the Federal Water Pollution Control Act (33 U.S.C. 1251-1387), as amended - Contracts and subgrants of amounts in excess of \$150,000 must contain a provision that requires the non-Federal award to agree to comply with all applicable standards, orders or regulations issued pursuant to the Clean Air Act (42 U.S.C. 7401-7671q) and the Federal Water Pollution Control Act as amended (33 U.S.C. 1251-1387). Violations must be reported to the Federal awarding agency and the Regional Office of the Environmental Protection Agency (EPA).	2 CFR 200 APPENDIX II (G)

>\$25,000	Debarment and Suspension (Executive Orders 12549 and 12689) - A contract award (see 2 CFR 180.220) must not be made to parties listed on the governmentwide exclusions in the System for Award Management (SAM), in accordance with the OMB guidelines at 2 CFR 180 that implement Executive Orders 12549 (3 CFR part 1986 Comp., p. 189) and 12689 (3 CFR part 1989 Comp., p. 235), "Debarment and Suspension." SAM Exclusions contains the names of parties debarred, suspended, or otherwise excluded by agencies, as well as parties declared ineligible under statutory or regulatory authority other than Executive Order 12549.	2 CFR 200 APPENDIX II (H)
>\$100,000	Byrd Anti-Lobbying Amendment (31 U.S.C. 1352) - Contractors that apply or bid for an award exceeding \$100,000 must file the required certification. Each tier certifies to the tier above that it will not and has not used Federal appropriated funds to pay any person or organization for influencing or attempting to influence an officer or employee of any agency, a member of Congress, officer or employee of Congress, or an employee of a member of Congress in connection with obtaining any Federal contract, grant or any other award covered by 31 U.S.C. 1352. Each tier must also disclose any lobbying with non-Federal funds that takes place in connection with obtaining any Federal award. Such disclosures are forwarded from tier to tier up to the non-Federal award.	2 CFR 200 APPENDIX II (I) and 24 CFR §570.303
	See 2 CFR §200.323.	2 CFR 200 APPENDIX II (J)
	See 2 CFR §200.216.	2 CFR 200 APPENDIX II (K)
	See 2 CFR §200.322.	2 CFR 200 APPENDIX II (L)
>\$10,000	A non-Federal entity that is a state agency or agency of a political subdivision of a state and its Contractors must comply with section 6002 of the Solid Waste Disposal Act, as amended by the Resource Conservation and Recovery Act. The requirements of Section 6002 include procuring only items designated in guidelines of the Environmental Protection Agency (EPA) at 40 CFR part 247 that contain the highest percentage of recovered materials practicable, consistent with maintaining a satisfactory level of competition, where the purchase price of the item exceeds \$10,000 or the value of the quantity acquired during the preceding fiscal year exceeded \$10,000; procuring solid waste management services in a manner that maximizes energy and resource recovery; and establishing an affirmative procurement program for procurement of recovered materials identified in the EPA guidelines.	2 CFR 200.323
>\$100,000	 §135.38 Section 3 clause All section 3 covered contracts shall include the following clause (referred to as the section 3 clause): A. The work to be performed under this contract is subject to the requirements of section 3 of the Housing and Urban Development Act of 1968, as amended, 12 U.S.C. 1701u (Section 3). The purpose of section 3 is to ensure that employment and other economic opportunities generated by HUD assistance or HUD-assisted projects covered by section 3, shall, to the greatest extent feasible, be directed to low- and very low-income persons, particularly persons who are recipients of HUD assistance for housing. B. The parties to this contract agree to comply with HUD's regulations in 24 CFR part 135, which implement section 3. As evidenced by their execution of this contract, the parties to this contract certify that they are under no contractual or other impediment that would prevent them from complying with the part 135 regulations. 	

	C. The Contractor agrees to send to each labor organization or representative of workers with which the Contractor has a collective bargaining agreement or other understanding, if any, a notice advising the labor organization or workers' representative of the Contractor's commitments under this section 3 clause, and will post copies of the notice in conspicuous places at the work site where both employees and applicants for training and employment positions can see the notice. The notice shall describe the section 3 preference, shall set forth minimum number and job titles subject to hire, availability of apprenticeship and training positions, the qualifications for each; and the name and location of the person(s) taking applications for each of the positions; and the anticipated date the work shall begin.	
	D. The Contractor agrees to include this section 3 clause in every subcontract subject to compliance with regulations in 24 CFR part 135, and agrees to take appropriate action, as provided in an applicable provision of the subcontract or in this section 3 clause, upon a finding that the Subcontractor is in violation of the regulations in 24 CFR part 135. The Contractor will not subcontract with any Subcontractor where the Contractor has notice or knowledge that the Subcontractor has been found in violation of the regulations in 24 CFR part 135.	
	E. The Contractor will certify that any vacant employment positions, including training positions, that are filled (1) after the Contractor is selected but before the contract is executed, and (2) with persons other than those to whom the regulations of 24 CFR part 135 require employment opportunities to be directed, were not filled to circumvent the Contractor's obligations under 24 CFR part 135.	
	F. Noncompliance with HUD's regulations in 24 CFR part 135 may result in sanctions, termination of this contract for default, and debarment or suspension from future HUD assisted contracts.	
	G. With respect to work performed in connection with section 3 covered Indian housing assistance, section 7(b) of the Indian Self-Determination and Education Assistance Act (25 U.S.C. 450e) also applies to the work to be performed under this contract. Section 7(b) requires that to the greatest extent feasible (i) preference and opportunities for training and employment shall be given to Indians, and (ii) preference in the award of contracts and subcontracts shall be given to Indian organizations and Indian-owned Economic Enterprises. Parties to this contract that are subject to the provisions of section 3 and section 7(b) agree to comply with section 3 to the maximum extent feasible, but not in derogation of compliance with section 7(b).	
None	Section 889(b)(1) of the John S. McCain National Defense Authorization Act for Fiscal Year 2019 (FY2019 NDAA) and 2 C.F.R. § 200.216, as implemented by FEMA Policy 405-143-1, Prohibitions on Expending FEMA Award Funds for Covered Telecommunications Equipment or Services (Interim), prohibit the obligation or expending of federal award funds on certain telecommunication products or from certain entities for national security reasons. Effective August 13, 2020, FEMA recipients and subrecipients, as well as their Contractors and Subcontractors, may not obligate or expend any FEMA award funds to:	2 CFR 200.216
	Recipients and subrecipients are prohibited from obligating or expending loan or grant funds to: (1) Procure or obtain; (2) Extend or renew a contract to procure or obtain; or (3) Enter into a contract (or extend or renew a contract) to procure or obtain equipment, services, or systems that uses covered	

	telecommunications equipment or services as a substantial or essential component of any system, or as critical technology as part of any system. As described in Public Law 115-232 , section 889, covered telecommunications equipment is telecommunications equipment produced by Huawei Technologies Company or ZTE Corporation (or any subsidiary or affiliate of such entities).	
	 (i) For the purpose of public safety, security of government facilities, physical security surveillance of critical infrastructure, and other national security purposes, video surveillance and telecommunications equipment produced by Hytera Communications Corporation, Hangzhou Hikvision Digital Technology Company, or Dahua Technology Company (or any subsidiary or affiliate of such entities). (ii) Telecommunications or video surveillance services provided by such entities or using such equipment. (iii) Telecommunications or video surveillance equipment or services produced or provided by an entity that the Secretary of Defense, in consultation with the Director of the National Intelligence or the Director of the Federal Bureau of Investigation, reasonably believes to be an entity owned or controlled by, or otherwise connected to, the government of a covered foreign country. 	
	(b) In implementing the prohibition under <u>Public Law 115-232</u> , section 889, subsection (f), paragraph (1), heads of executive agencies administering loan, grant, or subsidy programs shall prioritize available funding and technical support to assist affected businesses, institutions and organizations as is reasonably necessary for those affected entities to transition from covered communications equipment and services, to procure replacement equipment and services, and to ensure that communications service to users and customers is sustained.	
	(c) See Public Law 115-232, section 889 for additional information. (d) See also § 200.471.	
None	As appropriate and to the extent consistent with law, the non-Federal entity should, to the greatest extent practicable under a Federal award, provide a preference for the purchase, acquisition, or use of goods, products, or materials produced in the United States (including but not limited to iron, aluminum, steel, cement, and other manufactured products). The requirements of this section must be included in all subawards including all contracts and purchase orders for work or products under this award. For purposes of this section:	2 CFR
None	(1) "Produced in the United States" means, for iron and steel products, that all manufacturing processes, from the initial melting stage through the application of coatings, occurred in the United States.	200.322(a)(b)(1) (2)
	(2) "Manufactured products" means items and construction materials composed in whole or in part of non-ferrous metals such as aluminum; plastics and polymer-based products such as polyvinyl chloride pipe; aggregates such as concrete; glass, including optical fiber; and lumber.	
None	The Federal awarding agency must establish conflict of interest policies for Federal awards. The non-Federal entity must disclose in writing any potential conflict of interest to the Federal awarding agency or pass-through entity in accordance with applicable Federal awarding agency policy.	2 CFR 200.112

T	
The Federal awarding agency and the non-Federal entity should, whenever practicable, collect, transmit, and store Federal award-related information in open and machine-readable formats rather than in closed formats or on paper in accordance with applicable legislative requirements. A machine-readable format is a format in a standard computer language (not English text) that can be read automatically by a web browser or computer system. The Federal awarding agency or pass-through entity must always provide or accept paper versions of Federal award-related information to and from the non-Federal entity upon request. If paper copies are submitted, the Federal awarding agency or pass-through entity must not require more than an original and two copies. When original records are electronic and cannot be altered, there is no need to create and retain paper copies. When original records are paper, electronic versions may be substituted through the use of duplication or other forms of electronic media provided that they are subject to periodic quality control reviews, provide reasonable safeguards against alteration, and remain readable.	2 CFR 200.336
Contracting with HUB, small and minority businesses, women's business enterprises, and labor surplus area firms. (a) The non-Federal entity must take all necessary affirmative steps to assure that minority businesses, women's business enterprises, and labor surplus area firms are used when possible. (b) Affirmative steps must include: (1) Placing qualified small and minority businesses and women's business enterprises on solicitation lists; (2) Assuring that small and minority businesses, and women's business enterprises are solicited whenever they are potential sources; (3) Dividing total requirements, when economically feasible, into smaller tasks or quantities to permit maximum participation by small and minority businesses, and women's business enterprises; (4) Establishing delivery schedules, where the requirement permits, which encourage participation by small and minority businesses, and women's business enterprises; (5) Using the services and assistance, as appropriate, of such organizations as the Small Business Administration and the Minority Business Development Agency of the Department of Commerce; and (6) Requiring the prime Contractor, if subcontracts are to be let, to take the	2 CFR 200.321
Financial records, supporting documents, statistical records, and all other non-Federal entity records pertinent to a Federal award must be retained for a period of three years from the date of submission of the final expenditure report or, for Federal awards that are renewed quarterly or annually, from the date of the submission of the quarterly or annual financial report, respectively, as reported to the Federal awarding agency or pass-through entity in the case of a subrecipient. Federal awarding agencies and pass-through entities must not impose any other record retention requirements upon non-Federal entities. The only exceptions are the following: (a) If any litigation, claim, or audit is started before the expiration of the 3-year period, the records must be retained until all litigation, claims, or audit findings involving the records have been resolved and final action taken. (b) When the non-Federal entity is notified in writing by the Federal awarding agency, cognizant agency for audit, oversight agency for audit, cognizant agency for indirect costs, or pass-through entity to extend the retention period. (c) Records for real property and equipment acquired with Federal funds must be retained for 3 years after final disposition.	2 CFR 200.334
	practicable, collect, transmit, and store Federal award-related information in open and machine-readable formats rather than in closed formats or on paper in accordance with applicable legislative requirements. A machine-readable format is a format in a standard computer language (not English text) that can be read automatically by a web browser or computer system. The Federal awarding agency or pass-through entity must always provide or accept paper versions of Federal award-related information to and from the non-Federal entity upon request. If paper copies are submitted, the Federal awarding agency or pass-through entity must not require more than an original and two copies. When original records are paper, electronic versions may be substituted through the use of duplication or other forms of electronic media provided that they are subject to periodic quality control reviews, provide reasonable safeguards against alteration, and remain readable. Contracting with HUB, small and minority businesses, women's business enterprises, and labor surplus area firms. (a) The non-Federal entity must take all necessary affirmative steps to assure that minority businesses, women's business enterprises on solicitation lists; (2) Assuring that small and minority businesses and women's business enterprises on solicitation lists; (2) Assuring that small and minority businesses, and women's business enterprises on solicited whenever they are potential sources; (3) Dividing total requirements, when economically feasible, into smaller tasks or quantities to permit maximum participation by small and minority businesses, and women's business enterprises; (4) Establishing delivery schedules, where the requirement permits, which encourage participation by small and minority businesses, and women's business enterprises; (5) Using the services and assistance, as appropriate, of such organizations as the Small Business Administration and the Minority Business Development Agency of the Department of Commerce; and (6) Requiring

	(d) When records are transferred to or maintained by the Federal awarding agency or pass-through entity, the 3-year retention requirement is not applicable to the non-Federal entity. (e) Records for program income transactions after the period of performance. In some cases, recipients must report program income after the period of performance. Where there is such a requirement, the retention period for the records pertaining to the earning of the program income starts from the end of the non-Federal entity's fiscal year in which the program income is earned. (f) Indirect cost rate proposals and cost allocations plans. This paragraph applies to the following types of documents and their supporting records: Indirect cost rate computations or proposals, cost allocation plans, and any similar accounting computations of the rate at which a particular group of costs is chargeable (such as computer usage chargeback rates or composite fringe benefit rates). (1) If submitted for negotiation. If the proposal, plan, or other computation is required to be submitted to the Federal Government (or to the pass-through entity) to form the basis for negotiation of the rate, then the 3-year retention period for its supporting records starts from the date of such submission. (2) If not submitted for negotiation. If the proposal, plan, or other computation is not required to be submitted to the Federal Government (or to the pass-through entity) for negotiation purposes, then the 3-year retention period for the proposal, plan, or computation and its supporting records starts from the end of the fiscal year (or other accounting period) covered by the proposal, plan, or other computation.	
None	CONTRACTS WITH COMPANIES ENGAGED IN BUSINESS WITH IRAN, SUDAN, OR FOREIGN TERRORIST ORGANIZATION PROHIBITED. A governmental entity may not enter into a governmental contract with a company that is identified on a list prepared and maintained under Section 2270.0052, 2270.0102, or 2270.0152. In accordance with Texas Government Code, Chapter 2252, Subchapter F, Respondent hereby represents and warrants that it is not a company identified on the lists prepared and maintained under Texas Government Code §§ 2270.0052 (companies with business operations in Sudan), 2270.0102 (companies with business operations in Iran), or 2270.0152 (companies known to have contracts with or provide supplies or services to a foreign terrorist organization). Notwithstanding the foregoing, a company that the United States government affirmatively declares to be excluded from its federal sanctions regime relating to Sudan, Iran, or to a foreign terrorist organization, is not subject to contract prohibition under this clause. A company claiming such exemption must submit the official copy of the declaration.	Texas Government Code 2252.152
>\$100,000	PROVISION REQUIRED IN CONTRACT. (a) This section applies only to certain solicitations and contracts. Section 2271.002 of the Texas Government Code states the following: (a) This section applies only to a contract that: (1) is between a governmental entity and a company with 10 or more full-time employees; and (2) has a value of \$100,000 or more that is to be paid wholly or partly from public funds of the governmental entity. (b) A governmental entity may not enter into a contract with a company for goods or services unless the contract contains a written verification from the company that it:	Texas Government Code 2271.002

	(1) does not boycott Israel; and	
	(2) will not boycott Israel during the term of the contract. Section 2271.001(2) of the Government Code defines "company" to be the meaning assigned by Section 808.001 of the Texas Government Code, except that the term does not include a sole proprietorship.	
Option Contract		
Language for contracts	The contract award is contingent upon the receipt of federal funds. If no such	Optional
awarded prior to Grant	funds are awarded, the contract shall terminate.	Optional
Award		
	Mandatory standards and policies relating to energy efficiency which are contained in the state energy conservation plan issued in compliance with the Energy Policy and Conservation Act.	42 U.S.C. 6201
	The Firm agrees that no otherwise qualified individual with disabilities shall,	Section 504 of the
	solely by reason of his/her disability, be denied the benefits of, or be subjected	Rehabilitation Act
	to discrimination, including discrimination in employment, under any program	of 1973, as
	or activity receiving federal financial assistance.	amended.

BYRD ANTI-LOBBYING CERTIFICATION

Certification for Contracts, Grants, Loans, and Cooperative Agreements-The undersigned certifies, to the best of his or her knowledge and belief, that:

- 1) No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of an agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
- 2) If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.
- 3) The undersigned shall require that the language of this certification be included in the award documents for all subawards at all tiers (including subcontracts, subgrants, and contracts under grants, loans, and cooperative agreements) and that all subrecipients shall certify and disclose accordingly.

This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by section 1352, title 31, U.S. Code. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.

periare, et mer less man \$20,000 and mer mer e man	,
statement of its certification and disclosure, if an	certifies or affirms the truthfulness and accuracy of each y. In addition, the Contractor understands and agrees that the nedies for False Claims and Statements, apply to this certification
Signature of Contractor's Authorized Official	
Name and Title of Contractor's Authorized Official	
Date	

REQUIRED FORM

<u>Bidder</u>: Please complete this form and include with bid submission.

DEBARMENT/SUSPENSION CERTIFICATION

Non-Federal entities and Contractors are subject to the debarment and suspension regulations implementing Executive Order 12549, Debarment and Suspension (1986) and Executive Order 12689, Debarment and Suspension (1989) at 2 C.F.R. Part 180 and the Department of Homeland Security's regulations at 2 C.F.R. Part 3000 (No procurement Debarment and Suspension).

This requirement applies to all FEMA grant and cooperative agreement programs.

Federal Executive Order (E.O.) 12549 "Debarment" requires that all Contractors receiving individual awards, using federal funds, and all sub recipients certify that the organization and its principals are not debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded by any Federal department or agency from doing business with the Federal Government. By signing this document, you certify that your organization and its principals are not debarred. Failure to comply or attempts to edit this language may disqualify your bid. Information on debarment is available at the following websites: www.sam.gov and https://acguisition.qov/far/index.html see section 52.209-6.

The Contractor	certifies or affirms by your signature that neither you nor sed for debarment, declared ineligible, or voluntarily excluded partment or agency.
Signature of Contractor's Authorized Official	
Name and Title of Contractor's Authorized Official	

REQUIRED FORM

<u>Bidder</u>: Please complete this form and include with bid submission.

CIVIL RIGHTS COMPLIANCE PROVISIONS

1. EQUAL EMPLOYMENT OPPORTUNITY (Equal Opportunity Clause)

(For all awarded contracts that meet the definition of "federally assisted construction contract" provided in 41 CFR Part 60-1.3)

During the performance of this contract, the Contractor agrees as follows:

- 1) The Contractor will not discriminate against any employee or applicant for employment because of race, color, religion, sex, sexual orientation, gender identity, or national origin. The Contractor will take affirmative action to ensure that applicants are employed, and that employees are treated during employment without regard to their race, color, religion, sex, sexual orientation, gender identity, or national origin. Such action shall include, but not be limited to the following:
 - Employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The Contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices to be provided setting forth the provisions of this nondiscrimination clause.
- 2) The Contractor will, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, color, religion, sex, sexual orientation, gender identity, or national origin.
- 3) The Contractor will not discharge or in any other manner discriminate against any employee or applicant for employment because such employee or applicant has inquired about, discussed, or disclosed the compensation of the employee or applicant or another employee or applicant. This provision shall not apply to instances in which an employee who has access to the compensation information of other employees or applicants as a part of such employee's essential job functions discloses the compensation of such other employees or applicants to individuals who do not otherwise have access to such information, unless such disclosure is in response to a formal complaint or charge, in furtherance of an investigation, proceeding, hearing, or action, including an investigation conducted by the employer, or is consistent with the Contractor's legal duty to furnish information.
- 4) The Contractor will send to each labor union or representative of workers with which he has a collective bargaining agreement or other contract or understanding, a notice to be provided advising the said labor union or workers' representatives of the Contractor's commitments under this section and shall post copies of the notice in conspicuous places available to employees and applicants for employment.
- 5) The Contractor will comply with all provisions of Executive Order 11246 of September 24, 1965, and of the rules, regulations, and relevant orders of the Secretary of Labor.
- 6) The Contractor will furnish all information and reports required by Executive Order 11246 of September 24, 1965, and by rules, regulations, and orders of the Secretary of Labor, or pursuant thereto, and will permit access to his books, records, and accounts by the administering agency and the Secretary of Labor for purposes of investigation to ascertain compliance with such rules, regulations, and orders.
- 7) In the event of the Contractor's noncompliance with the nondiscrimination clauses of this contract or with any of the said rules, regulations, or order this contract may be canceled, terminated, or suspended in whole or in part and the Contractor may be declared ineligible for further Government contracts or federally assisted construction contracts in accordance with procedures authorized in Executive Order 11246 of September 24, 1965, and such other sanctions may be imposed and remedies invoked as provided in Executive Order 11246 of September 24, 1965, or by rule, regulation, or order of the Secretary of Labor, or as otherwise provided by law.
- 8) The Contractor will include the portion of the sentence immediately preceding paragraph (1) and the provisions of paragraphs (1) through (8) in every subcontract or purchase order unless exempted by rules, regulations, or orders of the Secretary of Labor issued pursuant to section 204 of Executive Order 11246 of September 24, 1965, so that such provisions will be binding upon each Subcontractor or vendor. The Contractor will take such action with respect to any subcontract or purchase order as the administering agency may direct as a means of enforcing such provisions, including sanctions for noncompliance:

CIVIL RIGHTS COMPLIANCE PROVISIONS (CONTINUED)

Provided, however, that in the event a Contractor becomes involved in, or is threatened with, litigation with a Subcontractor or vendor as a result of such direction by the administering agency, the Contractor may request the United States to enter into such litigation to protect the interests of the United States.

The applicant further agrees that it will be bound by the above equal opportunity clause with respect to its own employment practices when it participates in federally assisted construction work: Provided, that if the applicant so participating is a State or local government, the above equal opportunity clause is not applicable to any agency, instrumentality or subdivision of such government which does not participate in work on or under the contract.

The applicant agrees that it will assist and cooperate actively with the administering agency and the Secretary of Labor in obtaining the compliance of Contractors and Subcontractors with the equal opportunity clause and the rules, regulations, and relevant orders of the Secretary of Labor, that it will furnish the administering agency and the Secretary of Labor such information as they may require for the supervision of such compliance, and that it will otherwise assist the administering agency in the discharge of the agency's primary responsibility for securing compliance.

The applicant further agrees that it will refrain from entering into any contract or contract modification subject to Executive Order 11246 of September 24, 1965, with a Contractor debarred from, or who has not demonstrated eligibility for, Government contracts and federally assisted construction contracts pursuant to the Executive Order and will carry out such sanctions and penalties for violation of the equal opportunity clause as may be imposed upon Contractors and Subcontractors by the administering agency or the Secretary of Labor pursuant to Part II, Subpart D of the Executive Order. In addition, the applicant agrees that if it fails or refuses to comply with these undertakings, the administering agency may take any or all of the following actions: Cancel, terminate, or suspend in whole or in part this grant (contract, loan, insurance, guarantee); refrain from extending any further assistance to the applicant under the program with respect to which the failure or refund occurred until satisfactory assurance of future compliance has been received from such applicant; and refer the case to the Department of Justice for appropriate legal proceedings.

Signature of Contractor's Authorized Official
Name and Title of Contractor's Authorized Officia
Date

REQUIRED FORM

<u>Bidder</u>: Please complete this form and include with bid submission.

SECTION 3: SPECIAL REQUIREMENTS/BID SUBMISSION INSTRUCTIONS

The following requirements and instructions <u>supersede</u> General Requirements where applicable.

1. SUBMISSION OF BID.

Bidder is Responsible for Submitting:

One (1) Original and two (2) Bid Copies; with all copies to include a Completed Copy of this Specifications Packet (including technical specifications), in its entirety.

The County requests that bid submissions NOT be bound by staples or glued spines.

Each Bidder shall ensure that required parts of their bid submission are completed with accuracy and submitted as per the requirements within this specifications packet, including any addenda.

Additionally, Bidder shall monitor the Jefferson County Purchasing Department Website for any addenda, additional instructions, or bid updates. https://www.co.jefferson.tx.us/Purchasing/

Failure to return and/or complete all required documentation will result in a response being declared as non-responsive.

Bids must be submitted in complete original form by mail or messenger to the following address:

Jefferson County Purchasing Department 1149 Pearl Street, 1st Floor Beaumont, TX 77701

<u>BID PACKAGING</u>: Bidder shall submit response in a tightly sealed opaque envelope or box, plainly marked "SEALED BID." The outside of the envelope of box shall also include the IFB Number, IFB Name, IFB Due Date, and the Bidder's Name and Address; and shall be addressed to the Purchasing Agent.

All submissions must be received by 11:00 am CT, Wednesday, November 20, 2024.

Bids will be accepted at the above address until the time and date specified herein, and immediately after will be publicly opened and read aloud.

Jefferson County will not accept any responsibility for bids being delivered by third party carriers.

Late bids will not be accepted and will be returned unopened to the Bidder.

Jefferson County shall not be responsible for any effort or cost expended in the preparation of a response to this IFB.

All bid responses submitted in response to this invitation shall become the property of Jefferson County and will be a matter of public record available for review.

All protests should be coordinated through the Purchasing Office prior to award recommendation to Commissioners' Court.

<u>COURTHOUSE SECURITY</u>: All visitors to the Courthouse must pass through Security. Respondents planning to hand deliver proposals must allow time to get through Security, as a delay in entering the Courthouse will not be accepted as an excuse for late submittal. Mondays and Tuesdays are particularly heavy days.

In response to the Covid-19 pandemic, Jefferson County has implemented precautionary measures as currently recommended by the CDC within its facilities. Bidders are strongly urged to plan accordingly.

COUNTY HOLIDAYS (2024):

January 15	(Monday)	Martin Luther King, Jr. Day
March 29	(Friday)	Good Friday
May 27	(Monday)	Memorial Day
June 19	(Wednesday)	Juneteenth
July 4	(Thursday)	Independence Day
September 2	(Monday)	Labor Day
November 11	(Monday)	Veteran's Day
November 28 & 29	(Thursday & Friday)	Thanksgiving
December 25 & 26	(Wednesday & Thursday)	Christmas
January 1, 2025	(Wednesday)	New Year's

<u>Submissions During Time of Inclement Weather, Disaster, or Emergency:</u>

In case of inclement weather or any other unforeseen event causing the County to close for business on the date of a bid/proposal/statement of qualifications submission deadline, the IFB closing will automatically be postponed until the next business day that County offices are open to the public. Should inclement weather conditions or any other unforeseen event cause delays in courier service operations, the County may issue an addendum to all known vendors interested in the project to extend the deadline. It will be the responsibility of the vendor to notify the county of their interest in the project should these conditions impact their ability to submit a bid/proposal/statement of qualifications submission before the stated deadline. The County reserves the right to make the final judgement call to extend any deadline.

Should an emergency or unanticipated event interrupt normal County processes, and bid/proposal/statement of qualifications submissions cannot be received by the Jefferson County Purchasing Department's office by the exact time specified in the IFB and urgent County requirements preclude amendment to the IFB, the time specified for receipt of Statements of Qualifications will be deemed to be extended to the same time of day specified in the solicitation on the first business day on which normal County processes resume.

2. PRE-BID MEETING AND WALK-THROUGH.

There will be a Pre-Bid Meeting and Walk-Through on Thursday, November 7, 2024, at 2:00 PM CT, at Jefferson County Engineering Department Conference Room (5th Floor, Historic Courthouse) 1149 Pearl Street, Beaumont, Texas 77701

3. QUESTIONS/DEADLINE FOR QUESTIONS.

Questions may be emailed to **Mistey Reeves**, **Assistant Purchasing Agent** at: mistey.reeves@jeffcotx.us. If no response in 72 hours, contact **Deborah Clark**, **Purchasing Agent** at: deb.clark@jeffcotx.us. The Deadline for asking questions or requesting additional information (in writing) is 5:00 pm, CT, Wednesday, November 13, 2024.

4. VENDOR REGISTRATION (System for Award Management).

Vendors doing business with Jefferson County are <u>required</u> to be registered with The System for Award Management (SAM), with an "active" status. The System for Award Management (SAM) is the Official U.S. Government system that consolidated the capabilities of CCR/FedReg, ORCA, and EPLS. There is NO fee to register for this site. Entities may register at no cost directly from the SAM website at: https://www.sam.gov

In instances where a vendor has either an "Inactive" SAM Registration or is not currently registered with the System for Award Management, the Purchasing Department may <u>initially</u> accept proof (printout from the SAM website) that the vendor has begun the registration process in order for the IFB/RFQ/RFP submission to be considered as "responsive" to the specifications for the project.

However, the SAM Registration must be completed (showing "active" status, with no exclusions) <u>prior</u> to the award and/or execution of an agreement or contract for the project.

BIDDER:	INSERT PROOF OF	SYSTEM FOR AWARI	D MANAGEMENT (SAN	n) BEHIND THIS PAGE.
(IFB 24-06!	5/MR) Jefferson County Do	ggett Park Midway Rehabilitation	on	PAGE 30 OF 122

5. FORM 1295 (Texas Ethics Commission) SUBMISSSION REQUIREMENT/INSTRUCTIONS FOR BIDDERS.

All Non-Exempt Bidders are required to submit a completed FORM 1295 with bid submission.

1. Submit a FORM 1295 online via the Texas Ethics Commission website link below.

Vendors must enter the required information on Form 1295, and print a copy of the completed form. The form will include a certification of filing that will contain a unique certification number.

2. Submit a FORM 1295 <u>hard copy</u> (completed & signed by an Authorized Agent of the Awarded Vendor), to the Jefferson County Purchasing Department <u>with bid submission.</u>

FORM 1295, Completion Instructions, and Login Instructions are available via the Texas Ethics Commission Website at: https://www.ethics.state.tx.us/whatsnew/elf_info_form1295.htm

A sample of a completed FORM 1295 is included on **PAGE 32**.

FORM 1295 Implementation Background:

In accordance with House Bill 1295 (passed January 1, 2016), Vendors entering into contracts and professional agreements with Jefferson County will be required to complete a Certificate of Interested Parties (FORM 1295), unless contract is considered exempt as described below.

In 2017, the Texas legislature amended the law to require Form 1295 to include an "unsworn declaration" which includes, among other things, the date of birth and address of the authorized representative signing the form. The unsworn declaration, including the date of birth and address of the signatory, replaces the notary requirement that applied to contracts entered into before January 1, 2018. The TEC filing application does not capture the date of birth or street address of the signatory and it will not appear on forms that are filed using the TEC filing application.

Changes to the law requiring certain businesses to file a Form 1295 are in effect for contracts entered into or amended on or after January 1, 2018. The changes exempt businesses from filing a Form 1295 for certain types of contracts and replace the need for a completed Form 1295 to be notarized. Instead, the person filing a 1295 needs to complete an "unsworn declaration."

Question: Will the date of birth and address provided appear on the TEC's website when the form is filed?

<u>Answer</u>: No. The TEC filing application does not capture the date of birth or street address of the signatory and it will not appear on forms that are filed using the TEC filing application. Although the TEC does not capture the date of birth and street address of the signatory, the contracting state agency or governmental agency will have a physical copy of the form that includes the date of birth and address of the signatory. The TEC cannot answer whether the contracting state agency or governmental agency may release such information. Questions regarding the Texas Public Information Act may be directed to the Office of the Attorney General. See also Paxton v. City of Dall., No. 03-13-00546-CV, 2015 Tex. App. LEXIS 5228, at *10-11 (App.—Austin May 22, 2015) (mem. op.) (pet. denied) (available here)

FORM 1295 EXEMPTIONS:

What type of contracts are exempt from the Form 1295 filing requirement under the amended law?

The amended law adds to the list of types of contract exempt from the Form 1295 filing requirement.

A completed Form 1295 is <u>not</u> required for:

- a sponsored research contract of an institution of higher education
- an interagency contract of a state agency or an institution of higher education
- a contract related to health and human services if: the value of the contract cannot be determined at the time the contract is executed; and any qualified vendor is eligible for the contract
- a contract with a publicly traded business entity, including a wholly owned subsidiary of the business entity
- a contract with an electric utility, as that term is defined by Section 31.002, Utilities Code
- a contract with a gas utility, as that term is defined by Section 121.001, Utilities Code

SAMPLE COMPLETED FORM 1295

VENDOR: FORM 1295 MUST BE COMPLETED/SUBMITTED ON TEXAS ETHICS COMMISSION WEBSITE. HARD COPY OF FORM 1295 IS TO BE PRINTED, COMPLETED, SIGNED, AND SUBMITTED WITH BID/PROPOSAL/AGREEMENT/CONTRACT. JEFFERSON COUNTY WILL CONFIRM RECEIPT OF COMPLETED HARD COPY WITH THE TEXAS ETHICS COMMISSION. CERTIFICATE OF INTERESTED PARTIES FORM **1295** OFFICE USE ONLY Complete Nos. 1 - 4 and 6 if there are interested parties. Complete Nos. 1, 2, 3, 5, and 6 if there are no interested parties. 1 Name of business entity filing form, and the city, state and country of the business entity's place of business. VENDOR:ENTER YOUR BUSINESS NAME, CITY, STATE, AND COUNTRY HERE Name of governmental entity or state agency that is a party to the contract for which the form is being filed. **JEFFERSON COUNTY, TEXAS** Provide the identification number used by the governmental entity or state agency to track of identify and provide a description of the services, goods, or other property to be provided upon the contract. identify the contract, VENDOR: ENTER BID/PROPOSAL/CONTRACT/AGREEMENT REF# AND TITLE HER Nature of Interest (check applicable) City, State, Country Name of Interested Party (place of business) Controlling Intermediary St www ex VENDOR: ENTER EACH PERSON HAVING INTEREST, X OWNERS ARE THE CONTROLLING PARTIE VENDOR: WORKERS (OR NON-OWNERS) X COMPANY ARE INTERMEDIARY PARTIES **CHECK BELOW IF APPLICABLE** Check only if there Ointerested Party. VENDOR: COMPLETE, DATE, AND SIGN THIS DECLARATION SECTION. and my date of birth is (street) (city) (zip code) (country) penalty of perjury that the foregoing is true and correct. County, State of _ (month) (vear) Signature of authorized agent of contracting business entity (Declarant) ADD ADDITIONAL PAGES AS NECESSARY

Form provided by Texas Ethics Commission www.ethics.state.tx.us Revised 12/22/2017 NOTE: JEFFERSON COUNTY WILL KEEP A COPY OF THIS FORM ON FILE FOR EACH BID/PROPOSAL/CONTRACT/AGREEMENT AND EACH VENDOR RESPONDING TO BIDS/PROPOSALS.

BIDDER: INSERT COMPLETED FORM 1295 BEHIND THIS PAGE.

SECTION 3: SPECIAL REQUIREMENTS/BID SUBMISSION INSTRUCTIONS (CONTINUED)

6. MULTIPLE VENDOR AWARD.

Jefferson County reserves the right to award this contract to more than one vendor at the County's discretion.

7. DELIVERY.

If delivery is required, all items must be packaged so as to be protected from damage during shipping and handling. Any item(s) damaged in shipping must be replaced in kind, or repaired, by the Contractor, at the discretion of, and at no additional charge to, Jefferson County.

8. PAYMENT.

Jefferson County will pay original invoices that clearly itemize the goods and/or services provided as to quantity, part number, description, price, applicable discount (if any), labor charges showing time differential, if applicable and if previously agreed to, and delivery, installation, and set-up costs, if applicable and if previously agreed to. Only charges as stated on the Bid Form(s) submitted as a part of the bid will be considered.

Invoices must indicate Jefferson County as applicable, the address to which the product(s) and/or service(s) were delivered, and the applicable purchase order number. Invoices will be matched to delivery tickets prior to payment; therefore, all delivery tickets should have an accurate description of the product(s) and/or service(s).

Invoices shall be submitted to:

Jefferson County Auditing Department Attention: Accounts Payable 1149 Pearl Street, 7th floor Beaumont, TX 77701.

9. USAGE REPORTS.

Jefferson County reserves the right to request, and receive at no additional cost, up to two (2) times during the contract period, a usage report detailing the products and/or services furnished to date under a contract resulting from this IFB. The reports must be furnished no later than five (5) working days after written request and itemize all purchases to date by Jefferson County department, description of each item purchased, including manufacturer, quantity of each item purchased, per unit and extended price of each item purchased, and total amount and price of all items purchased.

10. INSURANCE.

The Contractor (including any and all Subcontractors as defined in Section 11.1.3 below) shall, at all times during the term of this contract, maintain insurance coverages with not less than the type and requirements shown below. Such insurance is to be provided at the sole cost of the Contractor. These requirements do not establish limits of the Contractor's liability.

All policies of insurance shall waive all rights of subrogation against the County, its officers, employees and agents; a copy of the policy wording or endorsement is required.

Contractor shall furnish Jefferson County with Certificate of Insurance naming Jefferson County as additional insured and will provide the actual policy wording or endorsement showing as such.

All insurance must be written by an insurer licensed to conduct business in the State of Texas.

Minimum Insurance Requirements:

Public Liability, including Products & Completed Operations \$1,000,000 Excess Liability \$1,000,000

<u>Property Insurance (policy below that is applicable to this project):</u>

Improvements & Betterments Policy: Improvements/Remodeling (for Lease Tenants)
Builder's Risk Policy: Structural Coverage for Construction Projects
Installation Floater Policy: Improvements/Alterations to Existing Structure

Workers' Compensation

Statutory Coverage (See Section 9 Below)

11. WORKERS' COMPENSATION INSURANCE

11.1 Definitions:

- 11.1.1 Certificate of coverage ("Certificate") A copy of a certificate of insurance, a certificate of authority to self-insure issued by the commission, or a coverage agreement, DWC-81, DWC-82, DWC-83, or DWC-84 showing statutory workers' compensation insurance coverage for the person's or entity's employees providing services on a project, for the duration of the project.
- 11.1.2 **Duration of the project** Includes the time from the beginning of the work on the project until the Contractor's/person's work on the project has been completed and accepted by the governmental entity.
- 11.1.3 Persons providing services on the project ("Subcontractor") in article 406.096 Includes all persons or entities performing all or part of the services under the Contractor has undertaken to perform on the project, regardless of whether that person contracted directly with the Contractor and regardless of whether that person has employees. This includes, without limitation, independent Contractors, Subcontractor, leasing companies, motor carriers, owner-operators, employees of any such entity, or employees of any entity which furnishes persons to provide services on the project. "Services" includes, without limitation, providing, hauling or delivering equipment or materials, or providing labor, transportation, or other service related to a project. "Services" does not include activities unrelated to the project, such as food/beverage vendors, office supply deliveries, and delivery of portable toilets.
- 11.2 The Contractor shall provide coverage, based on proper reporting of classification code and payroll amounts and filing any coverage agreements, which meets the statutory requirements of Texas Labor Code, Section 401.011(44) for all employees of the Contractor providing services on the project, for the duration of the project.
- 11.3 The Contractor must provide a certificate of coverage to the governmental entity prior to being awarded the contract **refer to Section 10 above**.
- 11.4 If the coverage period shown on the Contractor's current certificate of coverage ends during the duration of the project, the Contractor must, prior to the end of the coverage period, file a new certificate of coverage with the governmental entity showing that coverage has been extended.
- 11.5 The Contractor shall obtain from each person providing services on a project, and provide to the governmental entity:
 - 11.5.1 A certificate of coverage, prior to that person beginning work on the project, so the governmental entity will have on file certificates of coverage showing coverage for all persons providing services on the project; and
 - 11.5.2 No later than seven (7) days after receipt by the Contractor, a new certificate of coverage showing extension of coverage, if the coverage period shown on the current certificate ends during the duration of the project.
- 11.6 The Contractor shall retain all required certificates of coverage for the duration of the project and for one (1) year thereafter.
- 11.7 The Contractor shall notify the governmental entity in writing by certified mail or personal delivery, within ten (10) days after the contractor knew or should have known, of any change that materially affects the provision of coverage of any person providing services on the project.
- 11.8 The Contractor shall post on each project site a notice, in the text, form and manner prescribed by the Texas Department of Workers' Compensation, informing all persons providing services on the project that they are required to be covered, and stating how a person may verify coverage and report lack of coverage.

- 11.9 The Contractor shall contractually require each person with whom it contracts to provide services on a project to:
 - 11.9.1 Provide coverage, based on reporting of classification codes and payroll amounts and filing of any coverage agreements, which meets the statutory requirements of Texas Labor Code, Section 401.011(44) for all its employees providing services on the project, for the duration of the project.
 - 11.9.2 Provide to the Contractor, prior to that person beginning work on the project a certificate of coverage showing that coverage is being provided for all employees of the person providing services on the project, for the duration of the project.
 - 11.9.3 Provide the Contractor, prior to the end of coverage period, a new certificate of coverage showing extension of coverage, if the coverage period shown on the current certificate of coverage ends during the duration of the project.
 - 11.9.4 Obtain from each person with whom it contracts, and provide to the Contractor:
 - 11.9.4.1 A certificate of coverage, prior to the other person beginning work on the project; and
 - 11.9.4.2 the coverage period, if the coverage period shown on the current certificate of a new certificate of coverage showing extension of coverage, prior to the end of coverage ends during the duration of the project.
 - 11.9.5 Retain all required certificates of coverage on file for the duration of the project and for one (1) year thereafter.
 - 11.9.6 Notify the governmental entity in writing by certified mail or personal delivery, within ten (10) days after the person knew or should have known, of any change that materially affects the provision of coverage of any person providing services on the project; and
 - 11.9.7 Contractually require each person with whom it contracts to perform as required by paragraphs 11.1. 11.7., with the certificates of coverage to be provided to the person for whom they are providing services.
- By signing this contract or providing or causing to be provided a certificate of coverage, the Contractor is representing to the governmental entity that all employees of the Contractor who will provide services of the project will be covered by workers' compensation coverage for the duration of the project, that the coverage will be based on proper reporting of classification codes and payroll amounts, and that all coverage agreements will be filed with the appropriate insurance carrier or, in the case of a self-insured, with the commission's Division of Self-Insurance Regulation. Providing false or misleading information may subject the Contractor to administrative penalties, criminal penalties, civil penalties, or other civil actions.
- 11.11 The Contractor's failure to comply with any of these provisions is a breach of contract by the Contractor which entitles the governmental entity to declare the contract void if the Contractor does not remedy the breach within ten (10) days after receipt of notice of breach from the governmental entity.

BIDDER: INSERT COPY OF CERTIFICATE OF INSURANCE (COI) BEHIND THIS PAGE.

Note: For bid purposes, a general COI will suffice. However, a COI that includes the notation that "Jefferson County as an additional insured" will be required from Awarded Bidder(s) prior to the issuance of a Purchase Order.

BIDDER INFORMATION FORM

Instructions: Complete the form below. Please provide legible, accurate, and complete contact information. PLEASE PRINT.

Bid Number & Name: (IFB 24-065/MR) Jefferson County Doggett Park Midway Renabilitation				
Bidder's Company/	Business Name:			
Bidder's TAX ID Nu	mber:			
<i>If Applicable</i> : HU	B Vendor No	DBE Vendor No.		
Contact Person:		Title:		
Phone Number (wit	th area code):			
Alternate Phone Nu	umber if available (with area code):_			
Fax Number (with a	area code):			
Email Address:				
Mailing Address (Please provide a <u>physical address for bid bond return</u> , if applicable):				
Address				
City, State, Zip Code				

REQUIRED FORM

SECTION 4: MINIMUM SPECIFICATIONS

The following requirements and specifications supersede General Bid Requirements where applicable. Any questions relating to bid submission or bid item specifications requirements should be directed to Mistey Reeves, Assistant Purchasing Agent at 409-835-8593 or via email at: mistey.reeves@jeffcotx.us. If no response in 72 hours, contact Deborah Clark, Purchasing Agent at 409-835-8593 or via email at: deb.clark@jeffcotx.us. Please reference Bid Number: IFB 24-065/MR. To schedule a site visit, contact Michelle Falgout, County Engineer at 409-835-8584.

DIVISION I SCOPE OF WORK

PROJECT OVERVIEW

It is the intent of the Contract Documents to provide the requirements and specification for the construction associated with Jefferson County **Doggett Park Midway Rehabilitation Project** which includes all labor, material and work required for Excavation of 2.25 inches of the existing surface materials, reworking existing base, cement treating the base in-place, grading, priming and placement of 2 inches of HMA, and all other work related to rehabilitation as called out in the plans and specifications for this project.

The project requires that the construction be completed and ready for use by the Owner in the time specified in this document. CONTRACTOR TO PERFORM ALL WORK AS INDICATED. This contract shall provide for the necessary labor, overhead, supervision, equipment, tools, materials, and all other related construction items necessary for the proposed project, all in strict accordance with the construction plans and specifications. Contractor is responsible for all damages caused by the contractor. This includes labor, materials and work required to repair damages. The Geotechnical Investigations begin on page 71 of these specifications and the Project Plans begin on page 113 of these specifications.

GENERAL SCOPE OF WORK:

The general scope of the Midway Rehabilitation work includes all labor, material and work to perform the following:

- Excavating the top 2.25 inches of the existing surface to the limits shown on the plans. Surface varies, but includes chip seal, asphalt patches, grass areas, and base.
- Reworking 8 inches of the remaining base and subgrade materials
- Mixing 8% cement, by weight, into the 8 inch reworked surface
- Compacting, watering, grading to the required grades and micro cracking the surface
- Application of AEP primer to the surface
- Installing 2 inches of HMA with PG70-22 binder
- Performing hand work as necessary around areas in the parking lot that include concrete pads for water connections/sewer clean outs, light poles, electrical boxes, fire hydrants, bollards, etc.
- Placing temporary safety fencing at the location shown on the drawings and placing barricades areas between finished asphalt areas and areas still under construction, if needed, to provide access to the Arena doors near the north east corner of the Midway.
- Install, maintain, and remove erosion, sedimentation, and environmental control measures to prevent or reduce the discharge of pollutants to the existing storm sewer system and to areas around the Midway Project Area.

AREA CONDITIONS:

- There are various utilities in the Midway Project Area. Those include, but may not be limited to: stormwater pipes, water lines, sewer lines, electrical service or other possible lines. The approximate locations of the known services have been shown on the plans. The location and protection of these utilities is the sole responsibility of the Contractor. Any damage to these utilities is the responsibility of the Contractor.
- 2. Contractor shall exercise caution to avoid damage to any service lines and shall be responsible for their repair, if damaged. In the event that those utilities are damaged, the Contractor shall be responsible for repair and restoration without delay at no additional cost to the owner.
- 3. Contractor is required to notify and request locates from the Texas One Call System prior to beginning any work and to coordinate with the Owner or service line owners for location of various utility lines and other infrastructure. Where the owner is unable to locate those utilities, the Contractor shall take great care not to damage them in his operations.
- 4. All utility adjustments shall be the responsibility of the Owners of the utilities and if in the opinion of the Engineer adjustment is required, the Contractor will be responsible for notifying the respective owner.
- 5. The Contractor shall restore all pavements adjacent to the project that have been damaged by the Contractor, to their original condition or better, in the opinion of the Owner. This shall include any base repairs or surface repairs to pavements. There shall be no additional payment for adjacent pavement replacement or repairs.
- 6. All excess materials shall be disposed of on a regular basis or whenever, in the opinion of the Engineer, they constitute a hazard or nuisance. Disposal of excess soils shall be in accordance with all local, state, and federal laws and shall be solely at the Contractor's expense.
- 7. Bidders should visit the proposed project site to acquaint themselves with the site conditions and access limitations prior to bidding on the project. Bidding on the project shall be considered the Contractor's assurance that he is familiar with the site conditions and that his bid provides for reasonable unanticipated conditions.

WORK SEQUENCE/SCHEDULING:

It shall be the responsibility of the Contractor to coordinate all work with the County and any other party affected by this project.

Work may be performed at anytime, provided the project is completed in the specified time frame.

The contractor will work with the County and the Doggett Park management company to phase work as necessary to provide access to the Arena doors that face the Midway area, if needed, for specific events.

Contractor will begin work within 5 days of the notice to proceed and will be required to be finished with the project by February 28, 2025

SPECIAL CONSIDERATIONS:

Traffic flow through and around the construction area(s) shall be in accordance with the approved traffic control plan developed by the Contractor and shall be maintained with as little disruption as possible to the operations of Doggett Park. Barricades, lights, signs and other traffic control devices shall be installed, on a timely basis, and be maintained in accordance with the Texas MUTCD and provisions of these Contract Documents as approved by the Engineer.

The Contractor shall work closely with the various utility owners and assure prompt access to their equipment for service or adjustment. The Contractor shall be solely responsible for the coordination of work with any utility owner which may be affected by the work. Additionally, forces of Jefferson County, in order to secure the safety, welfare and convenience of the citizens of Jefferson County, must provide services on both emergency and normal, continuing basis. Provisions of these services may require County forces to work within or around the construction area prescribed by this project. While it is anticipated that the construction schedule impact induced by the work of and utility crews will be minimal, the Contractor, by affixing proper signature to these Contract Documents, agrees to indemnify and hold harmless Jefferson County from any and all claims of damage or delay, incurred or alleged to have incurred, in connection with the work of said crews.

SUBMITTALS:

Contractor shall submit the following submittals for review within 10 days of receiving the notice to proceed:

- 1 Proposed HMA Design;
- 2 Schedule showing estimated work times and sequencing of project work; and
- 3 Truck routes

1 YEAR WARRANTY

Contractor will provide an Affidavit of Warranty at the end of the project. A copy of the Warranty document is attached to this Scope of work. A copy of the Warranty document is attached on page 50 of these specifications.

END OF DIVISION I SCOPE OF WORK

DIVISION II GENERAL NOTES AND BID ITEM NOTES

General Notes

- 1. The Texas Standard Specifications 2014 will govern all specifications not directly addressed in this document.
- 2. Direct attention to comply with all ordinances and regulations of Jefferson County. A permit for this project will be required from the Jefferson County Environmental Control Department. A permit or permission for construction in the City of Beaumont drainage easement will also be required.
- 3. Temporary erosion, sediment and water control measures shall be required. Erosion control logs are to be utilized at every inlet or discharge point within the affected areas of construction and should remain in place throughout the duration of construction. Contractor will be responsible for removing dirt from the site roads daily to prevent tracking. Any concrete truck washout will be disposed of at the plant.
- 4. Procure all the necessary County permits and licenses before the start of this project. This will not be paid for directly but shall be considered subsidiary to various bid items of the contract.
- 5. Contractor is required to notify and request locates from the Texas One Call System prior to beginning any work. In Texas Call 811 or see the 811 website for information. Additional reference numbers are provided below

AT&T Communications	Entergy Distribution	CenterPoint Energy/ Entex
Beaumont, Texas 77701 (409) 839-7030 Randall Jennings	North 11 th Street Beaumont, Texas 77701 (409) 785-2136 Brian Cross	6090 College Street Beaumont, Texas 77707 (409) 860-7113 Tara Hunter
Spectrum 602 N. Hwy 69 Nederland, Texas 77627 (409) 720-5513 Michael Ward	Jefferson County Engineering Dept (409) 835-8584 Michelle Falgout	Doggett Ford Park Oak View Group (409)-291-0157 Lance Rosenberg
Jefferson County Precinct #4 (409)-273-3438 Milton Zachary	City of Beaumont City Engineer 409-880-3725 Molly Villareal	Doggett Ford Park Oak View Group Destin Deleon (409-499-8832

This action does not relieve the Contractor of the responsibilities under the terms of the contract or the plans and specifications. Damage caused by the Contractor's operations shall be repaired and restored to service in a timely manner at no expense to Jefferson County.

6. The approximate location of the known underground utility installations is as shown on the plans. Confirm the location of these utility lines and the exact location of any others which may exist. Assume full responsibility for notifying the utility involved in case of conflict or damage and he/she shall be responsible for damage that occurs due to his/her negligence. Remove and dispose of abandoned lines encountered that interfere with the construction of this project. Consider this work to be subsidiary to the various bid items of the contract.

- 7. Allow County forces to enter this project to accomplish such work as shown in the plans and as may be deemed necessary by the Engineer.
- 8. Maintain for the duration of this project, those sections of existing and proposed Midway areas, driveways, walkways, pavements and appurtenances which are to be constructed, reconstructed, modified, or remain in place under this project. Any portion of Midway areas, driveways, walkways, pavements and appurtenances damaged by the contractor's forces shall be repaired by the contractor at his/her expense. This shall include but is not limited to driveways, parking lots, fencing, gates, storm pipes, MH tops, area lighting poles, electrical boxes, water valves/hose bibs, underground electrical, sewer lines and cleanout, fire hydrants, bollards, misc. concrete pads, buildings etc. No payment will be made for this work. County forces will maintain the existing section of streets and its appurtenances not a part of this project except those sections damaged by the Contractor's forces shall be repaired by the Contractor at his entire expense
- 9. Place all equipment and vehicles not in operation behind barriers/fencing when not in use.
- 10. All truck traffic transporting materials to and from the project are to access and depart from the project site utilizing routes approved by the Engineer. Millings, sand, or other approved materials may be used on adjacent surfaces to absorb and therefore minimize tracking of the materials applied during the course of construction. Materials used for absorption shall be maintained for the duration of the project. Upon completion of material applications, clean and dispose of absorption material in accordance with federal, state, and local regulations. This will not be paid for directly but shall be considered subsidiary to various bid items of the contract.
- 11. Assume ownership for all designated waste material and dispose of properly according to all State and Federal rules and regulations.
- 12. Control the dust and tracking caused by construction operations.
- 13. Quality Control for this project will be provided by **Raba Kistner**. The contractor will contract with Raba Kistner to sample and field test base and asphalt materials in accordance with the test methods provided for, under the appropriate standard specifications for the various items. It is the responsibility of the Contractor to schedule testing with the lab at least 48 hours in advance. If the Contractor schedules quality testing and cancels services, the contractor will be responsible for any charges that occur for cancellation. The payment for the Quality Services will be paid for based on submitted invoices. Invoices submitted to the County for Payment will not be allowed to have any markup.
- 14. If overhead or underground power lines need to be de-energized, contact the electrical service provider to perform this work. Costs associated with de-energizing the power lines or other protective measures required are at no expense to the County. If working near power lines, comply with the appropriate sections of Texas State Law and Federal Regulations relating to the type of work involved.
- 15. Material on hand will not be paid for.
- 16. Anything deemed by the Contractor to be temporarily moved for the work will be done at the approval of the County and will not be paid for directly but will be considered subsidiary to various bid items.
- 17. Maintain adequate drainage throughout the limits of the project during all construction phases. Any dewatering will be responsibility of the Contractor and will be subsidiary to various bid items.
- 18. Construct paving to the grades shown on the plans. Mark all proposed grades at the edges of the asphalt and at grades breaks. Any discrepancies or issues shall be brought to the attention of the County.

- 19. Verify material quantities and dimensions prior to ordering materials.
- 20. Computation for bid quantities will be available upon contractor's request.
- 21. The Contractor will establish the project control point, points, or tangency, PI's (points of intersection), point of curvature (PC, PI, and PT) and bench marks at the beginning and end of the project on the plan view only. Contractor shall establish and maintain these points throughout construction. There will be no separate payment for this work, but it shall be considered subsidiary to various bid items.
- 22. Schedule work so as to prevent undue delay caused by wet weather.
- 23. When design details are not shown in the plans, provide barricades and temporary fencing conforming to the latest "Standard Highway Sign Designs for Texas" manual.
- 24. All materials, labor and incidentals required for the contractor to provide for traffic across site for temporary ingress and egress shall be furnished by the contractor at no additional cost to the County and shall be considered as incidental to the various bid items.
- 25. The Contractor will notify the Engineer 48 hours in advance of expected completion of the cement stabilized base work. The Engineer will inspect the base, receive quality testing and approve of the base prior to the placement of asphalt.
- 26. Contractor shall perform any handwork necessary around bollards, fire hydrants, utility islands, light pole foundations, flush utility pads, electrical box pads, existing concrete sidewalks/driveways, building foundations, etc. to attain the design section. The hand work necessary will not be paid for directly but will be subsidiary to all of the applicable bid items.

Bid Item Notes:

ITEM 5: CONTROL OF WORK

1. Station/mark the project and verify locations of work and area slopes with Engineer prior to the commencing of work. Mark ground elevations as noted on the plans. Maintain grades/slopes throughout the duration of the project. Consider this work to be subsidiary to the various bid items of the contract. Provide all surveying for the control of work.

ITEM 7: LEGAL RELATIONS AND RESPONSIBILITIES

- 1. Furnish all materials, labor and incidentals required to provide for traffic across the street and for temporary ingress and egress to private property in accordance with article 7.7 of the standard specifications at no additional cost to the County. Consider this work to be subsidiary to the various bid items of the contract.
- If needed, maintain the roadway slope stability. Temporary retaining structures or shoring may be required.
 Before installing any proposed temporary retaining structures or shoring, secure written approval. Submit
 design calculations, working drawings and a plan of operations including sequencing. Maintaining slope
 stability is subsidiary to the various bid items.

ITEM 8: PROSECUTION AND PROGRESS

- 1. Compute and charge working days in accordance with Article 8.3.1.5., "Calendar Day".
- 2. Gather information and direct attention to the aspects of adjoining projects that may be in the progress during the construction of a portion of this project. Plan and prosecute the sequence of construction and the traffic control plan with adjacent construction projects so as not to interfere with or hinder the completion of the work in progress on the adjoining projects. Coordinate projects to ensure an uninterrupted flow of traffic.

ITEM 9: MEASUREMENT AND PAYMENT

- 1. All items will be measured per TXDOT Specifications unless otherwise noted.
- 2. The Contractor shall submit all tickets, As-Built drawings and an updated schedule with each pay request.
- 3. The County will withhold a 10% retainage from each pay request.

ITEM 110 – EXCAVATION

- 1. Material generated from excavation activities, free from contaminants, shall be hauled and stockpiled on site at a County designated location. Excavation shall be performed according the TXDOT Item 110.
- 2. Quantity of this Item shown in the plans, only includes the quantity of material for this bid item. Excavation for this item is a plan quantity. Any other excavation (hand or machine) quantities will be subsidiary to other applicable bid items.
- 3. Hauling and stockpiling of all excavated materials will be subsidiary to this or other bid items.
- 4. After excavation, proof roll the surfaces to be cement stabilized. Proof rolling will not be paid for directly but shall be considered subsidiary to various bid items of the contract.

ITEM 251: REWORK BASE COURSES -

After excavation of the surface materials, scarify existing Midway Area remaining surface and existing base
materials to the depth shown on the plans and specifications and according to TXDOT Item 251. Scarify and
perform any grading, watering, etc. of the surface necessary for prep for Cement Stabilization of base.
Materials may include limestone, asphalt and clay materials. See Geotech Report included as an attachment
to this document.

ITEM 275: CEMENT TREATMENT (ROAD-MIXED)

- 1. This item shall be performed according to TXDOT item 275 and will include all necessary work for cement application, including but not limited to mixing of the cement into the existing material at the rate shown on the plans, compacting, watering to maintain moisture, grading and microcracking. Cement applied shall be in slurry form
- 2. Geotech shall test and approve of the Cement treated base prior to placement of prime.

BID ITEM 300 – AEP PRIME

- 1. Prime shall not be applied until the base prep has been reviewed and approved by the Geotechnical Engineer and the County Engineer.
- 2. Prime Coat shall be AEP. Distribute Prime smoothly and evenly at an estimated rate of 0.25 gallons per square yard. Actual amount used will be adjusted as necessary in the field according to conditions and in consultation with the County Engineer. Prime will be paid for by the gallon applied and paid by ticket.

ITEM 340 - DENSE-GRADED HOT-MIX ASPHALT (SMALL QUANTITY)

- 1. Type "C" Dense Graded Hot Mix Asphalt shall be placed according to the plans and specifications according to TXDOT Item 340. The use of RAP materials in the mix design will be allowed at a max of 20%. Asphalt binder shall be PG 70-22.
- 2. Contractor shall provide and place tack where new asphalt is placed against on sides of concrete slabs, foundations, sidewalks, driveway, other concrete structures, or asphalt driveways and any other location required by good practices. This shall not be paid for directly but will be subsidiary to this bid item.
- 3. Contractor shall protect existing concrete surface from oil and staining from the new prime and asphalt placement. This shall not be paid for directly but will be subsidiary to this bid item.

ITEM 351: SOFT SPOT SUBGRADE REPAIR (ONLY AS DIRECTED BY ENGINEER)

1. Repair soft subgrade areas only as directed by the Engineer. Identified soft spots shall be excavated a minimum 9 inches and backfilled and compacted in lifts with TXDOT limestone base. This item may or may not be used.

ITEM 500: MOBILIZATION

- 1. Establish and remove offices, plants, and facilities. Move personnel, equipment, and supplies to and from the project or the vicinity of the project site to begin work or complete work on Contract Items. Bonds and insurance are required for performing mobilization.
- 2. Mobilization shall not exceed three (3) percent of the total construction items amount prior to the cost of mobilization being added.

ITEM 502: BARRICADES AND TRAFFIC/PEDESTRIAN HANDLING

- 1. Furnish and maintain safety fencing to the limits shown on the plans during the entire duration of work. Secure safety fencing to existing fencing and hand rail as shown on the plans.
- 2. Contractor to place and maintain barricades to the limits shown on the plans from December 10 to December 14th for Doggett Ford Park Function. Barricades will be provided by Doggett Ford Park and the County.
- 3. Furnish and maintain the barricades and warning signs, including the necessary temporary and portable traffic control devices, during the various phases of construction. Place and construct these barricades and warning signs in accordance with the latest "Texas Manual on Uniform Traffic Control Devices for Streets and Highways" for typical construction layouts.
- 4. Furnish additional barricades and signs to maintain traffic and motorists' safety when directed by the

Engineer. Consider payment for these additional signs and barricades subsidiary to Item 502.

- 5. Cover work zone signs when work related to the signs is not in progress, or when any hazard related to the signs no longer exists.
- 6. Keep the delineation devices, signs, and pavement markings clean. This work is subsidiary to the Item, "Barricades, Signs, and Traffic Handling".
- 7. Do not mount signs on drums or barricades, except those listed in the latest Barricades and Construction standard sheets.
- 8. Use traffic cones for daytime work only. Replace the cones with plastic drums during nighttime hours.
- 9. Construct all work zone signs, sign supports, and barricades from material other than wood unless approved by the engineer.
- 10. Galvanize steel supports if used. Aluminum posts, if used, shall meet the following minimum thickness requirements:

 Square Feet

 Minimum Thickness

Less Than 1.5 0.080 Inches

1.5 To 7.5 0.100 Inches

Greater Than 7.5

11. Any changes to the traffic control plan must be approved in writing by the Engineer. Submit the revised plan for approval to the Engineer.

0.125 Inches

- 12. The Contractor shall include a schedule of street closure dates in the Traffic Control Plan. Contact the Engineer and Doggett Ford Park 72 hours in advance of closures and detours.
- 13. It is the responsibility of the Contractor to notify the Engineers Office and Doggett Ford Park of work to be performed 48 hours in advance.
- 14. The approval by the engineer of the method and procedure the contractor plans to use to handle or detour traffic will not relieve the contractor of his responsibility for the protection of the traveling public.
- 15. Use drums or vertical panels instead of cones as traffic control devices.
- 16. The Contractor shall submit to the County, prior to start of any construction work, a hauling truck and construction vehicles route plan. This route plan shall show streets to be taken for trucks and vehicles either empty or hauling materials going in or out the construction areas scope of work. The Streets that are to be used as truck and vehicle routes shall be truck loads roadway bearing pavements. Upon approval of the Engineer, this truck routing plan will be strictly implemented. Any changes that is required as construction phases progresses will be reviewed and approved by the Engineer. This work will not be measured or paid for separately but will be considered subsidiary to this pay item.
- 17. Provide flaggers at each side-road intersection and ensure they have communication with the flaggers controlling the movement of traffic on the highway.

ITEM 506: TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL CONTROLS

- 1. This item will not be paid for directly but considered subsidiary to various bid items.
- 2. Temporary erosion, sediment and water control measures shall be required.
 - a. Erosion control logs are to be utilized at every inlet or discharge point within the affected areas of construction and should remain in place throughout the duration of construction.
 - b. Contractor will be responsible for removing dirt from the roads daily to prevent tracking.
 - c. Contractor shall police the construction area at the end of each day and remove and containerize all trash
 - d. Pumped stormwater shall be channeled through a rock berm, erosion control log or other method to help prevent excessive discharge of silt.

END OF DIVISION II
GENERAL NOTES AND BID ITEM NOTES

DIVISION III GOVERNING CONSTRUCTION SPECIFICATIONS

The governing construction specifications applicable to this work are the Texas Department of Transportation (TXDOT) 2014 Standard Specifications for Construction of Highways, Streets and Bridges as adopted by the State of Texas.

These items which are listed below and which are contained in the TX DOT 2014 Standard Specifications are hereby adopted and made part of the Contract Documents to the same extent as if they were herein reproduced in full subject to such modifications, revisions or supplements as may appear in the section entitled Special Provisions in these Contract Documents to follow:

STANDARD SPECIFICATIONS:

Adopted by the Texas Department of Transportations, November 1, 2014, Standard Specifications and any other related or referenced TXDOT Specifications in the listed specifications are incorporated into the Contract by reference.

Items 1–9	General Requirements and Covenants
Item 110	Excavation
Item 150	Blading
Item 152	Road Grader Work
Item 204	Sprinkling
Item 210	Rolling
Item 251	Reworking Base Courses
Item 275	Cement Treatment (Road Mixed)
Item 300	AEP Prime
Item 340	Dense Graded Hot-Mix Asphalt (Small Quantity)
Item 351	Subgrade Repair
Item 500	Mobilization
Item 502	Barricades, Signs and Traffic Handling
Item 506	Temporary Erosion, Sedimentation, and Environmental Controls

SPECIAL SPECIFICATIONS:

Special Specifications will supplement specifications applicable to the individual project, not covered by the Standard Specifications, if needed.

END OF DIVISION III GOVERNING CONSTRUCTION SPECIFICATIONS

AFFIDAVIT OF WARRANTY

CONTR	ACTOR:		
PROJEC	T: <u>Jefferson Co</u>	unty Doggett Park Midway Rehabilitation	
LOCATI	ON:		
WORK I	PERFORMED <u>:</u>		
FINAL C	CONTRACT AMOUNT: \$		
CONTR	ACT DATE:		
Docum		es to the OWNER and that all Work is in accordance with the Contract CONTRACTOR'S warranty and guarantee hereunder excludes defects or	
1)		oper maintenance or operation by persons other than the CONTRACTOR, Su other individual or entity for whom the CONTRACTOR is responsible; or	ıp-
2)	Normal wear and tear under	normal usage.	
Require the Cor resultin	ements (Plans and Specification entract between og from faulty Workmanship a through	ONTRACTOR, does hereby Guarantee and Warranty in accordance with the ns), all Labor and Materials on the said Project, and all work performed und AND JEFFERSON COUNTY and/or assign to be free from defected/or Materials for the Guarantee Period extending from Upon receipt of written notice from the OWNER or JEFFERSON COUNTY, it is and replace any property damaged therefrom occurring within the warrance of the property damaged therefrom occurring within the warrance of the property damaged therefrom occurring within the warrance of the property damaged therefrom occurring within the warrance of the property damaged therefrom occurring within the warrance of the property damaged therefrom occurring within the warrance of the property damaged therefrom occurring within the warrance of the property damaged therefrom occurring within the warrance of the property damaged therefrom occurring within the warrance of the property damaged therefore occurring within the warrance of the property damaged therefore occurring within the warrance of the property damaged therefore occurring within the warrance of the property damaged therefore occurring within the warrance of the property damaged therefore occurring within the warrance of the property damaged therefore occurring within the warrance of the property damaged the property da	er ts the
SIGNIN	G OFFICER:	DATE:	
PRINTE	D NAME:	TITLE	
Acknow	vledged by	, Notary Public.	
Printed	Name		
My Con	nmission expires:		

OFFER AND ACCEPTANCE FORM OFFER TO CONTRACT

To Jefferson County:

We hereby offer and agree to furnish the materials or service in compliance with all terms, conditions, specifications, and amendments in the Invitation for Bid and any written exceptions in the offer.

We understand that the items in this Invitation for Bid, including, but not limited to, all required certificates are fully incorporated herein as a material and necessary part of the contract.

The undersigned hereby states, under penalty of perjury, that all information provided is true, accurate, and complete, and states that he/she has the authority to submit this bid, which will result in a binding contract if accepted by Jefferson County.

	For clarification of this offer, contact:
Company Name	
Address	Name & Title
City State Zip	Phone Fax
Signature of Person Authorized to Sign	E-mail
Printed Name	

REQUIRED FORM

ACCEPTANCE OF OFFER

The Offer is hereby accepted for the following items: Jefferson County Doggett Park Midway Rehabilitation

The Contractor is now bound to sell the materials or services listed by the attached contract and based upon the Invitation for Bid, including all terms, conditions, specifications, amendments, etc., and the Contractor's Offer as accepted by Jefferson County.

This contract shall henceforth be referred to as Contract No. (IFB 24-065/MR), Jefferson County Doggett Park Midway Rehabilitation. The Contractor has not been authorized to commence any billable work or to provide any material or service under this contract until Contractor receives a purchase order and/or a notice to proceed from the Jefferson County Purchasing Agent.

COUNTERSIGNED:	
Jeff R. Branick, County Judge JEFFERSON COUNTY, TEXAS	Date
ATTEST:	
Roxanne Acosta Hellberg, County Clerk JEFFERSON COUNTY, TEXAS	Date

BIDDER: INSERT ALL ADDENDA BEHIND THIS PAGE.

PLEASE BE SURE TO COMPLETE, SIGN, ATTEST, AND DATE EACH ADDENDUM.

BIDDER: INSERT BID SECURITY BEHIND THIS PAGE.

BID FORM

Bid Item	TXDOT Item	Bid Item Description	Unit	Estimated Quantity	Unit Price	Extended Amount (Total for Line Item)
1	500	Mobilization (Max 3%)	LS	1	\$	\$
2	110	Excavation: Excavate existing surface and base – (2.25" Depth) Stockpile on Site	CY	2494	\$	\$
3	251	Reworking Base Course (8" Depth)	SY	39900	\$	\$
4	275	Cement Treated Subgrade (Site Mixed 8" Deep) 8% (SY)	SY	39900	\$	\$
5	300	AEP Prime (0.25 Gallons/SY)	GAL	9975	\$	\$
6	340	Dense Graded Hot- Mix Asphalt: 2 inches thick, PG 70- 22 (20% RAP Allowed)	TON	4608	\$	\$
7	351	Flexible Pavement Subgrade Repair	SY	400	\$	\$
8	502	Barricades and Traffic/Pedestrian Handling	LS	1	\$	\$
					TOTAL BID AMOUNT	\$

REQUIRED FORM

VENDOR REFERENCES FORM

Bidder: Please list at least three (3) companies or governmental agencies (preferably a municipality) where the same or similar products and/or services as contained in this specification package were recently provided.

REQUIRED FORM

REFERENCE ONE	
Government/Company Name:	
Address:	
Contact Person and Title:	
Phone:	Fax:
Email Address:	Contract Period:
Scope of Work:	
REFERENCE TWO	
Government/Company Name:	
Address:	
Contact Person and Title:	_
Phone:	Fax:
Email Address:	Contract Period:
Scope of Work:	
REFERENCE THREE	
Government/Company Name:	
Address:	
Contact Person and Title:	
Phone:	Fax:
Email Address:	Contract Period:
Scope of Work:	

SIGNATURE PAGE

As permitted under Article 4413 (32c) V.A.C.S., other governmental entities may wish to participate under the same terms and conditions contained in this contract (i.e., piggyback). In the event any other entity participates, all purchase orders will be issued directly from and shipped directly to the entity requiring supplies/services. Jefferson County shall not be held responsible for any orders placed, deliveries made or payment for supplies/services ordered by another entity. Each entity reserves the right to determine their participation in this contract.

Would Bidder be willing to allow other governmental entit same terms and conditions?	
This bid shall remain in effect for ninety (90) days from bid of and local sales tax (exempt).	opening and shall be exclusive of federal excise and state
The undersigned agrees, if this bid is accepted, to furnish any and upon the terms and conditions contained in the Invitati Specifications and all other items made a part of the accepted	on for Bid, Conditions of Bidding, Terms of Contract, and
The undersigned affirms that they are duly authorized to expartnership or individual has not prepared this bid in collus bid as to prices, terms or conditions of said bid have not been or agent to any other Bidder or to any other person(s) engage this bid. And further, that neither the Bidder nor their emp directly nor indirectly concerned in any pool or agreement on, nor to influence any person to bid or not to bid thereon.	sion with any other Bidder, and that the contents of this a communicated by the undersigned nor by any employee ged in this type of business prior to the official opening of loyees nor agents have been for the past six (6) months or combination to control the price of goods or services
Bidder (Entity Name)	Signature
Street & Mailing Address	Print Name
City, State & Zip	Date Signed
Telephone Number	Fax Number
E-mail Address	

REQUIRED FORM

CERTIFICATION REGARDING LOBBYING

Certification for Contracts, Grants, Loans, and Cooperative Agreements

The undersigned certifies, to the best of his or her knowledge and belief, that:

- 1. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of an agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
- 2. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.
- 3. The undersigned shall require that the language of this certification be included in the award documents for all subawards at all tiers (including subcontracts, subgrants, and contracts under grants, loans, and cooperative agreements) and that all subrecipients shall certify and disclose accordingly.

This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by section 1352, title 31, U.S. Code. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.

The Contractor, certifies or affirms the truthfulness and accuracy of each statement of its certification and disclosure, if any. In addition, the Contractor understands and agrees that the provisions of 31 U.S.C. Chap. 38, Administrative Remedies for False Claims and Statements, apply to this certification and disclosure, if any.

Signature of Contractor's Authorized Official
Name and Title of Contractor's Authorized Official (Please Print)
Date

REQUIRED FORM

CONFLICT OF INTEREST QUESTIONNAIRE

CONFLICT OF INTEREST QUESTIONNAIRE For vendor doing business with local governmental entity	FORM CIQ			
This questionnaire reflects changes made to the law by H.B. 23, 84th Leg., Regular Session.	OFFICE USE ONLY			
This questionnaire is being filed in accordance with Chapter 176, Local Government Code, by a vendor who has a business relationship as defined by Section 176.001(1-a) with a local governmental entity and the vendor meets requirements under Section 176.006(a).	Date Received			
By law this questionnaire must be filed with the records administrator of the local governmental entity not later than the 7th business day after the date the vendor becomes aware of facts that require the statement to be filed. See Section 176.006(a-1), Local Government Code.				
A vendor commits an offense if the vendor knowingly violates Section 176.006, Local Government Code. An offense under this section is a misdemeanor.				
Name of vendor who has a business relationship with local governmental entity.				
Check this box if you are filing an update to a previously filed questionnaire.				
(The law requires that you file an updated completed questionnaire with the applater than the 7th business day after the date on which you became aware that the origincomplete or inaccurate.)				
Name of local government officer about whom the information in this section is being discl	osed.			
Name of Officer				
This section (item 3 including subparts A, B, C, & D) must be completed for each officer with whom the vendor has an employment or other business relationship as defined by Section 176.001(1-a), Local Government Code. Attach additional pages to this Form CIQ as necessary. A. Is the local government officer named in this section receiving or likely to receive taxable income, other than investment income, from the vendor?				
Yes No				
B. Is the vendor receiving or likely to receive taxable income, other than investment income, from or at the direction of the local government officer named in this section AND the taxable income is not received from the local governmental entity?				
Yes No				
C. Is the filer of this questionnaire employed by a corporation or other business entity with respect to which the local government officer serves as an officer or director, or holds an ownership interest of one percent or more?				
Yes No				
D. Describe each employment or business and family relationship with the local government officer named in this section.				
4				
Signature of vendor doing business with the governmental entity	Date			

Adopted 8/7/2015

REQUIRED FORM

LOCAL GOVERNMENT OFFICER CONFLICTS DISCLOSURE STATEMENT – OFFICE USE ONLY

	LOCAL GOVERNMEN' CONFLICTS DISCLOS		FORM CIS
TI	nis questionnaire reflects changes mad	e to the law by H.B. 23, 84th Leg., Regular Session.	OFFICE USE ONLY
g	his is the notice to the appropriate overnment officer has become aware accordance with Chapter 176, Local	Date Received	
1	Name of Local Government Officer		
2	Office Held		
3	Name of vendor described by Sect	ions 176.001(7) and 176.003(a), Local Government	Code
4	Description of the nature and exter	nt of employment or other business relationship wi	ith vendor named in item 3
5		vernment officer and any family member, if aggreg eds \$100 during the 12-month period described by	
	Date Gift Accepted	Description of Gift	
	Date Gift Accepted	Description of Gift	
	Date Gift Accepted	Description of Gift	
		(attach additional forms as necessary)	
6	AFFIDAVIT	I swear under penalty of perjury that the above statement is that the disclosure applies to each family member (as defi Government Code) of this local government officer. I also covers the 12-month period described by Section 176.003(a)	ned by Section 176.001(2), Local acknowledge that this statement
		Signature of Local	Government Officer
	AFFIX NOTARY STAMP / SEAL ABOV	E	
	Sworn to and subscribed before me, by the of, 20, to c	eatify which, witness my hand and seal of office.	, this the day
	Signature of officer administering oath	Printed name of officer administering oath	Fitle of officer administering oath

Adopted 8/7/2015

THIS FORM IS FOR OFFICE USE ONLY

GOOD FAITH EFFORT (GFE) DETERMINATION CHECKLIST

Bidder in	tends to ut	ilize S	Subcontractors/Subconsultants i	n the fulfillment of this contract (if awarded).				
opportur Contractor minimum exceed t	nities, the or/Consulta n efforts th he goals of	followant, ant, ant shape the shape	wing checklist and supporting and returned with the Prime (ould be put forth by the Prime (fort" was made in soliciting HUBs for subcontracting documentation shall be completed by the Prime Contractor/ Consultant's bid. This list contains the Contractor/Consultant when attempting to achieve or the Prime Contractor/Consultant may extend his/her and what is listed below.				
		Dic	I the Prime Contractor/Consulta	int?				
□Yes	□ No	1.		isistent with standard and prudent industry standards, the smallest feasible portions, to allow for maximum in?				
□ Yes	□ No	2.	Notify in writing a reasonable number of HUBs, allowing sufficient time for effe participation of the planned work to be subcontracted?					
☐ Yes	□ No	3.	Provide HUBs that were genuinely interested in bidding on a Subcontractor, adequa information regarding the project (i.e., plans, specifications, scope of work, bonding and insurance requirements, and a point of contract within the Print Contractor/Consultant's organization)?					
□ Yes	□ No	4.	Negotiate in good faith with interested HUBs, and not reject bids from HUBs that qualify as lowest and responsive Bidders?					
□ Yes	□ No	5.	Document reasons HUBs were rejected? Was a written rejection notice, including the reason for rejection, provided to the rejected HUBs?					
□ Yes	□ No	6.	If Prime Contractor/Consultant has zero (0) HUB participation, please explain the reasons why.					
I				any pertinent documentation with your bid. eet to answer the above questions.				
Printo	ed Name of A	Autho	rized Representative	Signature				
		Titl	e -	Date				
<u>Bidder</u>		ompl	ete this form submission.					

NOTICE OF INTENT (NOI) TO SUBCONTRACT WITH HISTORICALLY UNDERUTILIZED BUSINESS (HUB)

Bidder intends to utilize Subcontractors/Subconsultants in the fulfillment of this contract (if awarded). Yes No						
	Instructions for Prime Contractor/Consultant: Bidder shall submit this form with the bid; however, the information below may be submitted after contract award, but prior to beginning performance on the contract.					
Please submit one form for each HUB Su conditions of your contract.	bcontractor/S	ubconsultant w	ith proper s	ignatures, per the terms and		
Contractor Name:				HUB: Yes No		
Address:						
Street	City	State	Zip			
Phone (with area code):		Fax (with a	area code):			
Project Title & No.:						
Prime Contract Amount: \$						
HUB Subcontractor Name:						
HUB Status (Gender & Ethnicity):						
Certifying Agency: Tx. Bldg & Procurement	: Comm. 🗆 Jef	ferson County	Tx Unified Ce	rtification Prog.		
Address: Street	City	Ctata	7in			
Street	City	State	Zip			
Phone (with area code):		Fax (with a	area code):			
Proposed Subcontract Amount: \$		Percenta	age of Prime C	Contract: %		
Description of Subcontract Work to be Performed	l:					
Printed Name of Contractor Representative	Ciana	iture of Representativ	<u> </u>	 Date		
rinited Name of Contractor Representative	Signa	iture or nepresentativ	·C	Date		
Printed Name of HUB	Signa	ture of Representativ	 Date			

Note: Nothing on this Notice of Intent Form is intended to confer any rights, expressed or implied, to any third parties.

Pre-Approval for Subcontractor Substitutions must be obtained from the Jefferson County Purchasing Agent's Representative. The "HUB Subcontractor/Subconsultant Change Form" must be completed and faxed to 409-835-8456.

REQUIRED FORM

HISTORICALLY UNDERUTILIZED BUSINESS (HUB) SUCONTRACTING PARTICIPATION DECLARATION FORM

PAGE 1 OF 4 Bidder intends to utilize Subcontractors/Subconsultants in the fulfillment of this contract (if awarded). Yes No HUB: Yes No Prime Contractor: HUB Status (Gender & Ethnicity): Address: City State Zip Phone (with area code): Fax (with area code): IFB/RFP No.: Project Title & No.: Total HUB Subcontract(s): \$ **Total Contract:** 12.6% WBE: _____ Construction HUB Goals: 12.8% MBE:: % Sub-goals: 1.7 African-American, 9.7% Hispanic, 0.7% Native American, 0.8% Asian American. Use these goals as a guide to diversify. FOR HUB OFFICE USE ONLY: Verification date HUB Program Office reviewed and verified HUB Sub information Initials: PART I. HUB SUBCONTRACTOR DISCLOSURE **HUB Subcontractor Name:** HUB Status (Gender & Ethnicity): Texas Bldg & Procurement Comm. Texas Unified Certification Prog. Certifying Agency: Address: City State Zip Contact person: Title: Fax (with area code): Phone (with area code): Proposed Subcontract Amount: Percentage of Prime Contract: % \$ Description of Subcontract Work to be Performed:

REQUIRED FORM

HISTORICALLY UNDERUTILIZED BUSINESS (HUB) SUBCONTRACTING PARTICIPATION DECLARATION FORM

PAGE 2 OF 4

HUB Subcontractor Disclosure

PART I: Continuation Sheet (Duplicate as Needed)

HUB Subcontractor	Name:				
HUB Status (Gender	& Ethnicity):				
Certifying Agency:	☐ Tx. Bldg &	Procurement Comm		Tx Unified Certification Prog.	
Address:					
	Street	Cit	y State	Zip	
Contact person:			Title:		
Phone (with area co	de):		Fax (wit	h area code):	
Proposed Subcontra	ct Amount:	\$	Perce	ntage of Prime Contract:	%_
Description of Subco	ontract Work to b	pe Performed:			
Description of Subco	ontract Work to b	oe Performed: _			
Description of Subco	ontract Work to b	oe Performed: _			
		pe Performed: _			
Description of Subco	No.	_			
	Name:	-			
HUB Subcontractor	Name: & Ethnicity):				
HUB Subcontractor	Name: & Ethnicity):				
HUB Subcontractor HUB Status (Gender Certifying Agency:	Name: & Ethnicity):				
HUB Subcontractor HUB Status (Gender Certifying Agency:	Name: & Ethnicity): Tx. Bldg &	Procurement Comm	Jefferson County y State	Tx Unified Certification Prog.	
HUB Subcontractor HUB Status (Gender Certifying Agency: Address:	Name: & Ethnicity): Tx. Bldg &	Procurement Comm	Jefferson County y State Title:	Tx Unified Certification Prog.	
HUB Subcontractor HUB Status (Gender Certifying Agency: Address: Contact person:	Name: & Ethnicity): Tx. Bldg & Street de):	Procurement Comm	y State Title:	Tx Unified Certification Prog.	
HUB Subcontractor HUB Status (Gender Certifying Agency: Address: Contact person: Phone (with area co	Name: & Ethnicity): Tx. Bldg & Street de): ct Amount:	Procurement Comm	Jefferson County y State Title: Fax (wit	Tx Unified Certification Prog. Zip h area code):	%

All HUB Subcontractor Participation may be verified with the HUB Subcontractor(s) listed on Part I.

REQUIRED FORM

HISTORICALLY UNDERUTILIZED BUSINESS (HUB) SUCONTRACTING PARTICIPATION DECLARATION FORM

PAGE 3 OF 4

PART II: STATEMENT OF NON-COMPLIANCE FOR NOT MEETING HUB SUBCONTRACTING GOALS Instructions to Bidder: Please complete Good Faith Effort (GFE) Checklist and attach any supporting documentation. Our firm was unable to meet the HUB goals for this project for the following reasons: All Subcontractors to be utilized are "Non-HUBs." (Complete Part III) HUBs were solicited but did not respond. HUBs solicited were not competitive. HUBs were unavailable for the following trade(s): Other: Yes ☐ No Was the Jefferson County HUB Office contacted for assistance in locating HUBs? PART III: DISCLOSURE OF OTHER "NON-HUB" SUBCONTRACTS The Bidder shall use this area to provide a listing of all "Non-HUB" Subcontractors, including suppliers, that will perform under this project. A list of those "Non-HUB" Subcontractors the Bidder selects, after bid submission, shall be provided to the Purchasing Office not later than five (5) calendar days after being notified that Bidder is the apparent low Bidder. A list of those "Non-HUB" Subcontractors that are selected after contract award must be provided immediately after their selection. Subcontractor Name: Address: Street City State Title: Contact person: Fax (with area code): _____ Phone (with area code): Percentage of Prime Contract: \$ Proposed Subcontract Amount: Description of Subcontract Work to be Performed: Subcontractor Name: Address: City Street State Zip Contact person: Phone (with area code): Fax (with area code): Proposed Subcontract Amount: \$ Percentage of Prime Contract: Description of Subcontract Work to be Performed:

REQUIRED FORM

HISTORICALLY UNDERUTILIZED BUSINESS (HUB) SUBCONTRACTING PARTICIPATION DECLARATION FORM

Page 4	OF 4					
Subcontractor Name:						
Address:						
Street City	State Zip					
Contact person:	Title:					
Phone (with area code):	Fax (with area code):					
Proposed Subcontract Amount: \$	Percentage of Prime Contract:					
Description of Subcontract Work to be Performed:	·					
Subcontractor Name:						
Address:						
Street City	State Zip					
Contact person:	Title:					
Phone (with area code):	Fax (with area code):					
Proposed Subcontract Amount: \$	Percentage of Prime Contract:					
Description of Subcontract Work to be Performed:						
I hereby certify that I have read the <i>HUB Program Instructions</i> this form, and attached any necessary support documentation information on this document may result in my not receiving a	as required. I fully understand that intentionally falsifying					
Name (print or type):						
Title:						
Signature:						
Date:						
E-mail address:						
Contact person that will be in charge of invoicing for this project	t:					
Name (print or type):						
Title:	REQUIRED FORM					
Date:	Bidder: Please complete this form	ì				
E-mail address:	and include with bid submission.					

RESIDENCE CERTIFICATION/TAX FORM

Pursuant to	Texas Gover	nment Cod	de §2252.001	et seq.,	as amende	d, Jefferson	County r	equests	Resident
Certification.	§2252.001	et seq. of	the Governr	ment Cod	e provides	some restri	ctions on	the awa	arding of
governmenta	I contracts; p	ertinent pi	ovisions of §2	2252.001	are stated b	elow:			

	(3) "Non-resident Bidder" refers to a person who is not a resident.							
	(4) "Resident Bidder" refers to a person whose principal place of business is in this state, including a contractor whose ultimate parent company or majority owner has its principal place of business in this state.							
			ode §2252.001.		_ [company name] is a Resident Bidder of Texas as defined in			
	I certify that [company name] is a Nonresident Bidder as defined Government Code §2252.001 and our principal place of business is (city and state).							
Тахр	oayer I	dentificatio	n Number (T.I.N.)	:				
Com	pany l	Name subm	nitting bid/propos	al:				
Mai	ling ad	dress:						
If yo	u are a	an individua	al, list the names a	nd addresse	s of any partnership of which you are a general partner:			
Prop	erty:	List all tax	able property ov	vned by you	or above partnerships in Jefferson County.			
Jefferson County Tax Acct. No.* Property			Acct. No.*	Property a	ddress or location**			

- This is the property amount identification number assigned by the Jefferson County Appraisal District.
- ** For real property, specify the property address or legal description. For business property, specify the address where the property is located. For example, office equipment will normally be at your office, but inventory may be stored as a warehouse or other location.

REQUIRED FORM

Bidder: Please complete this form and include with bid submission.

HOUSE BILL 89 VERIFICATION

					REQUIF <u>Bidder</u> :		FORM ase complet	te thi	s form
	 Date								
•	Notary Sig	gnati	ure						
Notary Seal									
duly sworn, did swear and	confirm that	the			•	ei 501	ii, wiio aite	ıbyr	ne being
			the	ahove-na	med n	erco	n, who afte	r hv r	ne heina
On this day of		20	, personal	ly appea	red				
Date									
Signature of Company Repres	sentative								
venture, limited partnership, owned subsidiary, majority-association that exist to make	owned subsid		-			-		_	-
2. "Company" means a for-p									
1. "Boycott Israel" means reaction that is intended to pendor with a person or entity do action made ordinary business	alize, inflict ec ing business i	onon n Isra	nic harm on, or	limit com	nmercia	l rela	tions specific	ally w	ith Israel,
Pursuant to Section 2270.002	2, Texas Gove	rnme	ent Code:						
2. Will not boycott Israel dur	ing the term o	f the	e contract.						
Does not boycott Israel cu	rrently; and								
name)	eby depose a	nd v	erify under oa	th that t			_	ly swo	orn by the
l,	, tł	ne	undersigned	represer	ntative	of	(company		business eretofore

and include with bid submission.

SENATE BILL 252 CERTIFICATION

On this day, I, Deborah L. Clark, Purchasing Agent for Jefferson County, Texas, pursuant to Texas Government Code, Chapter 2252, Section 2252.152 and Section 2252.153, certify that I did review the website of the Comptroller of the State of Texas concerning the listing of companies that is identified under Section 806.051, Section 807.051, or Section 2253.253 and I have ascertained that the below named company is not contained on said listing of companies which do business with Iran, Sudan, or any Foreign Terrorist Organization.


Company Name
IFB/RFP/RFQ number
Certification check performed by:
,
Purchasing Representative
Date

THIS FORM IS FOR OFFICE USE ONLY

BID AFFIDAVIT

The undersigned certifies that the bid prices contained in this bid have been carefully reviewed and are submitted as correct and final. Bidder further certifies and agrees to furnish any and/or all commodities upon which prices are extended at the price offered, and upon the conditions contained in the specifications and the Notice to Bidders.

STATE OF	COUNTY OF
BEFORE ME, the undersigned authority, a	Notary Public in and for the State of,
on this day personally appeared	, who
	(name)
after being by me duly sworn, did depose	and say:
"l,	am a duly authorized officer of/agent
(name)	
for	and have been duly authorized to execute the
foregoing on behalf of the said	·
(name	of firm)
the Bidder is not now, nor has been for t agreement or combination, to control the persons to bid or not to bid thereon."	siness prior to the official opening of this bid. Further, I certify that he past six (6) months, directly or indirectly concerned in any pool or e price of services/commodities bid on, or to influence any person or
Fax:	Telephone#
by:	
(print name)	
Signature:	
SUBSCRIBED AND SWORN to before me b	
this the day of	
REQUIRED FORM Bidder: Please complete this form and include with bid submission.	Notary Public in and for the State of



SCIENCE ENGINEERING, LTD.

GEOTECHNICAL, ENVIRONMENTAL, MATERIALS TESTING

GEOTECHNICAL INVESTIGATION

FOR

EVALUATION OF EXISTING PAVING ON FORD PARK PARKING LOT

IN

BEAUMONT, TEXAS

REPORT NUMBER: 19216

REPORTED TO:

JEFFERSON COUNTY ENGINEERING C/O SETEX CONSTRUCTION 1660 S. 23RD STREET BEAUMONT, TEXAS 77707

SEPTEMBER 2019

PREPARED BY: SCIENCE ENGINEERING, LTD.

P.O. Box 2048 / Nederland, Texas 77627 / Tel.: (409) 982-0686 or (409) 727-2218 (IFB 24-065/MR) Jefferson County Doggett Park Midway Rehabilitation Fax: (409) 982-0619 / e-mail: yousef@science-engineer.com

GEOTECHNICAL INVESTIGATION Evaluation of Existing Paving Beaumont, Texas

INTRODUCTION

The study reported herein is an investigation of subsurface conditions for the evaluation of existing paving at Ford Park Parking Lot in Beaumont, Texas.

AUTHORIZATION

This investigation was authorized by Mr. Rocky Smith by telephone on August 19, 2019.

SUBSURFACE EXPLORATION

The subsurface exploration at the site was accomplished by means of twenty (20) undisturbed sample core borings drilled to depths of approximately two (2) feet below existing ground surface. Approximate locations of the borings were flagged by Setex Construction, as shown on attached boring plan.

SUBSURFACE INVESTIGATION

The subsurface investigation consisted of drilling three-inch nominal diameter core borings. Undisturbed samples of the cohesive soils were obtained from the borings by means of thin-wall, seamless steel Shelby tube samplers, in accordance with the ASTM D–1587 method.

All undisturbed samples were extracted mechanically from the core barrels in the field, classified, wrapped in aluminum foil, and sealed in airtight plastic bags to prevent moisture loss and disturbance. The samples were transported to our laboratory for testing and further study.

LABORATORY INVESTIGATIONS

All samples from borings were examined and classified in the laboratory by a soil engineer, according to procedures outlined in ASTM D-2488. Laboratory tests were performed on selected soil samples in order to evaluate the engineering properties of the soil in accordance with the indicated standard procedures.

LABORATORY TESTS

Atterberg Limits (L.L., P. L., P.I.) Soils Classification

STANDARD TESTS

ASTM D-4318 ASTM D-2487

Atterberg limits tests were performed on appropriate cohesive samples. The results of these tests are shown on the attached boring logs.

SUBSURFACE CONDITIONS

Specific types and depths of subsurface strata encountered on the site are shown on the attached boring logs. Review of the boring logs indicates that generalized stratography is approximately as follows:

Stratum No.	Average Depth, feet	Description of Strata
I	0.10	Asphalt
II	0.60	Limestone Base
III	0.32	Lime Stabilized Subgrade

The near surface soils are "CH" type soils when classified by the unified soils classification system. This type soil normally exhibits high swell potential during seasonal moisture variations.

Hydrostatic water was not encountered at the time of drilling.

FINDINGS

- 1. Asphaltic concrete pavement thickness varies from 1.0 to 3.0 inches (weighted average is 1.20 inches).
- 2. Limestone Base thickness varies from 3.0 to 18.0 inches (weighted average is 7.2 inches).
- 3. Lime Stabilized Subgrade thickness varies from 0 to 11.0 inches (weighted average is 3.84 inches).
- 4. Soil Boring terminated on Dark Gray CLAY (CH).

RECOMMENDATIONS FOR REPAIR

The failing paving in the parking lot can be repaired as follows:

	Vehicle
Type Pavement	Traffic
Asphaltic Concrete	1.5"
Limestone Base	8.0"
Lime Stabilized Subgrade	6.0"

Subgrade preparation should consist of removing all existing asphalt and base. Then scarify the subgrade to a depth of six (6) inches and stabilize with six to eight (6-8) percent of hydrated lime. The soil-lime mixture should be compacted to a minimum of 95% of Standard Proctor Density (ASTM D-698). Lime stabilization should conform to Texas Highway Department 2014 Standard Specification Item 260, which describes material and construction methods for treatment of materials in place.

The base material should be compacted to 95% of the maximum dry unit weight as obtained in the laboratory by means of the ASTM D-1557 Procedure. The compacted limestone base should then be primed with 0.20 gallons per square yard of MC-1 cut back asphalt.

Hot mix asphalt concrete should be placed in accordance with the Texas Highway Department Item 340 Type D Modified, which describes materials, gradation and construction methods for Hot Mix Asphaltic Pavement.

Note: Existing base can be re-used provided that it be stabilized with 4% cement by weight, and re-compacted to 95% by modified proctor ASTM-1557.


LIMITATIONS

The conclusions and recommendations given in this report are based on the analysis of the data collected for this project. Additive conclusions or recommendations made from this data by others are their responsibility.

Our study is based on the data obtained from soil borings made at the locations shown on borings plan. The nature and extent of variations between borings may become evident during construction. We should be requested to observe exposed conditions. After making these observations, and noting the engineering significance of variations, we will advise you of any changes in recommendations believed appropriate.

We appreciate this opportunity to provide our services to this project. Please let us know if you require additional information. Thank you.

Respectfully submitted for the firm, TBPE Registration No. 4060



Yousef Rahmani, P.E. President

Encl.:

Boring Plan

Boring Logs 1 – 20

Geotechnical Chart/Symbols


Copies:

2 – Client

1- Jefferson County Engineering


1 – SEL File 19216

YR/nb



GEOTECHNICAL, ENVIRONMENTAL, MATERIALS TESTING


Report Number 19216



EVALUATION OF EXISTING PARKING LOT AT FORD PARK BEAUMONT, TEXAS


BORING PLAN SEPTEMBER 2019

NOT TO SCALE



GEOTECHNICAL, ENVIRONMENTAL, MATERIALS TESTING


							LOG	OF B	ORI	NG			_					_				
Proje	ect:	Eva	aluatio	n of Exist ont, Texa	ing Par	king Lot a	t Ford Park				45 . 4 5409											
Borin	ng Nu			nt, Texa	is	B-1	_		Dat	Proje e of R	ct No:	1921	9/20	10							_	
Loca	tion:			Flagge		Setex Cor	nstruction		Dat	e of B	oring:	08/2	8/20	19				_			_	
Dry A	Auge	r:		0	_ to	2	Feet		Au	thoriz	ation:	Mr. I	Randy	y Sı	mith	ı						
									(0)								SH	EAI	R ST	TREN	NG.	ГΗ
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	ST	ΓRAT	UM DE	SCRIPTIO	ON	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	(PI)	PERCENT PASSING	NO. 200 SIEVE	POCKET	PENETROMETER	(TSF)	UNCONFINED	COMPRESSIVE	STRENGTH (TSF)
	4.0.				Aspha	ılt													٠		0	S
	10			4"	Base																	
				Da	rk Gra	ay CLAY																
_ 1 -											89	27	62									
																						-
														_								
 - 2 -								CH						+		-			+			-
- 2 - 					Е	ottom a	2 feet															
				1.			ot encounte	ered														-
					duri	ng drillir	ıg.							+					+			-
				2.		hole dry	upon															
					com	pletion.								+		-			+		_	-
																			+			+
														1								
														+		-			+	_	_	-
														1					+			-
														_					1			
																			+	_		+
														-		+		_	+	_		-



GEOTECHNICAL, ENVIRONMENTAL, MATERIALS TESTING


						LOG OF B	ORI	NG			+			er en la				
Proje	ct:	Eva	aluatio	on of Exist	ing Parking Lot at F	ord Park					_							
Borir	g Ni			nt, Texa	8 B-2		Dat	Proje	ct No:	1921	6 (20)	10						_
Locat			,c1.	Flagge	d by Setex Const	truction	Date	e of R	eport:	09/0	9/20	19		_				
Dry A		r:		0	to 2	Feet	Au	thoriz	ation:	Mr. F	Rand	y Sr	nith			-		
												Τ			SHE	AR S	TREN	NGTH
			_				(%)	E)			×		(5	İ	DITE	ARS	IKE	vGIII
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	ST	TRATUM DES	CRIPTION	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	(P1)	PERCENT PASSING	NO. 200 SIEVE	POCKET	(TSF)	UNCONFINED	COMPRESSIVE STRENGTH (TSF)
	NO.			1".	Asphalt					_			ш		4 6		2	S
- 1				18"	Bottom at 2 Water was not during drilling Bore hole dry u completion.	encountered												
-]																		
		_												Sec.				

Fax: (409) 982-0619 / e-mail: yousef@science-engineer.com



GEOTECHNICAL, ENVIRONMENTAL, MATERIALS TESTING

					LOG OF E	BORI	NG							-	
Proje	ct:	Eva	luatio	n of Existi	ing Parking Lot at Ford Park										
Borin	ıg Nı			nt, Texa	B-3	Dat	Proje	ct No:	1921	6 (2010					_
Locat	ion:			Flagge	d by Setex Construction	Dat	e of B	eport: oring:	$\frac{09/0}{08/2}$	9/2019 8/2019					-
Dry A	Auge	r:		0	to 2 Feet	Au	thoriz	ation:	Mr. I	Randy S	mith		-		-
												SHE	AR S	TREN	NGTH
DEP TH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	ST	TRATUM DESCRIPTION	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX (PI)	PERCENT PASSING NO. 200 SIEVE		(TSF)		COMPRESSIVE STRENGTH (TSF)
	20				Asphalt										<u> </u>
	0000			7"]	Base										
 - 1 -				Da	rk Gray CLAY										
								90	30	60					
 - 2 -	/				СН						-				-
-					Bottom at 2 feet										
 				1.	Water was not encountered during drilling.										
				2.	Bore hole dry upon completion.										
					comprehen.									V	




GEOTECHNICAL, ENVIRONMENTAL, MATERIALS TESTING


				LOG OF B	ORI	NG						
Proje Borir Locat Dry	ng Nu	Bea	aumo	on of Existing Parking Lot at Ford Park ont, Texas B-4 Flagged by Setex Construction 0 to 2 Feet	Dat	e of R e of B	oring:	09/0 08/2	6 9/2019 8/2019 Randy S	mith		
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	STRATUM DESCRIPTION	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX (PI)	PERCENT PASSING NO. 200 SIEVE	ER	UNCONFINED Z COMPRESSIVE D STRENGTH (TSF)
 	00000	ALC: NO.		3" Asphalt 6" Base								
- 1 - - 1 - 				Dark Gray CLAY			86	27	59			
				Bottom at 2 feet 1. Water was not encountered during drilling. 2. Bore hole dry upon completion.								

P.O. Box 2048 / Nederland, Texas 77627 / Tel.: (409) 982-0686 or (409) 327 2228 (IFB 24-065/MR) Jefferson County Doggett Park Midway Rehabilitation

Fax: (409) 982-0619 / e-mail: yousef@science-engineer.com




1					LC	OG OF B	ORI	NG							-		
Proje	ct:	Eva	aluatio	n of Exist ont, Texa	ing Parking Lot at Ford F	ark											
Borin Locat Dry A	ion:	ımb			B-5 d by Setex Constructi to 2 Feet	ion	Date Date	e of R	oring:	09/0	6 9/2019 8/2019 Randy)	h	1177			_
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	ST	TRATUM DESCRI	PTION	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	PERCENT PASSING	NO. 200 SIEVE		PENETROMETER AS (TSF)		COMPRESSIVE DA HE STRENGTH (TSF)
	D.O.			2" .	Asphalt				1	I	H C	1		-		12	S C
	50000				Base												
- 1 - 	0000000			10"	Lime Stabilized Sub	grade											
				Da	rk Gray CLAY												
- 2 - 				1. 2.	Bottom at 2 feet Water was not enco during drilling.	CH untered											
				2.	Bore hole dry upon completion.												




GEOTECHNICAL, ENVIRONMENTAL, MATERIALS TESTING

						LOG OF B	ORI	NG			-								
Proje	ct:			n of Exist	ing Parking Lot at F	ord Park			0.7-000-00-0										\neg
Borir	g Ni			nt, Texa	B-6				ct No:			10							
Locat				Flagge	d by Setex Const	ruction	Date	e of R	eport: oring:	$\frac{09/0}{08/2}$	8/20	19							
Dry A	Auge	r:		0	to2I	eet	Aut	thoriz	ation:	Mr. I	Randy	Sn	nith	1			_		
															SHI	EAR S	TRE	NG	гн
			L				(%) _	E			×		()				T	.,0.	
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	ST	TRATUM DESC	CRIPTION	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	(PI)	PERCENT PASSING	NO. 200 SIEVE	POCKET	PENETROMETER (TSF)	UNCONFINED	COMPRESSIVE	STRENGTH (TSF)
	Q.D.			2" .	Asphalt								_		4	<u> </u>	13	0	S
	5000000	Francisco H			Base														
_ 1 _				Da	rk Gray CLAY							+					-		\dashv
	/											1							\dashv
	/								86	26	60								\exists
												_							
_ =						CII						+							
- 2 -						СН	<u> </u>					+				_			4
					Bottom at 2	feet													
				1.	Water was not during drilling.														
				2.	Bore hole dry u	non						+		_					_
					completion.	port				_		-		+		_			\dashv
					•							+		1					+
																			7
														_					
												+		+	-				4
_]																			+
														-					
														+	-				-
				The second second			-	-											




GEOTECHNICAL, ENVIRONMENTAL, MATERIALS TESTING

						LOG OF I	BORI	NG				-							
Proje	ct:			on of Exist ont, Texa	ing Parking Lot at F	ord Park													
Borin Locat Dry A	ion:	ımł		100	B-7 ed by Setex Cons	truction Feet	Date	Proje e of R e of B thoriz	eport:	09/0	9/20	19 19 y Si	mitl	1					_
															SH	EAR	STI	REN	GTH
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	ST	TRATUM DES	CRIPTION	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	(P1)	PERCENT PASSING	NO. 200 SIEVE	POCKET	PENETROMETER	(LSF)	COMPRESSIVE	STRENGTH (TSF)
	00			1"	Asphalt							_		_		Н ;	-	, ,	On .
-	000			6"	Base														
 	0.00			6"	Lime Stabilized S	Subgrade													
	///			Da	ark Gray CLAY														
						CH						1					+		
-					Bottom at 2	feet													
				1.	Water was not during drilling														
				2.	Bore hole dry to completion.	ıpon	-												
												+							
																	I		




							LOG OF B	ORI	NG								
Proje Borin Locat Dry A	ng Nu	Beamh	aumo	nt, Texa	ing Parkings B- d by Sete	8 x Cons		Date	e of Re	ct No: eport: oring: ation:	09/09	9/201 8/201	9	:h			
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT			И DES	CRIPTION	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	PERCENT PASSING	NO. 200 SIEVE	PENETROMETER AV	UNCONFINED	STRENGTH (TSF)
 	000				Asphalt Base												
 - 1- 	50000			<i>7</i> " I	Lime Stal	oilized S	Subgrade										
 				Da	rk Gray (CLAY											
- 2				1.		drilling le dry ι	encountered										




GEOTECHNICAL, ENVIRONMENTAL, MATERIALS TESTING


							LOG OF	BOR	ING											
Proje	ect:	Eva	aluatio	on of Exist ont, Texa	ing Parki	ng Lot at	Ford Park				1001	,								
Borir Locat Dry A	ion:	ımb]	B-9 tex Cons 2	struction Feet	Da	te of E te of E uthoriz	Boring	09/0	9/201 8/201	9	th						
								@							SI	IEAI	R ST	CRE	NG	ТН
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	ST	ΓRATU	M DES	6CRIPTION	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	PERCENT PASSING	NO. 200 SIEVE	POCKET	PENETROMETER	(TSF)	UNCONFINED	COMPRESSIVE	STRENGTH (TSF)
	5.0			1"	Asphalt								+		1	-	٢		0	S
	9000			7"	Base															
 - 1 -	0000			6"	Lime St	abilized	Subgrade													
	/			Da	rk Gray	CLAY														
_										90	27	63	+		-		-			_
 - 2 -	/					·	C	Н									1			_
					Во	ttom at	2 feet													
				1.		was no g drillin	t encountered g.													
				2.		ole dry	upon										-			-
					compl	etion.														
													_				4			
																_	+			\dashv
																	+		-111-	+
													-				+		_	-
																	_			-



							LOC	G OF E	ORI	NG			+		_	_		-	_			
Proje	ct:	Eva	luatio	n of Exist ont, Texa	ing Parki	ng Lot at	Ford Park												-			
Borir Locat Dry A	ion:	umł			В	s-10 tex Cons 2	struction Feet	-	Dat Dat Au	Proje e of R e of B thoriz	ct No: eport: oring: ation:	09/0	9/20	019 019 dy S	mitl	n						
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	ST	FRATU	ION	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	(PI)	PERCENT PASSING	NO. 200 SIEVE		TROMETER	(TSF)	UNCONFINED		STRENGTH (TSF)		
	DO			1"	Asphalt				-		-	1		0	П	4	Ь	Ь		ם	U_	S
 	000000			10'	' Base																	
 - 2 -				Da	rk Gray	CLAY		СН														
				1.	Water	ttom at was no	t encount	tered														
				2.	Bore h	ole dry etion.	upon															




Project: Evaluation of Existing Parking Lot at Ford Park Beaumont, Texas Boring Number: B-11 Location: Flagged by Setex Construction Dry Auger: O to 2 Feet Date of Report: 09/09/2019 Date of Report: 09/09/2019 Date of Report: 09/09/2019 Authorization: Mr. Randy Smith STRATUM DESCRIPTION STRATUM DESCRIPTION Project No: 19216 Date of Report: 09/09/2019 Date of Boring: 08/28/2019 Authorization: Mr. Randy Smith SHEAR STR HILL AND DATE OF THE PARK STR AUTHORIZATION DESCRIPTION DATE OF THE PARK STR STRATUM DESCRIPTION DATE OF THE PARK STR SHEAR STR SHEAR STR AUTHORIZATION DESCRIPTION DATE OF THE PARK STR SHEAR STR SHEAR STR AUTHORIZATION DESCRIPTION DATE OF THE PARK STR SHEAR STR AUTHORIZATION DESCRIPTION DATE OF THE PARK STR SHEAR STR SHEAR STR SHEAR STR SHEAR STR SHEAR STR SHEAR STR AUTHORIZATION DESCRIPTION DATE OF THE PARK STR SHEAR								LOG OF I	BORI	ING			_					-	
Boring Number: Location: Flagged by Setex Construction O to 2 Feet Date of Report: 09/09/2019 08/28/2019 Authorization: Mr. Randy Smith Mr. Randy Smith STRATUM DESCRIPTION O	Proje	ct:	Eva	luatio	n of Exist	ing Parki	ng Lot at	Ford Park											
STRATUM DESCRIPTION STRATUM DESCRIPTION 1" Asphalt 8" Base 1 PARTICLIMIT Dark Gray CLAY Dark Gray CLAY Bottom at 2 feet 1. Water was not encountered	Locat	ion:	ımł		Flagge	ed by Se	tex Cons	struction Feet	Dat Dat Au	e of R	eport:	09/0	9/201	9 9 Smi	ith				=
1" Asphalt 8" Base Dark Gray CLAY Et al.	н, ғеет	TO	'LE	/S PER FOOT	ST	TRATU	JM DES	SCRIPTION											STRENGTH (TSF)
1" Asphalt 8" Base Dark Gray CLAY 888 28 60 CH Bottom at 2 feet 1. Water was not encountered	DEPT	SYMB	SAMI	BLOM					WATE	DRY D	LIQUII	PLAST	PLAST	PERCE	NO. 200	OCKE	PENETI TSF)	JNCON	TREN
Dark Gray CLAY Bottom at 2 feet 1. Water was not encountered		20			1".	Asphalt													2 05
Bottom at 2 feet 1. Water was not encountered during drilling. 2. Bore hole dry upon	 	0000			8"	Base													
CH Bottom at 2 feet 1. Water was not encountered	- 1 -				Da	rk Gray	CLAY												
Bottom at 2 feet 1. Water was not encountered	 										88	28	60						
1. Water was not encountered	_ 2 _							CH						-					
1. Water was not encountered during drilling. 2. Bore hole dry upon completion.						Во	ttom at 2	2 feet											
2. Bore hole dry upon completion.					1.														
					2.			upon											




GEOTECHNICAL, ENVIRONMENTAL, MATERIALS TESTING

							LC	OG OI	F BC	ORI	NG									-			
Proje	ect:	Eva	aluatio	n of Exis	ting Park	ing Lot a	t Ford Pa	ark															
Borin Locat Dry	tion:	aml		Flagge		3-12 tex Cor 2	nstructi Feet	on		Dat Dat	Proje e of R e of B thoriz	eport: oring:	09/0	9/20	019	mitl						_	
	Τ									714	Inoriz	ation.	1411.1	Vario	ty 3.		-	CH	EAI	2 67	TRE	=	TII
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	S	ΓRΑΤΙ	JM DE	SCRIF	PTION		WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	(PI)	PERCENT PASSING	NO. 200 SIEVE		TROMETER				STRENGTH (TSF)
	0.0			1"	Asphal	t									_			-	4	٢		0	S
	0000			8"	Base																		
_ 1 _				1. 2.	Water durin	ettom at was no g drillir	t 2 feet oot encom	untered	СН														




				LOG OF	BORI	NG						
Proje	ct:	Eva	luatio	n of Existing Parking Lot at Ford Park				200000000000000000000000000000000000000				
Borir Locat Dry A	ion:	ımb		B-13 Flagged by Setex Construction 0 to 2 Feet	Dat	e of R e of B	oring:	09/0	6 9/2019 8/2019 Randy S	mith		
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	STRATUM DESCRIPTION	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX (P!)	PERCENT PASSING NO. 200 SIEVE	ER	UNCONFINED TA COMPRESSIVE D STRENGTH (TSF)
	74			1" Asphalt								
 	300			6" Base Dark Gray CLAY								
 							85	26	59			
- 2 -					CH							
				Bottom at 2 feet 1. Water was not encountered during drilling. 2. Bore hole dry upon completion.								




GEOTECHNICAL, ENVIRONMENTAL, MATERIALS TESTING

				LOG OF B	ORI	NG						
Projec	ct:	Eva	aluatio	on of Existing Parking Lot at Ford Park								
Borin	g Nı			B-14		Project R			9/2019	-		
Locati	ion:			Flagged by Setex Construction	Date	e of Bo	oring:	08/2	8/2019			
Dry A	uge	r:		0 to2 Feet	Aut	horiz	ation:	Mr. F	Randy S	mith		
											SHEAR S	TRENGTH
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	STRATUM DESCRIPTION	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX (PI)	PERCENT PASSING NO. 200 SIEVE	POCKET PENETROMETER (TSF)	ONFINED PRESSIVE NGTH (TSF)
	66			1" Asphalt								
	50.00 000			7" Base								
- 1 - 1 - 	00000000			11" Lime Stabilized Subgrade								
2 -				Dark Gray CLAY CH								
				Bottom at 2 feet								
 				 Water was not encountered during drilling. 								
				Bore hole dry upon completion.								




					LOG OF E	BORI	NG											
Proje	ect:			n of Exist	ing Parking Lot at Ford Park													
Borir Locat Dry A	tion:	umb			B-15 ed by Setex Construction to 2 Feet	Dat	Project of R of B of thoriz	eport: oring:	09/0	9/20 ⁰	19	mith	1					-
						(9)								SH	EAR	STR	ENC	- TH
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	ST	TRATUM DESCRIPTION	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	(P1)	PERCENT PASSING	NO. 200 SIEVE	POCKET	PENETROMETER	UNCONFINED	COMPRESSIVE	STRENGTH (TSF)
	P.D.			1"	Asphalt	_		-	H	-	_	П		Ь	P E	2 2	Ü	S
	00 00 00				Base											+		
 	A (0.00)			7"]	Lime Stabilized Subgrade													
				Da	rk Gray CLAY													
 - 2 -					СН													
 					Bottom at 2 feet													
	NAME OF THE PERSON OF THE PERS			1.	Water was not encountered during drilling.													
 				2.	Bore hole dry upon completion.													
				=														
																E		




GEOTECHNICAL, ENVIRONMENTAL, MATERIALS TESTING

							LOG OF I	BOR	ING			T								
Proje	ect:	Eva Bea	aluatio aumo	n of Exist ont, Texa	ing Parkir s	g Lot at I	Ford Park			ct No:	1921	6								
Borir					B-	16		Dat	e of R	eport:	09/0	9/2	019				-			-
Locat				Flagge	d by Set		truction	Dat	e of B	oring:	08/2	8/2	019							-
Dry A	Auge	r:		0	_ to _	2	Feet	Au	thoriz	ation:	Mr. I	Ranc	dy S	mitl	ı					
								(%)								SH	EAR	ST	REN	GTH
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	ST	TRATU	M DES	CRIPTION	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	(PI)	PERCENT PASSING	NO. 200 SIEVE	POCKET	PENETROMETER	(ISF)	ONCONFINED	STRENGTH (TSF)
	20			1.5	" Aspha	lt												+	2	S
	202			6"]	Base															
	8000			6"]	Lime Sta	bilized S	Subgrade													
				Da	rk Gray	CLAY														
 - 2 -	/						CI	I										+		
					Bot	tom at 2	feet													
				1.		was not drilling	encountered													
				2.	Bore he	ole dry ı	ıpon											+		
																		+		
																		_		
													-	_	-			+		-
														-	-			+		_
_]																		+		\dashv
																_	_			




GEOTECHNICAL, ENVIRONMENTAL, MATERIALS TESTING


								LOG	OF	BO	RI	NG						_		_				
Proje	ct:			n of Exist nt, Texa		ing Lot	at For	d Park	a .				et No:	1921	6									
Borir Locat Dry	ion:		er:	Flagge 0	d by Se	3-17 etex Co 2	nstrı Fe	action et		1	Date Date	of Re	eport: oring:	09/0 08/2 Mr. F	9/20 8/20	019	mith	ı					_	
											(%)								SH	EAI	R ST	REN	\G	ГН
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	ST	ΓRATU	JM Di	ESCI	RIPTI	ON		WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	(PI)	PERCENT PASSING	NO. 200 SIEVE	POCKET	PENETROMETER	(TSF)	UNCONFINED	COMPRESSIVE	STRENGTH (TSF)
	Ø!0			1"	Asphal	t									T						۲		<u> </u>	S
	0000			7"	Base																			
- ₁ -	8000			6"	Lime S	tabilize	ed Su	bgrade	е															
 				Da	rk Gra	y CLA	Y						87	26	6	1								
- 2 -									C	H														
					Во	ottom a	at 2 fe	eet																
				1.		r was i		ncount	ered															
				2.		hole di letion.	y up	on																



					LOG OF B	ORI	NG											
Proje	ect:	Eva Bea	aluatio aumo	n of Exist ont, Texa	ing Parking Lot at Ford Park			ct No:	1921	6								
Borin	ng Ni				B-18	Dat	e of R	eport	09/0	9/20	119					-		_
Locat				Flagge	d by Setex Construction	Dat	e of B	oring:	08/2	8/20	19							
Dry A	Auge	r:		0	to 2 Feet	Au	thoriz	ation	Mr.	Rand	ly Si	mith	1					_
						(%								SH	EAF	R ST	TRE	NGT
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	ST	TRATUM DESCRIPTION	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	(PI)	PERCENT PASSING	NO. 200 SIEVE	POCKET	PENETROMETER	(TSF)	UNCONFINED	COMPRESSIVE
	90			1"	Asphalt											٦		0
_	D C			5"	Base													
 - 1 -	20000			8"	Lime Stabilized Subgrade													
				Da	rk Gray CLAY													
	/																	
 - 2 -	/				СН													
					Bottom at 2 feet													
				1.	Water was not encountered during drilling.													
				2.	Bore hole dry upon completion.											1		
_					•													
															2000			
-																		
-																		
																I		




							LOG	OF B	ORI	NG											
Proje	ct:					ing Lot at I	Ford Park														
Borin	g Nı			nt, Texa		B-19			Dat	Proje e of R	ct No:	1921	6 /201	0		_	_				_
Locat			, ci.	Flagge		etex Cons	truction		Date	e of B	eport: oring:	08/2	9/201 8/201	9				_	_	_	_
Dry A		r:		0	to		Feet	•	Au	thoriz	ation:	Mr. I	Randy	Sn	nith	1	_	_	_		-
							12000						T	T			SH	EAI	2 67	DEN	- IGTH
			Т						I (%)	(F)			×		S		011	LIX		KLI	GIII
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	ST	RATU	UM DES	SCRIPTI	ON	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	(F1)	PERCENT PASSING	NO. 200 SIEVE	POCKET	PENETROMETER	(TSF)	UNCONFINED	COMPRESSIVE STRENGTH (TSF)
	DQ			1" .	Asphal	t											_	_	٦		2 0,
 				Da	rk Gra	y CLAY															
- 1 - 											90	28	62								
 - 2 -								СН													
					В	ottom at 2	2 feet							+							
				1.		r was not ng drilling		ered													
				2.		hole dry letion.	upon														
					•																
														+							
														+		\dashv		_	+	-	



GEOTECHNICAL, ENVIRONMENTAL, MATERIALS TESTING

				LOG C	F BOR	ING						
Proje	ct:	Eva	luatio	on of Existing Parking Lot at Ford Park								
Borir Locat Dry	ion:	umb		B-20 Flagged by Setex Construction 0 to 2 Feet	Dat	te of R	oring	09/0	6 9/2019 8/2019 Randy S	mith		
					(%)						SHEAR S	TRENGTH
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	STRATUM DESCRIPTION	MATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX (PI)	PERCENT PASSING NO. 200 SIEVE	POCKET PENETROMETER (TSF)	UNCONFINED COMPRESSIVE STRENGTH (TSF)
	an.			1" Asphalt				-	1 0	1 2		0 0
	0.00			6" Base								
 - 1 - 	200000			11" Lime Stabilized Subgrade								
 				Dark Gray CLAY	СН							
-				Bottom at 2 feet								
				Water was not encountered during drilling.	d							
				Bore hole dry upon completion.								
			-									




GEOTECHNICAL, ENVIRONMENTAL, MATERIALS TESTING


KEY TO SOIL CLASSIFICATION AND SYMBOLS



SOIL GRAIN SIZE

U.S. Standard Sieve





CON	SISTENCY OF	COHESIVE	SOILS			'E DENSITY ONLESS SOILS
Penetration Resistance, blows per foot 0 - 2 2 - 4 4 - 8 8 - 15 15 - 30 > 30	Consistency Very Soft Soft Firm Stiff Very Stiff Hard	Cohesion TSF 0 - 0.125 0.125 - 0.25 0.25 - 0.5 0.5 - 1.0 1.0 - 2.0 > 2.0	Plasticity Index 0 - 5 5 - 10 10 - 20 20 - 40 > 40	Degree of Plasticity None Low Moderate Plastic Highly Plastic	Penetration Resistance, blows per foot 0 - 4 4 - 10 10 - 30 30 - 50 > 50	Relative <u>Density</u> Very Loose Loose Medium Dense Dense Very Dense



GEOTECHNICAL INVESTIGATION

FOR

FORD PARK PAVING REHABILITATION

IN

BEAUMONT, TEXAS

REPORT NUMBER: 24102

REPORTED TO:

JEFFERSON COUNTY COURTHOUSE 1149 PEARL STREET, 5TH FLOOR BEAUMONT, TEXAS 77701

FEBRUARY 2024

PREPARED BY: SCIENCE ENGINEERING, LTD.

P.O. Box 2048 Nederland, Texas 77627 Ph: (409) 982-0686 Fax: (409) 982-0619 Email: yousef@science-engineer.com

GEOTECHNICAL INVESTIGATION

Evaluation of Existing Paving Beaumont, Texas

INTRODUCTION

The study reported herein is an investigation of subsurface conditions for the evaluation of existing paving at Ford Park Parking Lot in Beaumont, Texas.

AUTHORIZATION

This investigation was authorized by Ms. Michelle Falgout, P.E. by e-mail on January 10, 2024.

SUBSURFACE EXPLORATION

The subsurface exploration at the site was accomplished by means of nine (9) undisturbed sample core borings drilled to depths of approximately three (3) feet below the existing ground surface. The approximate locations of the borings are shown on the attached boring plan.

Note: Borings B-2 and B-5 were moved due to underground utilities, as shown on the boring plan.

SUBSURFACE INVESTIGATION

The subsurface investigation consisted of drilling three-inch nominal diameter core borings. Undisturbed samples of the cohesive soils were obtained from the borings by means of thin-wall, seamless steel Shelby tube samplers, in accordance with the ASTM D-1587 method.

All undisturbed samples were extracted mechanically from the core barrels in the field, classified, wrapped in aluminum foil, and sealed in airtight plastic bags to prevent moisture loss and disturbance. The samples were transported to our laboratory for testing and further study.

LABORATORY INVESTIGATIONS

All samples from borings were examined and classified in the laboratory by a soil engineer, according to procedures outlined in ASTM D-2488. Laboratory tests were performed on selected soil samples in order to evaluate the engineering properties of the soil in accordance with the indicated standard procedures.

Laboratory Test	ASTM Standard
Atterberg Limits [Liquid Limit (LL), Plastic Limit (PL), Plasticity Index (PI)]	D-4318
Soil Moisture Content	D-2216
Unconfined Compressive Strength	D-2166
Soils Classification	D-2487

Undrained shear strength of selective cohesive soils was determined by unconfined compression tests. Water content and dry unit weight of the foundation soils were determined as routine parts of the unconfined compression tests. Atterberg limits tests were performed on appropriate cohesive samples. The results of these tests are shown on the attached boring logs.

SUBSURFACE CONDITIONS

Specific types and depths of subsurface strata encountered on the site are shown on the attached boring logs. A review of the boring logs indicates that generalized stratography is approximately as follows:

Stratum No.	Average Depth, feet	Soil Description
ı	0.00 - 0.02	Asphalt
11	0.02 - 0.35	Limestone Base
Ш	0.35 - 3.00	Dark Gray CLAY (CH)

The near-surface soils are "CH" type soils when classified by the unified soils classification system. This type of soil normally exhibits high swell potential during seasonal moisture variations.

Hydrostatic water was not encountered at the time of drilling.

FINDINGS

- Asphaltic concrete pavement thickness varies from 0.0 to 0.50 inches (weighted average is 0.24 inches).
- Limestone Base thickness varies from 2.5 to 5.0 inches (weighted average is 3.96 inches).
- 3. Soil Boring terminated on Dark Gray CLAY (CH).

RECOMMENDATIONS FOR REPAIR

Due to our findings, which indicate paving is extremely weak, we recommend the entire parking lot be removed and replaced as follows:

Type Pavement	Vehicle Traffic
Asphaltic Concrete	1.5"
Limestone Base	8.0"
Engineering Fabric Tensar	BX 1200
Lime Stabilized Subgrade	6.0"

Subgrade preparation should consist of removing all existing asphalt and base. Then scarify the subgrade to a depth of six (6) inches and stabilize with eight to ten (8-10) percent of hydrated lime. The soil-lime mixture should be compacted to a minimum of 95% of Standard Proctor Density (ASTM D-698). Lime stabilization should conform to Texas Highway Department 2014 Standard Specification Item 260, which describes material and construction methods for the treatment of materials in place.

The base material should be compacted to 95% of the maximum dry unit weight as obtained in the laboratory by means of the ASTM D-1557 Procedure. The compacted limestone base should then be primed with 0.20 gallons per square yard of MC-1 cutback asphalt.

Hot mix asphalt concrete should be placed in accordance with the Texas Highway Department Item 340 Type D Modified, which describes materials, gradation, and construction methods for Hot Mix Asphaltic Pavement.

Note: Existing base can be re-used provided that it be stabilized with 4% cement by weight and re-compacted to 95% by modified proctor ASTM-1557.

LIMITATIONS

The conclusions and recommendations given in this report are based on the analysis of the data collected for this project. Additive conclusions or recommendations made from this data by others are their responsibility.

Our study is based on the data obtained from soil borings made at the locations shown on borings plan. The nature and extent of variations between borings may become evident during construction. We should be requested to observe exposed conditions. After making these observations, and noting the engineering significance of variations, we will advise you of any changes in recommendations believed appropriate.

We appreciate this opportunity to provide our services to this project. Please let us know if you require additional information. Thank you.

Respectfully submitted for the firm, TBPE Registration No. 4060



Yousef Rahmani, P.E. President

Encl.: Boring Plan

Boring Logs 1-9

Geotechnical Chart/Symbols


Copies: 1 – Client

1 - SEL File 24102

YR/nb



Report Number 24102



FORD PARK PAVING REHABILITATION BEAUMONT, TEXAS

BORING PLAN

FEBRUARY 2023

NOT TO SCALE



				LOG C	FBC	RIN	G								_		
Projec	:t:			Paving Rehabilitation	Mis it costs		000000000000000000000000000000000000000									_	
Boring	- Alur			nt, Texas B-1		D.	Proje	ct No:	24102	'000 A						_	
Locati		iinei		See Boring Plan		Da	ate of E	teport:	02/08/	2024						_	6
Dry A				0 to 3 Feet		Δ	uthori:	zation:	Ms N	Aichelle	Falo	out	PF				6
]	П						l lation.	1413.14	T	T	out,	_	IEAR S	TDE	MCT	
		П											311	EAN 3	T	401	
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	STRATUM DESCRIPTION		WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX (PI)	PERCENT PASSING	NO. 200 SIEVE	POCKET	PENETROMETER (TSF)	UNCONFINED	COMPRESSIVE	STRENGTH (TSF)
				0" Asphalt and 3" Base													
	/			Dark Gray CLAY													
	/				CH	37	80	78	27	51			0	.75		0.50)
_ 3 _		П		B							_				_	_	
- :-	e e	П		Bottom at 3 Feet							-		_		-		
		Ш		No water was encountered				-		-	+	_			-	_	_
		П		during drilling.	-						+	_	_		-	-	_
= =		Ш		during urining.				-		-	+-	-	_		-	_	_
-: :-		Ш		2. Bore hole dry upon							+				-	_	
		П		completion.							+				 -	_	
		Ш															
		Ш														_	
		П								_	+				-	_	_
		Ш									+				-		-
	i	Ш									1						
		Ш			l												
		Ш															
- 8-		Ш				-		-			+-				 	_	_
		Ш			-						+				├-	_	_
= =		Ш									\vdash	_			+-	_	_
	1	П														_	
		Ш															
		П									_				_	_	_
		Ш									+	_	-	_	╀	_	_
		Ш			1	V)					+				+-		
											1					_	
	,														L		_



				LOG OF	RUKIN	lG											
Projec	et:			Paving Rehabilitation		1											
Boring	. M			t, Texas	_		ect No:										
boring Locati		nber		B-2	Date of Report: 02/08/2024 Date of Boring: 02/01/2024 Authorization: Ms. Michelle Falgout, P.E.												
Dry At			() ,	See Boring Plan 0 to 3 Feet													
DIY A	iyer.		Ť	to 3 reet		Authori	zation:	IVIS. IV	/iicnelle i	-aigout,							
											SHEAR STRENG						
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	STRATUM DESCRIPTION	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX (PI)	PERCENT PASSING NO. 200 SIEVE	POCKET PENETROMETER (TSF)	UNCONFINED					
				0.25" Asphalt and 4.5" Base								30					
-	/		ı	Dark Gray CLAY								-					
بد ر				CI	1 36	87	80	27	53		0.65	0.80					
3 _		П	1		•			(100,54)									
8 %				Bottom at 3 Feet													
				No water was encountered	-	-		_									
-		Ш			-	-	-	_									
				during drilling.	-		-										
_				20 2 2 2 2			-										
				2. Bore hole dry upon													
		Ш		completion.													
-						_	_	_									
-		Н					-										
-		$ \ $					-										
-		П			-	-	-					-					
-		Н			-	-		_									
-		Ш			_	-	-		-								
-		H			-	-			_		_	-					
-		П			-	1											
-		Н				-			<u> </u>								
-		Ш															
-		Н										-					
	1																
	1																
_																	
_																	
_																	



				LOG O	F BC	DRIN	G											
Projec	:t:			c Paving Rehabilitation														
Boring	. Nun			at, Texas B-3				ct No:										
Locati		iber	•	See Boring Plan	Date of Report: 02/08/2024 Date of Boring: 02/01/2024													
Dry A				0 to 3 Feet						7ichelle	Falgo	ut	PF	-				
200	Ī	П							Taige	SHEAR STRENGTH								
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	STRATUM DESCRIPTION		WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX (PI)	PERCENT PASSING	NO. 200 SIEVE	8	INFINED PRESSIVE NGTH (TSF)				
				0" Asphalt and 3" Base														
	/			Dark Gray CLAY														
					CH	37	78	100	35	65			0.85	0.60				
_ 3 _																		
<u>-</u> 0 0-				Bottom at 3 Feet														
				No water was encountered														
				during drilling.														
				2. Bore hole dry upon														
				completion.							_							
н -					-						-		- 4					
-: :-											+							
		П																
											-	_						
						-				_	-							
											1							
		П																
											-	_						
											-	-						
									_									
					-					_	+-	- 1						
											-							



n		F203	1 D!	D :	D-L 1"		LOG			_										_	
Projec	t:				Rehabili	tation					100200										
Beaumont, Texas Boring Number: B-4											ect No:									_	
											Report:										
	ocation: See Boring Plan ry Auger: 0 to 3 Feet								Date of Boring: 02/01/2024 Authorization: Ms. Michelle Falgout, P.E.												
Dry Au	ıger:			0	to	3	Feet		Α	uthori	zation:	Ms. N	/liche	elle F	algo	out,	P.E.			_	
													T					EAR S	TREN	GTH	
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT			1 (1 mm) (1 mm) (1 mm) (1 mm)	ESCRIPTION		WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	(PI)	PERCENT PASSING	NO. 200 SIEVE	POCKET	(TSF)	UNCONFINED	COMPRESSIVE	
			ļ	0.3	25" Aspha	alt and	4.5" Base														
	/			Da	ark Gray	CLAY															
								CH	42	74	105	34	7	'1		-	0.	65	0.	40	
3			3(7.1)																		
					В	ottom a	at 3 Feet														
		Ш			1. No wa	ater wa	s encountered														
		Ш			during	drilling	g.														
		Н																			
_		Ш		2	2. Bore l		/ upon														
_		Н			comp	letion.															
		Н																			
													┡								
													⊢	_	_			_		_	
55 2 -		П											⊢	_	_			_		_	
		Н																	8.		
														- 1							
													L				0				
													⊢	- 1			,	_	_	_	
-									-				\vdash	-			_			_	
* =													\vdash		_		_	_		_	
0. S																				_	
																				_	
													-					_	_	_	
88 8-																		-		_	
-									-						-			-		_	
		1 1	- 1									-	-	_	_	_		_		_	



Beaumont, Tex Boring Number: Location: Dry Auger: 8 WB01	ing Rehabilitation												
Boring Number: Location: Dry Auger: 0	ZEX		Proio	ct No	2//102								
Depth, Feet Sample BLOWS PER FOOT	B-5	Project No: 24102 Date of Report: 02/08/2024 Date of Boring: 02/01/2024										-	
SYMBOL SAMPLE BLOWS PER FOOT	See Boring Plan											-	
SYMBOL SAMPLE BLOWS PER FOOT	0 to 3 Feet	A	uthoriz	ation:	Ms. N	lichelle l	Falgo	ut. P	.E.	_	_	_	
								T	SHEAR STRENGTH				
	STRATUM DESCRIPTION	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX (PI)	PERCENT PASSING	NO. 200 SIEVE	~			CUMPRESSIVE	
	0.5" Asphalt and 5" Base							_					
3	Dark Gray CLAY			-	.,,			\perp					
- 3	CH CH	40	75	95	30	65		4	0.6	5	0.	40	
										_		_	
	Bottom at 3 Feet							4		_		_	
	F						_	_		_			
	No water was encountered							_		_			
	during drilling.							_		_			
			_					_		-			
	Bore hole dry upon completion.		_	_				-		_		_	
	completion.		_			-	-	+		\dashv		_	
	ŀ							\dashv					
	T I							1					
	-							_		_			
	+							+		-			
	ŀ							+		\dashv		_	
	ŀ							\dashv		-			
	i i							\top					
	ļ.							+					
	ŀ					-		\dashv		-			
	ŀ							+		-			
	t t							+					
	†						-						
_													



						LOG	OF BC	RIN	G										_	
Projec	t:			Paving R	ehabilita	ation														\exists
Boring	Nlus			t, Texas		0.6		В		ct No:					_					80
Location		iber	*			R-6 ring Plan		Da Da	ite of F	Report: Boring:	02/08/	2024						_		0
Dry Au				0	to	3 Feet		A	uthori	zation:	Ms. N	liche	elle F	alac	ut.	P.F.				4
		П	1		_	0.53						Ī					AR S	TREM	NGT	н
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT			UM DESCRIPTION		WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	(PI)	PERCENT PASSING	NO. 200 SIEVE	POCKET	(TSF)	UNCONFINED	COMPRESSIVE	STRENGTH (TSF)
						and 4.75" Base												5		
	//			Dari	k Gray C	LAY	1200												_	
							CH	36	79	81	27	5	4		_	0.7	5).40	_
_ 3 _					Br	ottom at 3 Feet	3			_			_	_	_				-	\dashv
	2	П				atori de orio e e							-							\dashv
 				1.		ter was encountered drilling.	3													
				2.	Bore h	ole dry upon														
																				=



Project: Ford Park Paving Rehabilitation Beaumont, Texas Project No: 24102		
Boring Number: B-7 Date of Report: 02/08/2024 Location: See Boring Plan Date of Boring: 02/01/2024		
Dry Auger: 0 to 3 Feet Authorization: Ms. Michigan		PF
Autoritation: Mo: Mo:	l l l l l l l l l l l l l l l l l l l	SHEAR STRENGTH
STRATUM DESCRIPTION (%)	ASSING	
SYMBOL SAMPLE BLOWS PER FOOT BLOWS PER FOOT MOITAINSSAMPLE NATER CONTENT (%) PLASTIC LIMIT PLASTICITY INDEX	(PI) PERCENT PASSING NO. 200 SIEVE	POCKET PENETROMETER (TSF) UNCONFINED COMPRESSIVE STRENGTH (TSF)
0.12" Asphalt and 4.25" Base		
Dark Gray CLAY		
	6	0.75 0.40
Bottom at 3 Feet	_	
- Bottom at 3 Feet	4	
1. No water was encountered	-	
during drilling.		
F -		
2. Bore hole dry upon	-1	
Completion.		
II I	_	
	_	
	-	
F -		
├ ┤		
F - 		



							LOG ()FB(DRIN	G							374				
Projec	et:	For	d Park	Paving I	Rehabili	tation															
Boring	. Nue			it, Texas		B-8					ect No:										_
Locati		mei	•			oring Plan				ate of I										_	_
Dry A				0	to	3 Feet	-		υ c	ate of E authori	zation:	Ms N	/ZUZ4	اماله	Falor	ut	PF		_	_	_
i i		П										1410.11	T	-	Ligi	Juc,	_	HEAR	CTI	PENI	
			F00T		STRAT	'UM DESCRIP	TION		TENT (%)	Y (PCF)		E	INDEX		SSING	ш	11120				
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT		James Ments 22				WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	(PI)	PERCENT PASSING	NO. 200 SIEV	POCKET	PENETROME	(ISI)	COMPRESSIV	STRENGTH (TSF)
L _						t and 4" Base								esque,				- 117-			
_ = = =	//			Dai	k Gray (CLAY															
								СН	40	80	69	24	4	5			().65		0.4	40
_ 3 _																				_	
- : :-		Ш			В	ottom at 3 Feet											_		1		
		П			No ma		-26000 N						_	_	_		_		-		
		П		31.		iter was encou drilling.	nterea						-		_		_		+	_	
					uurnig	unning.					_		\vdash	-	_		_		+	_	
				2.	Rore h	nole dry upon							-	_	_		-		+	_	
					compl									- 7	-	-	_		+	-	
					· · · · · · ·									-		_	_	_	+		
								1											+		
								, i											1	_	
													\vdash					_	+	_	\dashv
									-				\vdash	-	_			_	╁		-
																			$^{+}$	_	
									_												
																			I		
													_	_		_	_		+	_	_
										_			\vdash	-	-	-	_		╁		-
																			+		\neg
													_						1		
														-		-	_		+	_	-
											, N					-			+	_	
								1											+		



					OG OF BO	RIN	G										_	_
Projec	t			k Paving Rehabilitation														
Boring	n Nun			nt, Texas B-9		ъ.		ect No:										-
Locati		inci	•	See Boring Plan	_			Report: Boring:								_	_	-
Dry A				0 to 3 Feet				zation:				Falor	ut.	PF	_			-
								T		T		I I	-	_	HEAR	STR	ENGT	- H
DEPTH, FEET	SYMBOL	SAMPLE	BLOWS PER FOOT	STRATUM DESCRIPT	ION	WATER CONTENT (%)	DRY DENSITY (PCF)	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX	(PI)	PERCENT PASSING	NO. 200 SIEVE		PENETROMETER (TSE)	NFINED	ш	
	4			0" Asphalt and 2.5" Base														
<u> </u>	//			Dark Gray CLAY	100													
					CH	34	82	81	27	5	4			0	.75	\perp	0.60)
_ 3 _				D-W 40 F	-											\perp		
- :-		П		Bottom at 3 Feet	-		_									\perp		
				• ••							_		_			4		
<u>-</u> -				No water was encoun	tered											\perp		
				during drilling.	-				_							1		
				2 Barakatat	-			_		_		l.				╄		
				2. Bore hole dry upon	-			_								╄		
				completion.	-	_		_		_	_					╄		_
					<u> </u>					_	_	Di-				╀		\dashv
					- 1			_			-	-				╁	_	\dashv
				!						\vdash	\exists	-			_	+		\dashv
						7.										\top	_	\neg
L _																		
- :-					_					_								
					-					<u> </u>	_	_		_		╄		\dashv
				1	-					_	\dashv	_	-		_	╁	_	\dashv
					- 1		_				\neg					\vdash		\dashv
					Ī						\neg						_	\dashv
					-											L		
					-	-	-				_		_			╄		\dashv
					+						\dashv		-		_	╁	_	\dashv
					-						-					\vdash		\dashv
					1						\dashv		\exists			+		\dashv
											\neg					\vdash		\dashv
		\perp																
								_										\neg





KEY TO SOIL CLASSIFICATION AND SYMBOLS



SOIL GRAIN SIZE

U.S. Standard Sieve





<u>C</u>	ONSISTENCY OF	COHESIVE SO	<u>DILS</u>			E DENSITY ONLESS SOILS
Penetration Resistance,		Cohesion	Plasticity	Degree of	Penetration Resistance,	Relative
blows per foot	Consistency	TSF	Index	Plasticity	blows per foot	Density
0 - 2	Very Soft	0 - 0.125	0 - 5	None	0 - 4	Very Loose
2 - 4	Soft	0.125 - 0.25	5 - 10	Low	4 - 10	Loose
4 - 8	Firm	0.25 - 0.5	10 - 20	Moderate	10 - 30	Medium Dense
8 - 15	Stiff	0.5 - 1.0	20 - 40	Plastic	30 - 50	Dense
15 -30	Very Stiff	1.0 - 2.0	> 40	Highly Plastic	> 50	Very Dense
> 30	Hard	> 2.0		1900.1		,

INDEX OF SHEETS

DESCRIPTION SHT NO.

- TITLE SHEET
- 2 **GENERAL NOTES & SPECIFICATIONS**
- 3 **GENERAL NOTES & SPECIFICATIONS**
- **GENERAL NOTES & SPECIFICATIONS**
- 5 **ESTIMATED QUANTITIES**
- EXISTING PLAN 6
- PROPOSED GRADING PLAN
- **DETAILS**
- FENCING AND BARRICADE PLAN

JEFFERSON COUNTY ENGINEERING DEPARTMENT

PLANS OF PROPOSED DOGGETT FORD PARK MIDWAY ASPHALT REHABILITATION



SCALE: NTS



10-23-2024

JEFFERSON COUNTY ENGINEERING DEPARTMENT

FAX: (409) 835-8718 PROJECT: DOGGETT FORD PARK

MIDWAY ASPHALT REHABILITATION

SHEET I OF 9 DRW'N. BY: G.K.

TITLE SHEET PROJECT LOCATION 'age 114**(**)f|122

DIVISION II GENERAL NOTES AND BID ITEM NOTES JEFFERSON COUNTY DOGGETT PARK MIDWAY REHABILITATION

General Notes

- 1. The Texas Standard Specifications 2014 will govern all specifications not directly addressed in this document.
- 2. Direct attention to comply with all ordinances and regulations of Jefferson County. A permit for this project will be required from the Jefferson County Environmental Control Department. A permit or permission for construction in the City of Beaumont drainage easement will also be required.
- 3. Temporary erosion, sediment and water control measures shall be required. Erosion control logs are to be utilized at every inlet or discharge point within the affected areas of construction and should remain in place throughout the duration of construction. Contractor will be responsible for removing dirt from the site roads daily to prevent tracking. Any concrete truck washout will be disposed of at the plant.
- 4. Procure all the necessary County permits and licenses before the start of this project. This will not be paid for directly but shall be considered subsidiary to various bid items of the contract.
- 5. Contractor is required to notify and request locates from the Texas One Call System prior to beginning any work. In Texas Call 811 or see the 811 website for information. Additional reference numbers are provided below

AT&T Communications Beaumont, Texas 77701 (409) 839-7030 Randall Jennings	Entergy Distribution North 11th Street Beaumont, Texas 77701 (409) 785-2136 Brian Cross	CenterPoint Energy/Entex 6090 College Street Beaumont, Texas 77707 (409) 860-7113 Tara Hunter
Spectrum 602 N. Hwy 69 Nederland, Texas 77627 (409) 720-5513 Michael Ward	Jefferson County Engineering Dept (409) 835-8584 Michelle Falgout	Doggett Ford Park Cak View Group (409)-291-0157 Lance Rosenberg
Jefferson County Precinct #4 (409)-273-3438 Milton Zachary	City of Beaumont City Engineer 409-880-3725 Molly Villareal	Doggett Ford Park Cak View Group Destin Deleon (409-499-8332

This action does not relieve the Contractor of the responsibilities under the terms of the contract or the plans and specifications. Damage caused by the Contractor's operations shall be repaired and restored to service in a timely manner at no expense to Jefferson County.

- 6. The approximate location of the known underground utility installations is as shown on the plans. Confirm the location of these utility lines and the exact location of any others which may exist. Assume full responsibility for notifying the utility involved in case of conflict or damage and he/she shall be responsible for damage that occurs due to his/her negligence. Remove and dispose of abandoned lines encountered that interfere with the construction of this project. Consider this work to be subsidiary to the various bid items of the contract.
- 7. Allow County forces to enter this project to accomplish such work as shown in the plans and as may be deemed necessary by the Engineer.
- 8. Maintain for the duration of this project, those sections of existing and proposed Midway areas, driveways, walkways, pavements and appurtenances which are to be constructed, reconstructed, modified, or remain in place under this project. Any portion of Midway areas, driveways, walkways, pavements and appurtenances damaged by the contractor's forces shall be repaired by the contractor at his/her expense. This shall include but is not limited to driveways, parking lots, fencing, gates, storm pipes, MH tops, area lighting poles, electrical boxes, water valves/hose bibs, underground electrical, sewer lines and cleanout, fire hydrants, bollards, misc. concrete pads, buildings etc. No payment will be made for this work. County forces will maintain the existing section of streets and its appurtenances not a part of this project except those sections damaged by the Contractor's forces shall be repaired by the Contractor at his entire expense
- 9. Place all equipment and vehicles not in operation behind barriers/fencing when not in use...
- 10. All truck traffic transporting materials to and from the project are to access and depart from the project site utilizing routes approved by the Engineer. Millings, sand, or other approved materials may be used on adjacent surfaces to absorb and therefore minimize tracking of the materials applied during the course of construction. Materials used for absorption shall be maintained for the duration of the project. Upon completion of material applications, dean and dispose of absorption material in accordance with federal, state, and local regulations. This will not be paid for directly but shall be considered subsidiary to various bid items of the contract.
- 11. Assume ownership for all designated waste material and dispose of properly according to all State and Federal rules and regulations.
- 12. Control the dust and tracking caused by construction operations.

- 13. Quality Control for this project will be provided by Raba Kistner. The contractor will contract with Raba Kistner to sample and field test base and asphalt materials in accordance with the test methods provided for, under the appropriate standard specifications for the various items. It is the responsibility of the Contractor to schedule testing with the lab at least 48 hours in advance. If the Contractor schedules quality testing and cancels services, the contractor will be responsible for any charges that occur for cancellation. The payment for the Quality Services will be paid for based on submitted invoices. Invoices submitted to the County for Payment will not be allowed to have any markup.
- 14. If overhead or underground power lines need to be de-energized, contact the electrical service provider to perform this work. Costs associated with de-energizing the power lines or other protective measures required are at no expense to the County. If working near power lines, comply with the appropriate sections of Texas State Law and Federal Regulations relating to the type of work involved.
- 15. Material on hand will not be paid for.
- 16. Anything deemed by the Contractor to be temporarily moved for the work will be done at the approval of the County and will not be paid for directly but will be considered subsidiary to various bid items.
- 17. Maintain adequate drainage throughout the limits of the project during all construction phases. Any dewatering will be responsibility of the Contractor and will be subsidiary to various bid items.
- 18. Construct paving to the grades shown on the plans. Mark all proposed grades at the edges of the asphalt and at grades breaks. Any discrepancies or issues shall be brought to the attention of the County.
- 19. Verify material quantities and dimensions prior to ordering materials.
- 20. Computation for bid quantities will be available upon contractor's request.
- 21. The Contractor will establish the project control point, points, or tangency Pl's (points of intersection), point of curvature (PC, Pl, and PT) and bench marks at the beginning and end of the project on the plan view only. Contractor shall establish and maintain these points throughout construction. There will be no separate payment for this work, but it shall be considered subsidiary to various bid items.
- 22. Schedule work so as to prevent undue delay caused by wet weather.
- 23. When design details are not shown in the plans, provide barricades and temporary fencing conforming to the latest "Standard Highway Sign Designs for Texas" manual.
- 24. All materials, labor and incidentals required for the contractor to provide for traffic across site for temporary ingress and egress shall be furnished by the contractor at no additional cost to the County and shall be considered as incidental to the various bid items.
- 25. The Contractor will notify the Engineer 48 hours in advance of expected completion of the cement stabilized base work. The Engineer will inspect the base, receive quality testing and approve of the base prior to the placement of asphalt.
- 26. Contractor shall perform any handwork necessary around bollards, fire hydrants, utility islands, light pole foundations, flush utility pads, electrical box pads, existing concrete sidewalks/driveways, building foundations, etc. to attain the design section. The hand work necessary will not be paid for directly but will be subsidiary to all of the applicable bid items.

Bid Item Notes:

ITEM 5: CONTROL OF WORK

1. Station/mark the project and verify locations of work and area slopes with Engineer prior to the commencing of work. Mark ground elevations as noted on the plans. Maintain grades/slopes throughout the duration of the project. Consider this work to be subsidiary to the various bid items of the contract. Provide all surveying for the control of work.

ITEM 7: LEGAL RELATIONS AND RESPONSIBILITIES

1. Furnish all materials, labor and incidentals required to provide for traffic across the street and for temporary ingress and egress to private property in accordance with article 7.7 of the standard specifications at no additional cost to the County. Consider this work to be subsidiary to the various bid items of the contract.

M. H. FALGOUT
73458

24

CENSE

CONTRACTOR

JEFFERSON COUNTY
ENGINEERING DEPARTMENT
JEFFERSON COUNTY COURTHOUSE
1145 PEARL STREET, 5TH FLOOR
BEAUHONT, TEXAS 77701
409) 853-8588 FAX: (4(9) 835-8718

PROJECT: DOGGETT FORD PARK
MIDWAY ASPHALT REHABILITATION

SHEET 2 OF 9

DRW'N. BY:
G.K.

GENERAL NOTES
AND SPECIFICATIONS
Page 115 0 122

(IFB 24-065/MR) Jefferson County Doggett Park Midway Rehabilitation

2. If needed, maintain the roadway slope stability. Temporary retaining structures or shoring may be required. Before installing any proposed temporary retaining structures or shoring, secure written approval. Submit design calculations, working drawings and a plan of operations including sequencing. Maintaining slope stability is subsidiary to the various bid items.

ITEM 8: PROSECUTION AND PROGRESS

- 1. Compute and charge working days in accordance with Article 8.3.1.5., "Calendar Day".
- 2. Gather information and direct attention to the aspects of adjoining projects that may be in the progress during the construction of a portion of this project. Plan and prosecute the sequence of construction and the traffic control plan with adjacent construction projects so as not to interfere with or hinder the completion of the work in progress on the adjoining projects. Coordinate projects to ensure an uninterrupted flow of traffic

ITEM 9: MEASUREMENT AND PAYMENT

- 1. All items will be measured per TXDOT Specifications unless otherwise noted.
- 2. The Contractor shall submit all tickets, As-Built drawings and an updated schedule with each pay request.
- The County will withhold a 10% retainage from each pay request.

ITEM 110 - EXCAVATION

- 1. Material generated from excavation activities, free from contaminants, shall be hauled and stockpiled on site at a County designated location. Excavation shall be performed according the TXDOT Item 110.
- 2. Quantity of this Item shown in the plans, only includes the quantity of material for this bid item. Excavation for this item is a plan quantity. Any other excavation (hand or machine) quantities will be subsidiary to other applicable bid items.
- 3. Hauling and stockpiling of all excavated materials will be subsidiary to this or other bid items.
- 4. After excavation, proof roll the surfaces to be cement stabilized. Proof rolling will not be paid for directly but shall be considered subsidiary to various bid items of the contract.

ITEM 251: REWORK BASE COURSES -

1. After excavation of the surface materials, scarify existing Midway Area remaining surface and existing base materials to the depth shown on the plans and specifications and according to TXDOT Item 251. Scarify and perform any grading, watering, etc. of the surface necessary for prep for Cement Stabilization of base. Materials may include limestone, asphalt and clay materials. See Geotech Report included as an attachment to this document.

ITEM 275: CEMENT TREATMENT (ROAD-MIXED)

- 1. This item shall be performed according to TXDOT item 275 and will include all necessary work for cement application, including but not limited to mixing of the cement into the existing material at the rate shown on the plans, compacting, watering to maintain moisture, grading and microcracking. Cement applied shall be in slurry form
- 2. Geotech shall test and approve of the Cement treated base prior to placement of prime.

BID ITEM 300 - AEP PRIME

- 1. Prime shall not be applied until the base prep has been reviewed and approved by the Geotechnical Engineer and the County Engineer.
- 2. Prime Coat shall be AEP. Distribute Prime smoothly and evenly at an estimated rate of 0.25 gallons per square yard. Actual amount used will be adjusted as necessary in the field according to conditions and in consultation with the County Engineer. Prime will be paid for by the gallon applied and paid by ticket.

ITEM 340 - DENSE-GRADED HOT-MIX ASPHALT (SMALL QUANTITY)

- 1. Type "C" Dense Graded Hot Mix Asphalt shall be placed according to the plans and specifications according to TXDOT Item 340. The use of RAP materials in the mix design will be allowed at a max of 20%. Asphalt binder shall be PG 70-22.
- 2. Contractor shall provide and place tack where new asphalt is placed against on sides of concrete slabs, foundations, sidewalks, driveway, other concrete structures, or asphalt driveways and any other location required by good practices. This shall not be paid for directly but will be subsidiary to this bid item.
- 3. Contractor shall protect existing concrete surface from oil and staining from the new prime and asphalt placement. This shall not be paid for directly but will be subsidiary to this bid item.

ITEM 351: SOFT SPOT SUBGRADE REPAIR (ONLY AS DIRECTED BY ENGINEER)

1. Repair soft subgrade areas only as directed by the Engineer. Identified soft spots shall be excavated a minimum 9 inches and backfilled and compacted in lifts with TXDOT limestone base. This item may or may not be used.

ITEM 500: MOBILIZATION

- 1. Establish and remove offices, plants, and facilities. Move personnel, equipment, and supplies to and from the project or the vicinity of the project site to begin work or complete work on Contract Items. Bonds and insurance are required for performing mobilization.
- 2. Mobilization shall not exceed three (3) percent of the total construction items amount prior to the cost of mobilization being added.

ITEM 502: BARRICADES AND TRAFFIC/PEDESTRIAN HANDLING

- 1. Furnish and maintain safety fencing to the limits shown on the plans during the entire duration of work. Secure safety fencing to existing fencing and hand rail as shown on the plans.
- 2. Contractor to place and maintain barricades to the limits shown on the plans from December 10 to December 14th for Doggett Ford Park Function. Barricades will be provided by Doggett Ford Park and the County.
- 3. Furnish and maintain the barricades and warning signs, including the necessary temporary and portable traffic control devices, during the various phases of construction. Place and construct these barricades and warning signs in accordance with the latest "Texas Manual on Uniform Traffic Control Devices for Streets and Highways" for typical construction layouts.
- 4. Furnish additional barricades and signs to maintain traffic and motorists' safety when directed by the Engineer. Consider payment for these additional signs and barricades subsidiary to Item 502.
- 5. Cover work zone signs when work related to the signs is not in progress, or when any hazard related to the signs no longer exists.
- 6. Keep the delineation devices, signs, and pavement markings clean. This work is subsidiary to the Item, "Barricades, Signs, and Traffic Handling".
- 7. Do not mount signs on drums or barricades, except those listed in the latest Barricades and Construction standard sheets.
- Use traffic cones for daytime work only. Replace the cones with plastic drums during nighttime hours.
- 9. Construct all work zone signs, sign supports, and barricades from material other than wood unless approved by the engineer.
- 10. Galvanize steel supports if used. Aluminum posts, if used, shall meet the following minimum thickness requirements:

Square Feet Minimum Thickness
Less Than 1.5
0.080 Inches
1.5 To 7.5
0.100 Inches
Greater Than 7.5
0.125 Inches

- 11. Any changes to the traffic control plan must be approved in writing by the Engineer. Submit the revised plan for approval to the Engineer.
- 12. The Contractor shall include a schedule of street closure dates in the Traffic Control Plan. Contact the Engineer and Doggett Ford Park 72 hours in advance of closures and detours.
- 13. It is the responsibility of the Contractor to notify the Engineers Office and Doggett Ford Park of work to be performed 48 hours in advance.
- 14. The approval by the engineer of the method and procedure the contractor plans to use to handle or detour traffic will not relieve the contractor of his responsibility for the protection of the traveling public.
- 15. Use drums or vertical panels instead of cones as traffic control devices.



JEFFERSON COUNTY
ENGINEERING DEPARTMENT
JEFFERSON COUNTY COURTHOUSE
1145 PEARL STREET, 5TH FLOOR
BEAUMONT, TEXAS 77701
FAX: (4(9) 835-8718

PROJECT: DOGGETT FORD PARK
MIDWAY ASPHALT REHABILITATION

SHEET 3 OF 9
DRW'N. BY:
G.K.

GENERAL NOTES
AND SPECIFICATIONS
Page 116707422

- 16. The Contractor shall submit to the County, prior to start of any construction work, a hauling truck and construction vehicles route plan. This route plan shall show streets to be taken for trucks and vehicles either empty or hauling materials going in or out the construction areas scope of work. The Streets that are to be used as truck and vehicle routes shall be truck loads roadway bearing pavements. Upon approval of the Engineer, this truck routing plan will be strictly implemented. Any changes that is required as construction phases progresses will be reviewed and approved by the Engineer. This work will not be measured or paid for separately but will be considered subsidiary to this pay item.
- 17. Provide flaggers at each side-road intersection and ensure they have communication with the flaggers controlling the movement of traffic on the highway.

ITEM 506: TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL CONTROLS

- 1. This item will not be paid for directly but considered subsidiary to various bid items.
- 2. Temporary erosion, sediment and water control measures shall be required.
 - a. Erosion control logs are to be utilized at every inlet or discharge point within the affected areas of construction and should remain in place throughout the duration of construction.
 - b. Contractor will be responsible for removing dirt from the roads daily to prevent tracking.
 - c. Contractor shall police the construction area at the end of each day and remove and containerize all trash
 - d. Pumped stormwater shall be channeled through a rock berm, erosion control log or other method to help prevent excessive discharge of silt.

END OF DIVISION II
GENERAL NOTES AND BID ITEM NOTES



JEFFERSON COUNTY
ENGINEERING DEPARTMENT
JEFFERSON COUNTY COURTHOUSE
II49 PEARL STREET, 5TH FLOOR
BEAUMONT, TEXAS 777.01

PROJECT: DOGGETT FORD PARK

MIDWAY ASPHALT REHABILITATION
SHEET 4 OF 9 SHEET

GENERAL NOTES
AND SPECIFICATIONS

CHK'D. BY:

Page 117 of 122

JEFFERSON COUNTY DOGGETT FORD PARK MIDWAY REHABILITATION PROJECT **QUANTITIES**

General Site Information

SQUARE YARDS OF SURFACE (SY) 39,900.0 **EXCAVATION (INCHES)** 2.25 LIME STABILIZATION (INCHES) 8.0 HMAC (INCHES) 2.00

	IIIOI ILO			2.00
Bid Item	TXDOT Item	BID ITEM DESCRIPTION	Estimated Quantities	Unit
1	500	MOBILIZATION (MAX 3%)	1	LS
		EXCAVATION		
		Excavate existing surface and base- (2.25" DEPTH)		
2	110	Stockpile on site	2494	CY
3	251	REWORKING BASE COURSE (8" DEPTH)	39900	SY
		CEMENT TREATED SUBGRADE (Site Mixed 8" deep)		
4	275	8% (SY)	39900	SY
_		AED DEME (0.05 OALL ONG/OV)	0075	0.41
5	300	AEP PRIME (0.25 GALLONS/SY)	9975	GAL
		DENSE CRADED HOT MIX ASPILALT		
6	340	DENSE GRADED HOT-MIX ASPHALT 2 inches thick, PG 70-22 (20% RAP Allowed)	4608	TON
			1990	
7	351	FLEXIBLE PAVEMENT SUBRADE REPAIR	400	SY
0	502	BARRICATES AND TRAFFIC/PEDESTRIAN HANDLING		
8	502	DAINIOATES AND THAIT IS/FEDESTINAN HANDEING	l l	LS




JEFFERSON COUNTY
ENGINEERING DEPARTMENT
JEFFERSON COUNTY COURTHOUSE
III49 PEARL STREET, 5TH FLOOR
BEAUMONT, TEXAS 77701
PHONE: (4.09) 835-8584
PROJECT: DOGGETT FORD PARK
MIDWAY ASPHALT REHABILITATION


SHEET 5 OF 9


QUANTITIES


(IFB 24-065/MR) Jefferson County Doggett Park Midway Rehabilitation

DRW'N. BY: G.K. 'age 11805122









- NOTES:

 1) SEE GEOTECHNICAL REPORTS FOR EXISTING MATERIALS INFORMATION.

 2) CONTRACTOR SHALL PERFORM ANY HAND WORK NECESSARY TO PROVIDE THE REQUIRED SECTIONS AROUND ALL UTILITY ISLAND AREAS, FIRE HYDRANTS, BOLLARDS, ELECTRICAL PADS, LIGHT POLE STANDS, BUILDING FOUNDATIONS, ETC.



JEFFERSON COUNTY
ENGINEERING DEPARTMENT
JEFFERSON COUNTY COURTHOUSE
II45 PEARL STREET, 5TH FLOOR
BEAUMONT, TEXAS 77701
PHONE: (409) 835-8584
FAX: (409) 835-8718
PROJECT: DOGGETT FORD PARK
MIDWAY ASPHALT REHABILITATION


DETAILS

Page 1210 122

SHEET 8 OF 9

DRW'N. BY: G.K. CHK'D. BY:

(IFB 24-065/MR) Jefferson County Doggett Park Midway Rehabilitation



NOTES:

1) CONTRACTOR TO PROVIDE ORANGE SAFETY FENCING TO THE LIMITS SHOWN. SAFETY FENCE TO REMAIN IN PLACE DURING ENTIRE PROJECT FROM MOB TO DEMOB.

2) CONTRACTOR TO PROVIDE TEMPORARY BARRICADES TO THE APPROXIMATE LIMITS SHOWN FOR RESERVED AREA FUNCTION. RESERVED AREA INCLUDES DRIVEWAYS @ AG BARNS AS NOTED.

PLAN-TEMPERARY FENCING AND BARRICADES SCALE: NTS



JEFFERSON COUNTY
ENGINEERING DEPARTMENT
JEFFERSON COUNTY COURTHOUSE
IIA5 PEARL STREET, 5TH FLOOR
BEAUMONT, TEXAS 77701
PHONE: (409) 835-8584
FAX: (409) 835-8718
PROJECT: DOGGETT FORD PARK
MIDWAY ASPHALT REHABILITATION

SHEET 9 OF 9 DRW'N. BY: G.K.

CHK'D. BY:

FENCING AND BARRICADE PLAN Page 12200 22

(IFB 24-065/MR) Jefferson County Doggett Park Midway Rehabilitation