



JEFFERSON COUNTY PURCHASING DEPARTMENT
Deborah L. Clark, Purchasing Agent

1149 Pearl Street
1st Floor, Beaumont, TX 77701

OFFICE MAIN: (409) 835-8593
FAX: (409) 835-8456

Addendum to IFB

IFB NUMBER: IFB 22-028/JW

IFB TITLE: Rehabilitation of Fuel Farm Pavement at the Jack Brooks Regional

IFB DUE BY: Airport **11:00 am CT, Wednesday, August 24, 2022**

ADDENDUM NO.: 2

ISSUED (DATE): August 17, 2022

To Bidder: This Addendum is an integral part of the IFB package under consideration by you as a Bidder in connection with the subject matter herein identified. Jefferson County deems all sealed bids to have been proffered in recognition and consideration of the entire IFB Specifications Package – *including all addenda*. For purposes of clarification, **receipt of this present Addendum by a Bidder should be evidenced by returning it (signed) as part of the Bidder's sealed bid submission**. If the bid submission has already been received by the Jefferson County Purchasing Department, Bidder should return this addendum in a separate sealed envelope, clearly marked with the IFB Title, IFB Number, and IFB Opening Date and Time, as stated above.

REASONS FOR ISSUANCE OF THIS ADDENDUM:

- **Clarifications (See Pages 1-4)**
- **REVISED PLAN SHEET NO. 3**
- **REVISED BID FORM PAGE 42 (REPLACEMENT PAGE)**

The information included herein is hereby incorporated into the documents of this present bid matter and supersedes any conflicting documents or portion thereof previously issued.

Receipt of this Addendum is hereby acknowledged by the undersigned Respondent:

ATTEST:

Authorized Signature (Respondent)

Witness

Title of Person Signing Above

Witness

Typed Name of Business or Individual

Approved by _____ Date: _____

Address

FB 22-028/JW ADDENDUM NO. 2

DATE: 8/10/2022

OWNER: Jefferson County/Jack Brooks Regional Airport

PROJECT: FB 22-028/JW Rehabilitation of Fuel Farm Pavement at Jack Brooks Regional Airport

TSG Project No: 2021-10-1092

DEADLINE FOR QUESTIONS: Email questions to Jamey West, Contract Specialist at jwest@co.jefferson.tx.us by **Thursday, August 18, 2022, at 5:00 p.m.**

SUBMITTAL DEADLINE: Bid date **Wednesday, August 24, 2022, at 11:00 a.m.**, Central Standard Time.

The additions, omissions, clarifications, and corrections herein shall be made to the contract documents, plans and specifications, for the Rehabilitation of Fuel Farm Pavement Project. **All Bidders must acknowledge receipt of this addendum on the appropriate section of the Bid Form and include with the Contract Documents.**

Addendum references to answer questions posted by potential bidders are summarized below.

1. CONTRACT TIME: Can the time of completion be revised to 45 or 60 calendar days? Given the phasing and access issues, 30 days is going to be difficult. **30 days is preferred timeframe. The access issues and project phasing concerns are clarified in section 5 of this addendum.**

Can we work Sundays? **Yes**

2. ALLOWANCE FOR STORM SEWER PIPE: Is the County going to provide an amount to input for the allowance? **No**

Without more information, it is very difficult to assess what is required. **A core sample taken during a geotechnical investigation indicated an accumulation of water beneath a section of the concrete panels. This accumulation of water is the likely cause of the panel failures. The purpose of the allowance is to provide compensation for the contractor to locate the source of the water accumulation and repair a broken water line if encountered. The onsite resident project representative (RPR) will work with contractor after the panels are removed to examine the area and resolve the issue before new concrete is placed.**

Addendum No. 2 - Page 1
(IFB 22-028/JW)

3. CONCRETE SLUMP/PUMPING: Can the max slump allowed be revised to 5" to 6" so we can pump the concrete? It would help speed up the schedule if pumping is allowed but the slump requirements would have to be modified.

No. The contract specifications apply as indicated in P-501-7 - Flexural strength. Test specimens shall be prepared in accordance with ASTM C192 and tested in accordance with ASTM C78. At the start of the project, the Contractor shall determine an allowable slump as determined by ASTM C143 not to exceed 2 inches (50 mm) for slip-form placement. For fixed-form placement, the slump shall not exceed 3 inches (75 mm). For hand placement, the slump shall not exceed 4 inches (100 mm)

4. CONCRETE FINISHING EQUIPMENT: Can you clarify what finishing equipment will be allowed? Is this area considered irregular?

This is considered irregular. Any appropriate equipment may be used as long as the concrete requirements are met, such as smoothness, etc.

A slip form paver cannot be used in this location. Would a vibratory screed be allowed?
Yes – as long as concrete as specified is achieved.

5. ACCESS: Please clarify the extent we must accommodate airport access. Will we have to shutdown work at anytime to allow planes to fuel, etc.?

This construction project shall take place outside of the Aircraft Operational Area (AOA). The contractor shall NOT access the AOA without the explicit permission of the airport owner. Further clarification on the possibility of accommodating fueling operations during the construction project includes the following:

- a. **Aircraft will not enter into the construction area.**
- b. **All construction equipment shall remain outside of the AOA.**
- c. **Fuel trucks will be used to provide fuel to aircraft in the AOA when needed.**
- d. **Fueling operations will cease during the concrete demolition phase of this project.**
- e. **In the event that emergency access to the fuel farm tanks is needed, or anticipated to be needed during this construction period, the airport owner and the engineer will coordinate with the contractor to phase the concrete placement in a manner that allows an emergency lane for fuel truck access. Emergency fueling operations will only use this temporary emergency lane after sufficient concrete curing has occurred.**

- f. The contractor will need to be prepared to accommodate a temporary interruption of work only for a brief period of time to allow for emergency fueling operations.
- g. The contractor will need to ensure there is a safe distance between ongoing construction activities and emergency fueling operations.

Addendum Prepared By:

Kelvin Solco, PE,
Principal



FB 22-028/JW ADDENDUM NO. 2

DATE: 8/15/2022

Addendum No. 2 - Page 4
(IFB 22-028/JW)

OWNER: Jefferson County/Jack Brooks Regional Airport

PROJECT: FB 22-028/JW Rehabilitation of Fuel Farm Pavement at Jack Brooks Regional Airport

TSG Project No: 2021-10-1092

DEADLINE FOR QUESTIONS: email questions to Jamey West, Contract Specialist at jwest@co.jefferson.tx.us by **Thursday, August 15, 2022, at 5:00 p.m.**

SUBMITTAL DEADLINE: Bid date **Wednesday, August 24, 2022, at 11:00 a.m.**, Central Standard Time.

The additions, omissions, clarifications, and corrections herein shall be made to the contract documents, plans and specifications, for the Rehabilitation of Fuel Farm Pavement Project. **All Bidders must acknowledge receipt of this addendum on the appropriate section of the Bid Form and include with the Contract Documents.**

Addendum references to answer questions posted by potential bidders are summarized below.


1. Who is responsible for Materials Testing? All quality assurance testing shall be done by the Contractor. Please see the Items below:
 - a. Item 152-5, section 152-2.10 under paragraph 2, last sentence.
 - b. Item 155-4, section 155-6.10 and a. Density Paragraph
 - c. Item 501-7, section 501-3.3 f., 501-3.4 Concrete Mix Submittal, 501-4.8 c. Consolidation, 501-4-11 e. Straightedge testing and surface correction., P-501-24 CONTRACTOR QUALITY CONTROL (CQC)
 - d. Page 8 of 61 of bid documents section 2.12.
2. DRAWING PLAN SHEET 3 – Replace Sheet 3 with New Sheet 3. Arrow for “One-Way” traffic corrected.
3. BID DOCUMENTS – Replace pg. 42 with New Page to include TOTAL BID LINE.

Addendum Prepared By:

Kelvin Solco, PE,
President / CEO

PO BOX 22001 BEAUMONT, TEXAS 77720
817-564-6895 / 833-591-5780
<https://thesolcogroup.com>





BID FORM (CONTINUED) **REPLACEMENT PAGE 42**

DESCRIPTION:	☒ Base Bid			
REF. NO. 14	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times Unit Price)
Biodegradable Erosion Control Logs (Install) TXDOT 506-6.6.1	200	LF		

DESCRIPTION:	☒ Base Bid			
REF. NO. 15	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times Unit Price)
Biodegradable Erosion Control Logs (Removal) TXDOT 506-6.6.2	200	LF		

DESCRIPTION:	☒ Base Bid			
REF. NO. 16	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times Unit Price)
4" Concrete Curb TXDOT 529	278	LF		

DESCRIPTION:	☒ Base Bid			
REF. NO. 17	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times Unit Price)
Furnish and Install 4' Steel Bollards	2	EA		

DESCRIPTION:	☒ Base Bid			
REF. NO. 18	QUANTITY:	UNIT OF MEASURE:	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times Unit Price)
Install 6' Rubber Speed Bumps	4	EA		

DESCRIPTION:	☒ Base Bid			
	TOTAL BID PRICE (\$ XXX,XXX.XX)			
TOTAL BID				

REQUIRED FORM

Bidder: Please complete this form
and include with bid submission.

BIDDER ACKNOWLEDGEMENT OF BID ADDENDA (IF APPLICABLE):

Addendum 1 _____ Date Received _____

Addendum 2 _____ Date Received _____

Addendum 3 _____ Date Received _____

Addendum 4 _____ Date Received _____

Addendum 5 _____ Date Received _____